/ UTAH OIL AND GAS C	ONSERVATION COMMISSION
REMARKS: WELL LOG ELECTRIC LOGS FILE X = WATER SANI	DS LOCATION INSP
alocal Command talocalon PA. O. alo-	
9/01913 PANEMENTIAL STATIS ENDICED &	20-10-96
100 115 WIGHT WARTING STIFT WE CAN INCOME	
DATE FILED . DECEMBER 20, 1994	
LAND: FEE & PATENTED STATE LEASE NO.	PUBLIC LEASE NO. U-44426 INDIAN
DRILLING APPROVED: MARCH 7, 1995	
SPUDDED IN: F-QH-QF	
COMPLETED: 8 - 10 - 95 COW PUT TO PRODUCING:	
INITIAL PRODUCTION:	
GRAVITY A.P.I.	
GOR:	
PRODUCING ZONES: 4784-5114' (SR)	
TOTAL DEPTH:	
WELL ELEVATION: 57H3 (JR	•
DATE ABANDONED:	
FIELD: MONUMENT BUTTE FIELD	
UNIT: JONAH UNIT	
COUNTY: DUCHESNE	
WELL NO. MONUMENT BUTTE FEDERAL #11-	7J API NO. 43-013-31492
LOCATION 681 FNL FT. FROM (N) (S) LINE, 447 FWL	FT. FROM (E) (W) LINE. NW NW 1/4 - 1/4 SEC. 7
TWP. RGE. SEC. OPERATOR	TWP. RGE. SEC. OPERATOR
	9S 17E 7 EQUIT RES ENERGY CO

Form 3160-3 (November 1983) (formerly 9-331C)

UNITED STATES DEPARTMENT OF THE INTER

SUBMIT RIPLICATE (Other detions on reverse side)

Form approved.
Budget Bureau No. 1004-0136
Expires August 31, 1985

	DEPAR'	TMENT	OF THE I	NTER	llOR	سالحما احمالت	الحيا اطلعاسات	5. LEASE DESIGNATIO	
			LAND MANAG					l	N AND BERIAL NO.
APPLICATION					#14.0 BAR	DILIC	DACK	6. IF INDIAN, ALLOTT	TE OR TRIBE NAME
1a. TYPE OF WORK	TON FE	VIAIII I	O DRILL, I	JEEFE	.14, OK	FLUG I	MCK	n/a	
	ILL X		DEEPEN []	PI	UG BA	ск 🗆	7. UNIT AGREEMENT	NAME
b. Tipe of Well				_				Jonah Unit	
WELL LA W	ELL	OTHER	. 		NGLE	MULTI ZONE	PLE _	8. FARM OR LEASE N	AMB
2. NAME OF OPERATOR		-	C D.	. 7	041 D			Balcron Monumer	ıt Federal
Equitable R		nergy	Company, B	aicro	ע ווט מי	1 V 1 S 1 O n		9. WELL NO.	
P.O. Box 21	•	inac M	T 50104					#11-7J 10. FIELD AND POOL,	
4. LOCATION OF WELL (R				h any S	tate requiren	ents.*)		Monument Butte	
At surface				, -		,		11. SEC., T., B., M., O	
NW NW Section	7, T9S,	R17E	681' FN	L, 44	7' FWL			AND SURVEY OR	AREA
are proposed production								Sec. 7, T9S,	R17E
14. DISTANCE IN MILES								12. COUNTY OR PARIS	H 13. STATE
Approximately		southw	vest of Myt	ion, l	Jtah			Duchesne	UTAH
15. DISTANCE FROM PROPO LOCATION TO NEARES:	r			16. NO	OF ACRES 1	N LEASE		OF ACRES ASSIGNED HIS WELL	
PROPERTY OR LEASE I	g. unit line, if a								
18. DISTANCE FROM PROF TO NEAREST WELL, D	RILLING, COMPL	ETED,			700 '	H	1	BY OR CABLE TOOLS	
OR APPLIED FOR, ON TH		D eta \)),	700		I KC	tary	
GL 5343.2		114 cm.)						3/1/95	VORE WILL BIRKT
23.	• •	· D1	DODOTED GASIN		OFILEMANINA	IC PROCE	436	7 3/1/33	
	·	, F1	ROPOSED CASIN	NG ANL			лм 		· · · · · · · · · · · · · · · · · · ·
SIZE OF HOLE	SIZE OF CA	ABING	WEIGHT PER FO	00T	BETTING	DEPTH	-	QUANTITY OF CEM	ENT
	TT 11011 0	, , , , , . .	70		D .		-		
	tr n. n.	ıııng	Program/Ca	<u>sing</u>	<u>vesign</u>		-		
	1	; ;							
Onerator in	tands to	drill t	hic wall i	n acc	rordance	with t	he atta	ched permit.	A listing
of EXHIBITS					, or warre		,,,,	i i	74 1100111g
						_	_	•	
SELF CERTIFICATIO									
operations associa									
being provided by surety under BLM									
with all of the t									
Midiali of ale o	cinb and cor	arcions	or alac por ci	1011 01	aic icusc	. 45500.4	cca man	uns apprication	•
•									
		-							
IN ABOVE SPACE DESCRIBE									
zone. If proposal is to preventer program, if an		directional	ly, give pertinent	data o	n subsurface	locations a	nd measure	d and true vertical der	ths. Give blowout
24.	0	··			20122408	y and			
Soblet	e XChu	Man			egulator Environm		Snecial	ist DATE 12-	19-94
Bobbie	Schuman								entage of a grander
(This space for Fede		•				AF	BROVE	DAY THE'S	TATE
PERMIT NO. 43	-013-31	492	,	/	APPROVAY/DA	·· <u> </u>	95/U//	A MASION	OF.
	EN)	#//	111	Yn.	taston	m 55	GA RELECTION	S, AND MIN	NGy lor
APPROVED BY CONDITIONS OF APPROV	AL. IF ANY	M	TIT		THE WALL	- 3A		DATE	
TOTAL OF ALLEVI	7.					BY:			
							_L SPA	CING	
						ا سنة ال	UI /\	VIIVU	

ГОПМ 3		ITE OF UTAH DIL, GAS AND MININ	G			
	Division of	TE, CAO AND MININ		IAL	5. Lease Designation and Strederal #U-444	
APPLI	CATION FOR PE	RMIT TO DRILL	OR DEEPEN		e. If Indian, Allottee or Tribe	Name:
1A. Type of Work:	7. Unit Agreement Name: Jonah Unit					
B. Type of Well: OIL	GAS OTHER:	SINGLE	ZONE MULTIPLE ZO	ONE 🗌	8. Farm or Lease Name: Balcron Monument	Federal
2. Name of Operator: Equitable Re:	sources Energy Co	mpany, Balcron ()il Division		9. Well Number: #11-7J	······································
3. Address and Telephone Num P.O. Box 210	ber 17; Billings, MT	59104 (40	06) 259-7860		10. Field and Pool, or Wilde Monument Butte/Gr	een River
Location of Well (Footages) At Surface: NW NW S At Proposed Producing Zone:	Section 7, T9S, R	17E 681' FNL	, 447' FWL		11. Otr/Otr, Section, Towns!	
	for from nearest town or post office: 13 miles southwe		.h	7.2	12. County: Duchesne	13. State: UTAH
15. Distance to nearest property or lease line (feet):	**************************************	16. Number of acres in lease		17. Numb	per of acres assigned to this we	ll:
18. Distance to nearest well, dri completed, or applied for, o	=	19. Proposed Depth:	5,700'	1	ny or cable tools: Rotary	
21. Elevations (show whether Diggs 5343.21	F, RT, GR, etc.):				22. Approximate date work 3/1/95	will start:
23.	PROP	OSED CASING AND	CEMENTING PRO	GRAM		
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT		
See EXHIBIT	"D" Drilling Pro	gram/Casing Desi	gn		· · · · · · · · · · · · · · · · · · ·	
subsurface locations and measure Operator int	M: If proposal is to deepen, give da ed and true vertical depths. Give blo cends to drill the for Permit to Dr	owout preventer program, Hany. is well in accor				give pertinent data o
Name & Signature: BOO	blie Schuma bie Schuman	<i>In</i>	Regulato THO: Environ		U BY THE STA	12-19-94
a space for State use only) API Number Assigned:	3-013-31492		Approva: Approva	TOTAL TOTAL	AH DIVISION O S. AND MININ LIGHT	= '

T9S, R17E, S.L.B.&M.

N89°55'E - 78.50 (G.L.O.) (G.L.O.)

WELL LOCATION: BALCRON MONUMENT FEDERAL #11—7J

Basis of Measured ELEV. UNGRADED GROUND = 5343.2' 0. 0 0 NORTH 2642 (G.L.O.) NORTH

N89°52'E - 78.50 (G.L.O.)



earings

 $\tilde{\omega}$

= SECTION CORNERS LOCATED

BASIS OF BEARINGS; G.L.O. DATED 1909

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SE)

EQUITABLE RESOURCES ENERGY CO.

WELL LOCATION, BALCRON MONUMENT FEDERAL #11-7, LOCATED AS SHOWN IN THE NW 1/4 NW 1/4 OF SECTION 7, T9S, R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



(G.L.O.

THIS IS TO CERTIFY THAT THE ABOYE PLATEWAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE DEST OF MY KNOWLEDGE AND BELLEFF GENE

REGISTERED LAND SURVEYOR REGISTRATION No. 144102

TRI STATE LAND SURVEYING & CONSULTING

38 EAST 100 NORTH, VERNAL, UTAH 84078 (801) 781-2501

<u> </u>	
SCALE: 1" = 1000'	SURVEYED BY: S.S. J.S.
DATE: 11-8-94	WEATHER: COLD
NOTES:	FILE #11-7J



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

December 19, 1994

-- VIA FEDERAL EXPRESS --

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

Enclosed are Applications for Permit to Drill the wells on the enclosed list.

As operator, we hereby request that the status of this well be held tight for the maximum period allowed by Federal and State regulations.

Archeology and palentology surveys have been ordered and reports will be sent to you as soon as they are complete.

Sincerely,

Bobbie Schuman

Regulatory and Environmental Specialist

1994

OV OF OIL, **gas & Mini**ng

/hs

Enclosures

cc: Utah Division of Oil, Gas and Mining

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

	==.=	01-1 07 10 7 11 1D 17 11 11 11	1140			
				TIAL	5. Lease Designation and Federal #U-44	Serial Number: 426
APPI	LICATION FOR PE	RMIT TO DRILL	OR DEEPEN		6. If Indian, Allottee or Trib	e Name:
1A. Type of Work:	7. Unit Agreement Name: Jonah Unit					
B. Type of Well: OIL	ĞAS ☐ OTHER:	SINGL	E ZONE MULTIPLE	ZONE 🗌	8. Farm or Lease Name: Balcron Monument	Federal
2. Name of Operator: Equitable Re	esources Energy Co	mpany, Balcron	Oil Division		9. Well Number: #11-7J	reactar
3. Address and Telephone Nu			106) 259-7860		10. Field and Pool, or Wild Monument Butte/Gi	cat: reen River
4. Location of Well (Footages) At Surface: NILL NILL					11. Otr/Otr, Section, Towns	
At Proposed Producing Zone	Section 7, T9S, R:	1/E 681 FN	L, 447' FWL		NW NW 7, T9S,	R17E
	ction from nearest town or post office: 13 miles southwes	st of Myton, Ut	ah		12. County:	13. State:
15. Distance to nearest property or lease line (feet)		16. Number of acres in leas		17. Numbe	Duchesne or of acres assigned to this we	<u> </u> :
Distance to nearest well, dr completed, or applied for, or		19. Proposed Depth:	5,700'		or cable tools:	
21. Elevations (show whether D	OF, RT, GR, etc.):				22. Approximate date work 3/1/95	will start:
23.		SED CASING AND	CEMENTING PRO	GRAM		
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH		QUANTITY OF CEMEN	τ
See EXHIBIT	"D" Drilling Prog	ram/Casing Desi	gn		·	
Operator int	M: If proposal is to deepen, give data and true vertical depths. Give blow cends to drill this for Permit to Dri	s well in accor				give pertinent data or
			2 0 1994			
24		_	SION OF S & MININO		-	
24. Name & Signature: BOD BOD	laie Schuman Die Schuman		Regulator		ecialist Date:	12-19-94
s space for State use only)						
API Number Assigned:		_	Approval:			

Approval:

Form 3160-3 (November 1983) (formerly 9-331C)

UNITED STATES DEPARTMENT OF THE INTER

SUBMIT RIPLICATE (Other ctions on reverse side)


Form approved.
Budget Bureau No. 1004-0136
Expires August 31, 1985

	BL		LAND MANA		L '			MAI	5. LEASE DESIGNATIO	N AND BERIAL NO.
APPLICAT	TION FOR I				the state of	DI I			• U-44426 6. IF INDIAN, ALLOTT	ER OR TRIBE NAME
1a. TYPE OF WORK		LIVIAIII I	O DIVILL, I	/ LLI	LIN, OF	· rec	<u>д</u>	ACK	n/a	*
	DRILL 🗓		DEEPEN (•	PLUG	BAC	Ж 🔲 📗	7. UNIT AGREEMENT	NAME
b. Tipe of Well	GAS [8	INGLE []	MULTIPI		Jonah Unit	
WELL 2. NAME OF OPERAT	OR WELL	OTHER	 		ONE L		ZONE		_	
Eguitab1	e Resources	Energy	Company, B	alcr	on Oil	Divis	sion		Balcron Monumer	it rederal
3. ADDRESS OF OPER	ATOR ,								#11-7J	
	21017; Bil								10. FIELD AND POOL,	
4. LOCATION OF WEI	LL (Report locatio	n clearly and	in accordance wit	h any i	State requir	rements.	.•)		Monument Butte	
NW NW Sect	ion 7, T9S	, R17E	681' FN	L. 4	47' FWL	_			11. SEC., T., R., M., OI AND SURVEY OR	R BLK. AREA
At proposed pro	u. sone			-, .					Sec. 7, T9S,	R17F
14. DISTANCE IN M							· · · · · ·		12. COUNTY OR PARIS	
	cely 13 mile	es south	west of Myt	on,	Utah				Duchesne	UTAH
15. DISTANCE FROM LOCATION TO NE	AREST			16. N	O. OF ACRE	IN LEA	ASE		F ACRES ASSIGNED	
	it drig, unit line, i									
18. DISTANCE FROM TO NEAREST WE	PROPOSED LOCATION OF THIS LEASE, PT.	ON* PLETED,			700 °	РТН		l	T OR CABLE TOOLS	
21. ELEVATIONS (Sho		GR. etc.)		5	, 700			ко	tary	
	13.2'	, 414, 444,							3/1/95	VORE WILL START-
23.		· P	ROPOSED CASIN	G ANI	CEMENT	TING PI	ROGRA	<u></u>	1 0/2/30	
SIZE OF HOLE	9179 04	CABING			,					
3.02 07 11,000	- 3.22 0	CABINO	WEIGHT PER FO	-	8277	NG DEPT	н		QUANTITY OF CEM	ENT
See EX	HIBIT "D" [rilling	Program/Ca	sina	Design)		· · · · · · · · · · · · · · · · · · ·		
		Bulling		21119	<u>DC3191</u>	<u>' </u>				
of EXHIB	ITS is also ATION: I here	attache by certify	ed. v that I am au	ıthori:	zed, by	proper	· leas	e interes	ched permit.	duct these
being provided surety under 1	d by Equitable BLM Bond No. M	Resources 17 0576 (Na	s Energy Compa ationwide Oil	iny as & Gas	princip Bond #5	al and 547188	l Safe 3) who	co Insura will be	for lease activence Company of a responsible for this application	America as compliance
in above space descende. If proposal is preventer program,	s to drill or deep	ROGRAM: If pen directional	ly, give pertinent	data o	egulato	ory a	nd	esent produ d measured	active sone and proposed and true vertical dep	ths. Give blowout
(This space for	Federal or State	office use)								
PERNIT NO.	·				APPROVAL	DATE				·
APPROVED BY	PROVAL. IF ANY:			LE					DATE	

T9S, R17E, S.L.B.&M.

N89'55'E - 78.50 (G.L.O.) (G.L.O.)

WELL LOCATION: BALCRON MONUMENT FEDERAL #11-7J



N89'52'E - 78.50 (G.L.O.)



Bearings


= SECTION CORNERS LOCATED

BASIS OF BEARINGS; G.L.O. DATED 1909

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SE)

EQUITABLE RESOURCES ENERGY CO.

WELL LOCATION, BALCRON MONUMENT FEDERAL #11-7, LOCATED AS SHOWN IN THE NW 1/4 NW 1/4 OF SECTION 7, T9S, R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT T PREPARED FROM FIELD NOTE MADE BY ME OR UNDERPINE THE SAME ARE TRUE AND CA MY KNOWLEDGE AND

REGISTRATION No.

TRI STATE LAND SURVE

38 EAST 100 NORTH, VERNAL, UTAH 84078 (801) 781-2501

SCALE: 1" = 1000'	SURVEYED BY: S.S. J.S.
DATE: 11-8-94	WEATHER: COLD
NOTES:	FILE #11-7J

Balcron Monument Federal #41-12J NE NE Section 12, T9S, R16E Duchesne County, Utah 395' FNL, 476' FEL Field: Monument Butte (Jonah Unit) FLS #U-44426 (Green River formation) 5,750' PTD: GL: 5457.6' Balcron Monument Federal #42-12J SE NE Section 12, T9S, R16E Duchesne County, Utah 2550' FNL, 391' FEL Field: Monument Butte (Jonah Unit) FLS #U-035521 (Green River formation) PTD: 5,700' 5474.4' GL:

Balcron Monument Federal #12-14J
SW NW Section 14, T9S, R16E
Duchesne County, Utah
2004' FNL, 658' FWL
Field: Monument Butte (Jonah Unit)
FLS #U-096547
PTD: 5,600' (Green River formation)
GL: 5605.2'

Balcron Monument Federal #22-14J
SE NW Section 14, T9S, R16E
Duchesne County, Utah
2134' FNL, 2198' FWL
Field: Monument Butte (Jonah Unit)
FLS #U-096547
PTD: 5,600' (Green River formation)
GL: 5594.3'

Balcron Monument Federal #32-14J
SW NE Section 14, T9S, R16E
Duchesne County, Utah
1980' FNL, 1980' FEL
Field: Monument Butte (Jonah Unit)
FLS #U-096547
PTD: 5,600' (Green River formation)
GL: 5572'

Balcron Monument Federal #42-14J
SE NE Section 14, T9S, R16E
Duchesne County, Utah
1882' FNL, 773' FEL
Field: Monument Butte (Jonah Unit)
FLS #U-096550
PTD: 5,650' (Green River formation)
GL: 5604.9'

Balcron Monument Federal #11-7J NW NW Section 7, T9S, R17E Duchesne County, Utah 681' FNL, 447' FWL

Field: Monument Butte (Jonah Unit)

FLS #U-44426

PTD: 5,700' (Green River formation)

GL: 5343.2'

Balcron Monument Federal #12-7J

SW NW Section 7, T9S, R17E

Duchesne County, Utah 1965' FNL, 620' FWL

Field: Monument Butte (Jonah Unit)

FLS #U-44426

PTD: 5,600' (Green River formation)

GL: 5338.2'

NOTE: This location has already been built. It was formerly

the Alta #7E location, built but not drilled.

EXHIBITS

A	PROPODED DEIDELING IMOGRAE.
В	PROPOSED SURFACE USE PROGRAM
С	GEOLOGIC PROGNOSIS
D	DRILLING PROGRAM/CASING DESIGN/WELLBORE DIAGRAM
E	HAZMAT DECLARATION
F	EXISTING & PLANNED ACCESS ROADS (MAPS A & B)
G	WELLSITE LAYOUT
Н	BOPE SCHEMATIC
I	EXISTING ROADS (MAP C)
J	PROPOSED PRODUCTION FACILITY DIAGRAM
K	SURVEY PLAT
L	LAYOUT/CUT & FILL DIAGRAM

11/2/94

CONFIDENTIAL

AS OPERATOR, WE HEREBY REQUEST THAT THE STATUS OF THIS WELL BE HELD TIGHT FOR THE MAXIMUM PERIOD ALLOWED BY FEDERAL AND STATE REGULATIONS.

Equitable Resources Energy Company
Balcron Oil Division
P.O. Box 21017
Billings, MT 59104
(406) 259-7860

EXHIBIT "A"
Proposed Drilling Program
Page 1

EQUITABLE RESOURCES ENERGY COMPANY Balcron Oil Division Jonah Unit Balcron Monument Federal #11-7J NW NW Section 7, T9S, R17E Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162-3.1 (d):

1. ESTIMATED IMPORTANT GEOLOGICAL MARKERS:

See Geologic Prognosis (EXHIBIT "C")

2. ESTIMATED DEPTHS OF ANTICIPATED OIL, GAS OR WATER:

See Geologic Prognosis (EXHIBIT "C")

3. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

- a. EXHIBIT "H" is a schematic of the BOP equipment and choke manifold. A 2M system will be used. The BOPE will be installed after setting 8-5/8" casing at 260'. The blind rams and pipe rams will be tested to 1500 psi. Pipe rams will be operationally checked each 24-hour period and blind rams each time pipe is pulled out of the hole.
- b. The BOPE will be tested to 1500 psi when initially installed, whenever any seal subject to test pressure is broken, and following related repairs. The pipe and blind rams will be activated at least weekly and on every trip the pipe and blind rams will be activated.
- c. An accumulator of sufficient capacity to open the hydraulically-controlled choke valve lines (if so equipped), close all rams, and retain a minimum of 200 psi above precharge on the closing manifold without the use of the closing unit pumps will be installed during the drilling of this well.
- d. An upper kelly cock will be used during the drilling of this well.
- e. Visual mud monitoring equipment will be used to detect volume changes indicating loss or gain in circulating fluid volume.
- f. Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control.

4. PROPOSED CASING AND CEMENTING PROGRAM:

- a. Surface casing will be set in the Uinta formation to approximately 260' and cemented to surface.
- b. All potentially productive hydrocarbon zones will be isolated.

EXHIT "A"
Proposed Drilling Program
Page 2

- c. Casing designs are based on factors of burst: 1.25, collapse: 1.125, and joint strength: 1.8.
- d. All casing strings will be pressure tested to 0.22 psi/ft. of casing string length or 1500 psi whichever is greater (not to exceed 70% of yield).
- E. For details of casing, cement program, drilling fluid program, and proposed mud program, see the following attachment:

Drilling Program/Casing Design (EXHIBIT "D")

5. HAZARDOUS PRESSURES, TEMPERATURES, FLUIDS/GASSES EXPECTED:

- a. Expected bottom hole temperature is 125 degrees F. Expected bottom hole pressure is 1500 psi.
- b. No abnormal pressures or temperatures have been noted or reported in wells drilled to the Green River formation in this area.
- c. No dangerous levels of hydrogen sulfide, hazardous fluids, or gasses have been found, reported, or known to exist at the depth to be drilled in this well, in this area.

6. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

- a. The drilling operations for this well will begin as soon after APD approval as possible.
- b. These drilling operations should be completed within 12 days after spudding the well depending on weather and hole conditions.
- c. If the well is productive, a sundry notice and plat showing exact installed facilities will be submitted.
- d. If this well is non-productive, a sundry notice will be filed with the BLM District Office within 30 days following completion of the well for abandonment.

7. OTHER

- a. Operator requests a variance to regulations requiring a straight run blooie line.
- b. Operator requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line.

SURFACE USE PROGRAM

EQUITABLE RESOURCES ENERGY COMPANY
Balcron Oil Division
Jonah Unit
Balcron Monument Federal #11-7J
NW NW Section 7, T9S, R17E
Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162.3-1 (d):

1. EXISTING ROADS:

- a. From Myton, Utah, take Highway #40 west out of town 1.6 miles to the Sand Wash road. Go south on the Sand Wash road for approximately 9.8 miles to an intersection with the Monument Butte Gas Plant/Jonah Unit road. Turn right and continue 1.7 miles to road intersection. Turn left and proceed 0.5 miles to a dry hole marker. Follow flags 0.3 mile to location..
- b. Existing roadways need no improvements for these drilling operations.
- c. All existing roads used by these drilling operations will be maintained in the same or better condition as were existing prior to entry.
- d. See EXHIBIT "F" Maps A and B for access route.
- 2. PLANNED ACCESS ROADS: See EXHIBIT "F" Maps A & B
 - a. Length: Approximately 0.3 miles of new access road will be required.
 - b. Width: Maximum 30' overall right-of-way with an 18' running surface.
 - c. Maximum grade: < 8%
 - d. Turnouts: None
 - e. Drainage design: Low water crossing if necessary.
 - f. No culverts or bridges are necessary.
 - g. Surface materials: Any surface materials which are required will be native materials from the location and/or access site.
 - h. No gates, cattleguards, or fence cuts and/or modifications to existing facilities will be required.

- i. All travel will be confined to location and access routes.
- j. All access roads and surface disturbing activities will conform to the standards outlined in the Bureau of Land Management and Forest Service publication: <u>Surface Operating Standards for Oil and Gas Exploration and Development</u>, (1989).

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. This shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed safe road. If necessary prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Road drainage crossings will be of the typical dry creek draining crossing type. Crossings, if necessary, will be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading will not be done during muddy conditions. Should mud holes develop, they will be filled in and detours around them will be avoided.

k. If a right-of-way is needed for access, please consider this Application for Permit to Drill as the application for rightof-way.

3. LOCATION OF EXISTING WELLS:

See EXHIBIT "I" Map C.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

- a. Upon completion, a sundry notice and plat showing exact production facilities will be submitted.
- b. All above-ground facilities will be painted earthtone color Desert Brown #10Y/R in accordance with the Munsell Soil Color chart within six months of the well completion unless prior written approval to proceed with another alternative has been granted via Sundry Notice.
- c. See EXHIBIT "J" for the Proposed Production Facility Diagram.

5. LOCATION AND TYPE OF WATER SUPPLY:

- a. The drilling water source will be obtained from a private source owned by Joe Shields.
- b. The drilling water will be hauled by truck to the location site.

6. CONSTRUCTION ROAD/LOCATION MATERIALS:

- a. Any construction materials which are required will be native materials from the location and/or access site.
- b. All construction materials for this location site and access road shall be borrowed material accumulated during the construction of the site and road. No additional construction material from other sources is anticipated at this time. If additional construction material is needed, it will be from an approved source.
- c. Reasonable precautions will be taken to protect all lands.

7. METHODS FOR HANDLING WASTE MATERIALS AND DISPOSAL:

- a. Garbage will be stored in a dumpster and disposed of according to local and state regulations, at an approved facility. Disposal will not be allowed on location. No trash will be disposed of in the reserve pit.
- b. Fluids produced during the completion operation will be collected in test tanks. Any spills of oil, gas, salt water or other noxious fluids will be cleaned up and hauled to an approved disposal site. Burning will not be allowed.
- c. The reserve pit will be lined. If a plastic nylon reinforced liner is used, it will be torn and perforated before backfilling of the reserve pit.
- d. Saltwater or testing tanks will be located and/or diked so that any spilled fluids will flow into the reserve pit. Saltwater tanks will not be placed on topsoil stockpiles.
- e. Any produced water will be contained on site for a period not to exceed 90 days.
- f. Sewage will be disposed of according to county and state requirements. Sealed chemical portable toilets will be on location during these drilling operations. Waste and chemicals will not be disposed of on location.
- q. Cuttings will be deposited in the reserve pit.

8. ANCILLARY FACILITIES:

None anticipated.

9. LOCATION SITE LAYOUT:

a. The proposed location site and elevation plat is shown on EXHIBIT "K".

- b. The drill pad layout, showing elevations, orientation, and access to the pad is shown on EXHIBIT "L".
- c. The drilling rig facilities layout is shown on EXHIBIT "G". No permanent living facilities are planned. There will be two or three trailers on location during drilling operations.
- d. The reserve pit and the blooie pit will be constructed as a combination pit capable of holding 12,000 bbls of fluid. The size of the pit will be approximately equivalent to four times the TD hole volume. The blooie pit might be used for testing, but only after the drilling is completed and the drilling equipment and personnel are off the location.
- e. The reserve pit will be located on the West side of the location.
- f. If needed, flare pit will be located downwind of the prevailing wind directions a minimum of 100' from the wellhead and 30' from the reserve pit fence.
- g. Stockpiled topsoil (first 6 inches) will be stored on the North side between corners 7 and 8.
- h. Access to the wellpad will be from the North near corner 6.
- i. The east corner (#2) of the pad will be rounded off to avoid the drainage.
- j. The reserve pit will be constructed long and narrow for topographic reasons.
- k. All pits will be fenced according to the following minimum standards:
 - a. 39-inch net wire will be used with at least one strand of barbed wire on top of the net wire unless pipe or some type of reinforcement rod is attached to the top of the entire fence.
 - b. The net wire shall be no more than 2 inches above the ground. If barbed wire it shall be 3 inches above the net wire. Total height of fence will be at least 42 inches.
 - c. Corner posts will be cemented and/or braced in such a manner to keep the fence tight at all times. Standard steel, wood, or pipe posts will be used between the cornerbraces. Maximum distance between any two posts will be no greater than 16'.
 - d. All wire will be stretched before it is attached to the corner posts.

The reserve pit will be fenced on three sides during drilling operations and on the fourth side when the rig moves off locations. Pits will be fenced and maintained until clean-up.

1. The east side of the location will be pulled in as much as possible when constructing the location to avoid a drainage.

10. PLANS FOR RECLAMATION OF LOCATION SITE:

The BLM will be contacted prior to commencement of any reclamation operations.

Producing location:

- a. Immediately upon well completion, the location and surrounding areas will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.
- b. Immediately upon well completion, any hydrocarbons in the pit will be removed in accordance with 43 CFR 3162.7-1.
- c. If a plastic nylon reinforced liner is used, it will be torn and perforated before backfilling of the reserve pit.
- d. The reserve pit and that portion of the location not needed for production facilities or operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 120 days from the date of well completion. Before any dirt work takes place, the reserve pit will have all fluids and hydrocarbons removed and all trash will be removed.

Dry hole/abandoned location:

At such time as the well is plugged and abandoned, operator will submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP:

Bureau of Land Management Vernal District Office 170 South 500 East Vernal, UT 84078

12. OTHER INFORMATION:

- a. An Archeology Survey will be provided as soon as it is completed.
- b. If unexpected cultural resources are observed during construction or reclamation operations, Equitable Resources Energy Company's Balcron Oil division will suspend operations in the vicinity of the discovery and immediately report the finding to the BLM District Office.

- c. Operator will have on site a copy of the Surface Use Program and a copy of the supplemental conditions.
- d. Drilling operations will be conducted in accordance with the Bureau of Land Management conditions of approval when received.
- e. If needed, instructions regarding a silt catchment dam being constructed will be provided for in the Conditions of Approval.

13. OPERATOR'S REPRESENTATIVES:

Equitable Resources Energy Company, Balcron Oil Division 1601 Lewis Avenue P.O. Box 21017 Billings, Montana 59104 (8:00 a.m. to 5:00 p.m.) (406) 259-7860 FAX: (406) 245-1361

Dave McCoskery, Operations Manager Home: (406) 248-3864

Mobile: (406) 698-3732

Dale Griffin, Operations Supervisor Mobile: (801) 828-7291

Home: (801) 781-1018

14. CERTIFICATION:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that any statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Equitable Resources Energy Company's Balcron Oil Division and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Date 19, 1994

Bobbie Schuman

Regulatory and I

and Environmental

Specialist

Equitable Resources Energy

Company, Balcron Oil Division



Well Name BALCRON	MONUMENT FE	EDERAL #11-7	J	Exploratory		Control Well_	BMF #44-1J
Location NW NW SI	ECTION 7-T9S-R1	7E, 681' FNL	,447' FWL D	evelopment	X	Operator	EREC
County DUCHESN					JONAH UNIT		5382
State UTAH					NW NW 7		SE SE 1
Total Depth 5700					98		
GL (Ung) 5343.2	EST. KB	5352		_	17E	·	
02 (016)	LOT. ND.	3302	-	Kange		Range_	10E
Formation Tops	_	nosis	Samp	-	Control Well	High/Low	
Formation	Depth	Datum	Depth	Datum	Datum	Prog Cntl	Deviation
UINTAH	SURFACE						
GREEN RIVER	1470	3882			3882		
HORSEBENCH SS	2168	3184			3184		
2ND GARDEN GULCH	3818	1534			1534		
YELLOW MARKER	4446	906			906		
DOUGLAS CREEK R-1 SAND (PAY)	4604	748			748		· · · · · · · · · · · · · · · · · · ·
R-5 SAND (PAY)	4643 4808	709			709		
2ND DOUGLAS CREEK	4851	544 501			544 501		
G-1 SAND (PAY)	4941	411			501		
GREEN MARKER	5000	352			411 352		
G-4 SAND (PAY)	5152	200			200		
CARBONATE MARKER	5457	-105			-105		
B-1 SAND (PAY)	5487	-135			NP .		
TD	5700						
		.,w.					
							
							· · · · · · · · · · · · · · · · · · ·
							
							- · · · · · · · · · · · · · · · · · · ·
Samples		DST,s			Wellsite Geo	ologist	
50' FROM 1400' TO 3900'	· · · · · · · · · · · · · · · · · · ·	DST #1			Name:		··
30' FROM 3900' TO TD	· · · · · · · · · · · · · · · · · · ·	DST #2			From:	to:	
5' THROUGH EXPECTED I	PAYS	DST #3			Address:		
5' THROUGH DRILLING B	REAKS	DST #4					
					Phone #		wk.
Logs		Cores			•		hm.
DLL FROM SURF CSG TO		Core #1	NONE		Fav #		Tilli.
LDT/CNL FROM 3500' TO			ITOITE				
EDITCHE PROM 3500 TO	10	Core #2	*****		N.C. 1 T	/TT - TA7*	
			· · · · · · · · · · · · · · · · · · ·		Mud Logger		
		Core #4			Company:		
					Required:	(Yes/No) \underline{Y}	ES
					Type:	TWO MAN	
Comments:							
				-	Fax #		
Report To: 1st Nam	O. DAVE DICIZED	CT A DD	Dh #	(406)250 5060	-		1
the state of the s			_	(406)259-7860 "		245-2261	hm.
	e: KEVEN REINS		Phone #_	 		248-7026	hm.
Prepared By: K.K. REINS	CHMIDT	12/13/94	Phone #		wk.		hm

Equitable Resources Energy Company Balcron Oil Division

EXHIBIT "D" Page 1 of 2

DRILLING PROGRAM

WELL NAME: Balcron Monument Fed. 11-7J PROSPECT/FIELD: Jonah Unit

LOCATION: NW NW Sec.7 Twn.98 Rge.17E

COUNTY: Duchesne STATE: Utah

TOTAL DEPTH: 5700

HOLE SIZE INTERVAL

12 1/4" 0 to 260'
7 7/8" 260 to T.D.

CASING	INTERVAL	Casing
=======================================		

STRING TYPE	FROM	TO	8]	ZE	WEIGHT	GRADE
Surface Casing Production Casing	0 0	260 T.D. asing wi	8 5	5/8" 1/2"	24 #/Ft 15.50#/Ft	J-55

CEMENT PROGRAM

Surface 150 sacks 75% Class "G" 25% Poz with 2% CaCl and 1/4 #/Sk Flocele.

(Cement will be circulated to surface.)

Production

180 sacks Western Super G consisting of 47 #/sk G, 20 #/sk Poz A, 17 #/sk CSE, 3% salt, 2% gel, and 2 #/sk Hi-Seal. (Yield=2.76 Cu.Ft./sk Weight=11.08 PPG) Tailed with 300 sacks 50-50 Poz with 2% gel, 1/4 #/sk Cello-seal and 2 #/sk Hi-seal.Yield=1.24 Cu.Ft./sk Weight=14.30 PPG) a.) Actual cement volume will be determined from caliper log.

b.) Actual cement top will be specified in conditions of approval.

PRELIMINARY DRILLING FLUID PROGRAM

TYPE	FROM	то	WEIGHT	PLAS. VIS	YIELD POINT
Air and air mist	0	260	N.A.	N.A.	N.A.
Air/Air Mist/KCl Water	260	T.D.	8.7-8.9	N.A.	N.A.

Depending on the drilling contractor either:

- a.) Drilling will be with air and air mist from surface to as deep as hole conditions allow. 2% KCl fluid will be used for the remainder of the hole.
- b.) Drilling will be done using 2% KCl water and gel.

COMMENTS

1.) No cores or DST's are planned.

BALCRON OIL CO.

Operator: BALCRON OIL	Well Name: Monument Fed.11-7J
Project ID:	Location: Duchesne/Utah

Design Parameters:	Design Factors:	
Mud weight (8.80 ppg) : 0.457 psi/ft	Collapse : 1.1	25
Shut in surface pressure : 2036 psi	Burst : 1.0	0
Internal gradient (burst) : 0.100 psi/ft	8 Round : 1.8	(J)
Annular gradient (burst) : 0.000 psi/ft	Buttress : 1.6	0 (J)
Tensile load is determined using air weight	Body Yield : 1.5	0 (B)
Service rating is "Sweet"	Overput t	0 lbs.

	Length (feet)	Size (in.)	Weight (lb/ft)	Grade	Joint		Depth (feet)	Drift (in.)	Cost
1	5,700	5-1/2"	15.50	K-5	5 ST&C		5,700	4.825	
	Load (psi)	Collapse Strgth (psi)	S.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Load (kips)	Tension Strgth (kips)	
1	2606	4040	1.550	2606	4810	1.85	88.35	5 222	2.51 J

Prepared by : McCoskery, Billings, MT

Date : 12-16-1994

Remarks

Minimum segment length for the 5,700 foot well is 1,500 feet.

The mud gradient and bottom hole pressures (for burst) are 0.457 psi/ft and 2,606 psi, respectively.


NOTE: The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser. Costs for this design are based on a 1990 pricing model. (Version 1.0G) A. Hazardous chemicals 10,000 pounds of which will most likely be used, produced, stored, transported, or disposed of in association with the proposed action of drilling, completing and producing this well:

We anticipate that none of the hazardous chemicals in quantities of 10,000 pounds or more will be associated with these operations.

B. Extremely hazardous substances threshold quantities (per Howard Cleavinger 11/30/93) of which will be used, produced, stored, transported, or disposed of in association with the proposed action of drilling, completing and producing this well:

We anticipate that none of the extremely hazardous substances in threshold quantities per 40 CFR 355 will be associated with these operations.


12/1/93 Revised 12/7/93 /rs



EQUITABLE RESOURCES CO.

BALCRON MONUMENT FEDERAL #11-7J SECTION 7, T9S, R17E, S.L.B. &M. TOPO "A"

Tri State Land Surveying. Inc. **∆**(801) 781-2501 38 WEST 100 NORTH VERNAL, UTAH 84078




SECTION 7, T9S, R17E, S.L.B.&M. TOPO "B"

Land Surveying. Inc. **∆**(801) 781-2501


SCALE: 1" = 2000'

38 WEST 100 NORTH VERNAL, UTAH 84078


EQUITABLE RESOURCES ENERGY CO. WELLSITE LAYOUT




TRI—STATE
LIND SURVEYING, INC.
38 HS1 100 HRPH, YERH, BLAH BADE
801-781-2501





#3000__STACK___



Equipoble Resources Energy Company Balcron Monument Federal 11-7J Proposed Production Facility Diagram







APD RECEIVED: 12/20/94

API NO. ASSIGNED: 43-013-31492

WELL NAME: BALCRON MONUMENT FED 11-7J OPERATOR: EQUITABLE RESOURCES (N9890)

PROPOSED LOCATION: 17
NWNW 07 - T09S - RN6E
SURFACE: 0681-FNL-0447-FWL
BOTTOM: 0681-FNL-0447-FWL

DUCHESNE COUNTY

MONUMENT BUTTE FIELD (105)

LEASE TYPE: FED

LEASE NUMBER: U-44426

PROPOSED PRODUCING FORMATION: GRRV

INSPECT LOCA	ATION BY:	/ /
TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED: V	LOCATION AND SITING: R649-2-3. Unit:12086A R649-3-2. General. R649-3-3. Exception. Drilling Unit. Board Cause no:Date:
COMMENTS:	GSRIADEN TIAL OBENITATION NO TOTAL STATEMENT TO THE TIAL STATEM
STIPULATIONS:	
PI	FIDENTIAL ERIOD FIRED

STATE OF UTAH

Operator: EQUITABLE RESOURCES | Well Name: MONUMENT BUTTE FED.

Project ID: 43-013-31492 | Location: SEC. 7 - T09S - R17E

Design Factors: Design Parameters: : 1.125 Mud weight (8.90 ppg) : 0.462 psi/ft Collapse Shut in surface pressure : 2317 Burst : 1.00 psi : 1.80 8 Round (J) Internal gradient (burst): 0.056 psi/ft : 1.60 (J) Annular gradient (burst) : 0.000 psi/ft Ruttress : 1.50 (J) Other Tensile load is determined using buoyed weight Body Yield : 1.50 (B) Service rating is "Sweet"

	Length (feet)	Size (in.)	Weight (lb/ft)	Grade	Joir	nt	Depth (feet)	Drift (in.)	Cost
1	5,700	5.500	15.50	K-55	ST&C	2	5,700	4.825	
	Load (psi)	Collapse Strgth (psi)	S.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Load (kips)	Tension Strgth (kips)	s.F.
1	2635	4040	1.533	2635	4810	1.83	76.33	3 222	2.91 J

Prepared by: KMH, Salt Lake City, UT

Date : 03-07-1995

Remarks :

Minimum segment length for the 5,700 foot well is 1,000 feet.

SICP is based on the ideal gas law, a gas gravity of 0.69, and a mean gas temperature of 102°F (Surface 74°F, BHT 131°F & temp. gradient 1.000°/100 ft.)

The mud gradient and bottom hole pressures (for burst) are 0.462 psi/ft and 2,635 psi, respectively.

NOTE: The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser. Costs for this design are based on a 1987 pricing model. (Version 1.06)

:		:			ø	:	ø			Y			
		,	И			. :		ø	*				
			e s		K			ŕ			*	T 8 S	•
	·ABLE RE	ESOUF	RCES	EN	ER	GY	,	•			•	T9 S	,
	ON MOI	NUME	NT BU	JTT	E						•	• ø	. ø
	UNIT W				16	2 .	1 .	F	•	•	•	<i>у</i>	,
	SINE		130), i\	10	CC :	١,	-	,	•		ø *	, ,
					· • • •	· • · · ·		*	••••	÷	41-12J	● 11-7J	
•		*	•	•	•	*	•		٥		42-12J [●]	● 12-7J	
•			0	•	*	*	•	•		•		·	•
		• •		•	•		•	•					
				•			*						* *
			12-14J	22-14J	32-14J	9 2-1	ÅJ						
		•	!								Ш	Ш	٥
			•								16	17	
			1				• • •				C	2	
					•		· · ·						
	:				*								
	•						•						
	•					•	:	<i>-</i>	•	- <i></i> -			
	•				*								
							:					*	



DIVISION OF OIL, GAS AND MINING

Ted Stewart **Executive Director** James W. Carter

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) Division Director 801-538-5319 (TDD)

March 7, 1995

Equitable Resources Energy Company P.O. Box 21017 Billings, Montana 59104

Balcron Monument Federal #11-7J Well, 681' FNL, 447' FWL, NW NW, Sec. 7, Re: T. 9 S., R. 17 E., Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Admin. R. 649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-31492.

Sincerely.

Associate Director

ldc

Enclosures

Duchesne County Assessor

Bureau of Land Management, Vernal District Office

WAPD



Operator:	Equitable	Resou	rces Er	iergy Co	ompany			
Well Name	& Number:	<u>Bal</u>	cron M	orume	nt Federa	<u>#11-7</u>	J	
API Numb	er: <u>43-01</u>	3-31492						
Lease:	Federal #U-	44426						
Location:	NW NW	_ Sec	7	T	9 S.,	_ R	17 E.	

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5340.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews or Mike Hebertson at (801)538-5340.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

Form 3160-3 (November 1983)



Form approved.
Budget Bureau No. 1004-0136
Expires August 31, 1985

(Iomerly 9-331C)	DEPARTME	NT OF THE I	NTEF	RIOR			5. LEASE DEBIGNATION	ON AND BREIT WA
		OF LAND MANA		L 1 11			5. LEASE DESIGNATION U-44426	JA ARD BERIAL RO.
APPI ICATI	ON FOR PERMI	T TO DRILL	DEEDI	FN OR P	LUG P	BACK	6. IF INDIAN, ALLOT	TEE OR TRIBE NAME
1a. TYPE OF WORK		i io biliaa, i					n/a	<i>s</i>
	DRILL 🛛	DEEPEN		PLU	JG BA	CK 🗆	7. UNIT AGREEMENT	MAMB
OIL X	GAS			INGLE	MULTIP ZONE	,re [Jonah Unit 8. FARM OR LEASE 1	NAMB
2. NAME OF OPERATO	WELL OTHER	· · ·		JAE LJ	ZUNE		Balcron Monume	nt Federal
Equitable	Resources Energ	gy Company, B	alcro	on Oil Div	vision		9. WELL NO.	
3. ADDRESS OF OPERA	• • •	MT 50104					#11-7J	
	21017; Billings (Report location clearly		th any E	tate requiremen	nts.*)		Monument Butte	
At surface					·	ŀ	11. SEC., T., R., M., O	<u> </u>
NW NW Secti	on 7, T9S, R17E	681' FN	٠.					
				-013-3	1493	2	Sec. 7, T9S,	
	ely 13 miles sou						12. COUNTY OR PARIS	
15. DISTANCE FROM P	BOPUSED®	CHWC3C OF TIS		O OCT ACRES IN	LEASE		F ACRES ASSIGNED	HATU
PROPERTY OR LEA		•				TO TH	IIS WELL	
18. DISTANCE FROM			1	OPOSED DEPTH		20. ROTAB	T OR CABLE TOOLS	
OR APPLIED FOR, ON	THIS LEASE, FT.		5,	,700'		Ro	tary	
	whether DF, RT, GR, etc.)					3/1/95	WORK WILL START®
GL 534:	3.2	PROPOGER CAST		- CHIVENING	- DROCR		7 3/1/33	
		PROPOSED CASI		····		7		
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER F	00T	BETTING D	EPTH	·	QUANTITY OF CEA	IENT
Soo EVI	IIBIT "D" Drilli	ng Program/Ca	sina	Design		·		
DEE LAI		ng 11 og alli og	, <u>5,1119</u>	0001911	· · · · · · · · · · · · · · · · · · ·			
		 	ا	l 	العادية في	l balaite		A liatina
	intends to dril TS is also atta		n acc	cordance v	with t	ne alla	ched permit.	A ITSUTING
O! EVIIIDI	. 13 13 0130 0000	cheu.						
					_			
SELF CERTIFICAT	1 nereby cert	rify that I am au	uthori:	zed, by prop	per leas	e interes	st owner, to con	duct these
operations asso	ociated with the app by Equitable Resour	ncation. Bond res Energy Comp	covera anv as	age pursuam orincinal a	i w 43 and Safe	co Insura	ance Company of	America as
surety under Bl	M Bond No. MT 0576	(Nationwide 0il	& Gas	Bond #55471	188) who	will be	responsible for	compliance
with all of the	e terms and condition	ons of that port	ion of	the lease a	associat	ed with t	this application	l .
•					l Uspirir	وقاء الأهود فلمحاكمتها بقداد دينها والرابي	a top a constitute	
•						MAR I O	1995	
							· · · · · · · · · · · · · · · · · · ·	
»					. An encour	income and income	S & MINING	
N ABOVE SPACE DESC	RIBE PROPOSED PROGRAM:	If proposal is to deep	en or p	lug back, give	data on pi	resent-produ	ictive sone and propo	sed new productive
one. If proposal is reventer program, if	to drill or deepen directi any.	onally, give pertinent	i data o	n subsurface lo	eations ar	id measured	and true vertical de	pths. Give blowout
P4.	. 0.		R ₁	egulatory	and		-	
BIGNED DO	bee Schume	Ţ17	rLE	Environme	ntal S	peciali	st DATE 12-	<u>19-94</u>
(This space for F	e Schuman 'ederal or State office use)							
BB5345 NO	1 0001	1		APPROVAL DATE				
PERMIT NO.	7 / 1/1/1			-			MAR	6 1995
APPROVED BY	naid Sila	UTURS X TIT		ASSISTANT D	DISTRICT		DATE	
CONDITIONS OF APP	ROVAL, IF ANY:		*	L. Millian III	CC	ו מדוכאכ	J 0= (a see

TO OPERATORIO COPT

COA's Page 1 of 8 Well: Balcron Fed. 11-7J

CONDITIONS OF APPROVAL APPLICATION FOR PERMIT TO DRILL

Company/Operator: <u>Equitable Resources Energy Company</u>

Well Nan	ne & N	fumber: Balcron Federal 11-7J
API Num	nber: _	43-013-31492
Lease Nu	ımber:	<u>U-44426</u>
Location:	. <u>NW</u> !	NW Sec. 7 T. 9S R. 17E
]	NOTIFICATION REQUIREMENTS
Location Construction -		at least forty-eight (48) hours prior to construction of location and access roads.
Location Completion -	I	prior to moving on the drilling rig.
Spud Notice -	8	at least twenty-four (24) hours prior to spudding the well.
Casing String and - Cementing		at least twenty-four (24) hours prior to running casing and cementing all casing strings.
BOP and Related - Equipment Tests	a	at least twenty-four (24) hours prior to initiating pressure tests.
First Production - Notice		within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90)

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

days.

COA's Page 2 of 8 Well: Balcron Fed. 11-7J

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. <u>Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered</u>

Report <u>ALL</u> water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

The Vernal District Office shall be notified, at least 24 hours prior to initiating the pressure tests, in order to have a BLM representative on location during pressure testing.

COA's Page 3 of 8 Well: Balcron Fed. 11-7J

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

The surface casing will need to be cemented with neat cement.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the Usable Water zone identified at \pm 408 ft. or by extending the surface casing to \pm 458 ft. and having a cement top for the production casing at least 200 ft. above the top of The Mahogany Oil Shale Zone identified at \pm 2730 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

The Vernal District Office shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to \pm 2530 ft. if the surface casing is set at \pm 458 ft. or to the surface if the surface casing is set at \pm 260 ft. The CBL shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

COA's Page 4 of 8 Well: Balcron Fed. 11-7J

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours **prior** to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

<u>Immediate Report</u>: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

COA's Page 5 of 8 Well: Balcron Fed. 11-7J

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9. d.), and shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b. 4).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted following initial installation and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

COA's Page 6 of 8 Well: Balcron Fed. 11-7J

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Wayne P. Bankert

(801) 789-4170

Petroleum Engineer

Ed Forsman

(801) 789-7077

Petroleum Engineer

BLM FAX Machine

(801) 781-4410

COA's Page 7 of 8 Well: Balcron Fed. 11-7J

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

COA's Page 8 of 8 Well: Balcron Fed. 11-7J

SURFACE USE PLAN OF OPERATION

Conditions of Approval (COAs)

Methods for Handling Waste Disposal

The reserve pit will be lined with a plastic liner 12 mil in thickness or greater. The reserve pit will have sufficient bedding of straw or dirt to prevent the liner from being punctured. No trash or loose equipment shall enter the reserve pit.

Plans for Reclamation of Location

The reserve pit and that portion of the location not needed for production facilities or operations in addition to being recontoured to approximate natural contours will also be reseeded to the specifications of the Authorized Officer of the BLM.

At time of abandonment the intent of reclamation will be to return the disturbed area to near natural conditions. Recontour the surface of the disturbed area to blend all cuts, fills, road berms, and borrow ditches to be natural in appearance with the surrounding terrain. Stockpiled topsoil will be spread over the surface, and the area revegetated to the satisfaction of the Authorized Officer of the BLM.

Additional Surface Conditions of Approval

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362, forty-eight (48) hours prior to construction activities, including installation of the pit liner.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

A silt catchment basin shall be constructed due north of the northwest section corner to section 7 to mitigate soil erosion caused by the surface disturbance to develop this location.



DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of C	Company: <u>EQUITAB</u>	<u>LE RESOU</u>	RCES EN	ERGY		
	BALCRON MONUME					
	43-013-31492					
API NO	45 015 5145 <u>6</u>			***		_
Section	7 Township	9S	Range_	17E	County_	DUCHESNE
Drilling	Contractor	UNION				
Rig #	17					
SPUDDED:	Date 5/24/95					
	Time_7:00 PM					
	How_ROTARY					
Drilling	will commence				_	
Reported	by AL PLUNKETT				_	
Telephone	e #	-,			_	
,	- 40 4 40 5	a !		TTIM		
Date:	5/24/95	51q	ned:	${ t JLT}$		

5-30-95



BALCRON OIL DIVISION

1601 Lewis Avenue Billings, MT 59102

MAY 26 1995
DIV. OF OIL, GAS & MINING

Office: (406) 259-7860

FAX: (406) 245-1365 FAX: (406) 245-1361

May 24, 1995

Bureau of Land Management Vernal District Office 170 South 500 East Vernal, UT 84078-2799

JANIDEIMIN

Gentlemen:

RE: Balcron Monument Federal #11-7J

NW NW Section 7, T9S, R17E

Duchesne County, Utah

43-013-31492

This letter is notice that the subject well was spud on 5-23-95 at 7:00 p.m.

Please feel free to contact me if you have any questions.

Sincerely,

Molly Conrad

Operations Secretary

/mc

cc: State of Utah, Division of Oil, Gas & Mining - also enclosed is V

our Entity Action Form 6

Bobbie Schuman Dawn Schindler Lou Ann Carlson STATE OF UTAH DIVISION OF OIL, GAS AND MINING ENTITY ACTION FORM - FORM 6

Equitable Resources Energy Company OPERATOR Balcron Oil Division

OPERATOR ACCT. NO. H 9890

ADDRESS 1601 Lewis Avenue

Billings, MI 59102

(406) 259-7860

ACTION CODE	CURRENT ENTITY NO.	HEH ENTITY HO:	APT HUHDER	WELL NAME	70	SC	YELL I	OCATIO RG	COUHTY .	SPUO OATE	EFFECTIVE DATE
В	11492 —	>	43-013-31492	Balcron Monument Federal #11-7J	NW NW	7	9S	17E	Duchesne	5-23-95	5-23-95
HELL 1 C	OHMENTS:				111		n- 1)	l	<u> </u>		<u> </u>
	Spud of	fanew well	l, please add to	current Jonah Entity. Entity a a	ded =	5-2lv-1	15. Lec	_			:
	,										
HELL 2 C	OMHENTS:						· · · · · · · · · · · · · · · · · · ·	<u> </u>	, de .	<u> </u>	
									:		
WELL 3 C	OHMENTS:					-		·	·		
WELL 4 C	OHMENTS:					.1		<u> </u>	<u> </u>		
					·						
WELL 5 C	OHITEITS:			••	-1			,	L	<u> </u>	<u> </u>
ACTION C	ONES (See 1	nstructions	on back of form)						Mall	77	

A - Establish new entity for new well (single well only)


D - Add new well to existing entity (group or unit well)

C - Re-assign well from one existing entity to another existing entity

D - Re-assign well from one existing entity to a new entity

E - Other (explain in convents section)

HOTE: Use COMMENT section to explain why each Action Code was selected. (3/89)



Plione No. (406) 259-7860

GEOLOGICAL WELLSITE REPORT

Balcron Oil Company

Monument Federal No. 11-7J NWNW Sec. 7-T9S-R17E Duchesne County, Utah

> Durwood Johnson Petroleum Geologist 3118 Avenue F Billings, MT 59102 (406) 656-4872

TABLE OF CONTENTS

Location Plat	1
Data Sheet	s
Formation Tops	3
Compensated Neutron- Litho-Density	4-5
Show Report	6
Penetration Chart	7
Bit Record	8
Deviation Surveys	8
Well History	9
Sample Description	10-19
Penetration Log	In Pocket

EQUITABLE RESOURCES ENERGY CO.

WELL LOCATION, BALCRON MONUMENT FEDERAL #11-7, LOCATED AS SHOWN IN THE NW 1/4 NW 1/4 OF SECTION 7, T9S, R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLATEWAS
PREPARED FROM FIELD NOTE OF ACTUAL SORVEYS
MADE BY ME OR UNDER MY SUPERVISION AND WHAT
THE SAME ARE TRUE AND CHRECT TO THE DEST OF
MY KNOWLEDGE AND BELLEFF GENE

STEWART

REGISTERED LAND SURVEYOR
REGISTRATION No. 34102 STATE OF UTIL

TRI STATE LAND SURVEYING & CONSULTING 38 EAST 100 NORTH, VERNAL, UTAH 84078 (801) 781-2501

SCALE: 1" = 1000'	SURVEYED BY: S.S. J.S.
DATE: 11-8-94	WEATHER: COLD
NOTES:	FILE #11-7J

DATA SHEET

OPERATOR:

Balcron Oil Company

WELL NAME:

Monument Federal No. 11-7J

LOCATION:

NWNW (681'fn1-447' fwl) Section 7, Township 9 South, Range 17 East, Duchesne County, Utah

AREA:

Jonah Unit

ELEVATION:

Ground Graded 5345' KB 5355'

SPUDDED:

May 23, 1995 @ 7:00 PM

DRILLED OUT:

May 24, 1995 @ 3:00 PM

REACHED T.D.:

May 31, 1995 @ 4:00 PM

RIG RELEASE:

June 1, 1995 @ 6:00 PM

STATUS:

Oil Well

HOLE SIZE:

12½" Surface-294'; 7 7/8" 294-5700'

DRILLING FLUID:

Air and foam Surface-294'; Kcl water 294'-T.D.

SURFACE CSG.:

Ran 6 jts (264.4') 8 5/8", 24 lb, J-55 to 274' KB. Cemented w/160 sxs Class G, 2% CaCl₂, % lb/sx Cello Seal. Plug down May 24, 1995 @ 3:00

AM.

PRODUCTION CSG.: Ran 131 jts (5659.72') 5%", 15% lb, J-55 to 5669.72 KB. Cemented w/383 sxs Super G, 47 lbs/sx G, 20 lbs/sx Poz, 17 lbs/sx CFE, 3% salt, 2% gel, 2 lbs/sx HiSeal 2; % lb/sx Cello Seal. Tailed w/232 sxs 50/50 Poz, 2% gel, ½ lb/sx Cello Seal, 2 lbs/sx Hi Seal. Plug down June 1, 1995 @

2:00 PM.

DSTs

None.

CORES: None.

LOGGING:

Engineer: White Vernal, UT Schlumberger BSC-T.D. 1. Dual Laterolog w/Gr & Cal 3900-T.D. FDC-CNL w/Gr & Cal

MUD LOGGER:

Northwest Well Logging Service Vodahl, Schmoldt

CONTRACTOR:

Union Drilling Co. Rig 17 Pusher: Dave Gray

SUPERVISION:

Al Plunkett

Gillette, WY

GEOLOGIST:

Durwood Johnson

Billings, MT

FORMATION TOPS

Formation	Depth	Datum	* Reference Well
TERTIARY			
Uintah	Surface		
Green River	1452	+3903	21' High
Horsebench Sand	2154	+3201	17' High
2nd Garden Gulch	3996	+1559	25' High
Y-2 Sand	4076	+1279	
Y-4 Sand	4344	+1011	
Yellow Marker	4426	+ 929	23' High
Douglas Creek	4591	+ 764	16' High
A-5 Sand	4784	+ 571	
2nd Douglas Creek	4835	+ 520	19' High
Green Marker	4977	+ 378	26' High
G-4 Sand	5074	+ 281	
BSF	5288	+ 67	§، High
Carbonate Marker	5436	- 81	24' High
8-1 Sand	5448	- 93	
B-3 Sand	5656	- 301	
TOTAL DEPTH:			
Oriller	57001		
Schlumberger	5687'		

* Reference Well:

BFM No. 44-1J SESE Sec. 1-T9S-R16E Duchesne County, Utah


FINAL PRINT	SIMULTANEOUS COMPENSATED NEU	TPON-
Schlumberger	LITHO-DENSITY	AOIV.
COMPANY	BALCRON OIL COMPANY	
:		
WELL	BALCRON MONUMENT FEDERAL	11-7J
FIELD	JONAH UNIT	
1 - 3 3 2 1	DUCHESNE STATE UT	м
7 1 2 2 6 681 FNL 6 4	12500	Nher Services:
NW.NW	.,	ULIGR DIT LDT-GR
2 2 1	. SECT. TWP RANGE	
8 g g g g 43-013-3149	2 7 9S 17E	
Permanent Datum GROUN Log Measured From KELLY B		DF:5354 DF
Drilling Messured From KELLY E	USHING	G.L 5345 0 F
4300	2===>	
		3
	1	\$
		5 - 1
		<i>f</i> : : : : : : : : : : : : : : : : : : :
Y-4 Sand		+ 1011
50	-:555	
		= 5 = =
		<u> </u>
	=======================================	
4400	F=+==== : :	
4400		
	552 i dan da i	
		:
Yellow Marker		+929
		-3-1-
	1 1 1 1 1	
4500		
4300		
5"/100"	PREFERENCE CONTRACTOR	SETONE 12 69 GICCI
	SANU 5 31-MAY-1995 21:30	STONE (2.68 G/CC) (UP)
Main Pass	Main Pass	Main Pass
	Gas et	ect .
	1	TENS(LBF)
	Ī	0000 0000
	<u>.</u>	DRHO(G/C3) 2500 25000
	NPCR(
CALIUN 1	30000 NPCR	v.v.i
6 0000 16 000	70000	30000
GP(GAP!) 0.0 150.00	30000 DEHIO	. 1000 . 1000
0.0 150.00		

1	FII	NAL P	RINT		SI	MULTANE	ous	201	•
	Sch	dmuli	erger	CO	MPENS LITE	SATED 10-DE	NEUT	HUN-	
	,	?	COMPA	NY BALO	RON OIL				
	'	4	WELL	BALC	OM NOR	UMENT F	EDERAL 1	1-7J	
						· • · · · ·	252.74		
	- 3	3 3	FIELD		AH UNIT			. [
	1967 (1-4) 1967 (1-4)	1 1	COUNT		HESNE	STATE		er Services:	
	8 % 3	1 1	15	IL 8 447 FWL			:20.1	-GR TIDT-GR	
		1	API SERIA		SECT.	TWP.	RANGE		
	Permanen	£ 8	43-013-		7 Elev.	9 S 345 0 F	17 E	v.; K.B.5355 S ^c	
	Log Mees	ured From	m KE	LLY BUSHING		sbove Perm.		D.F.5354 0 F	
	Drifting Me	sesured I		700 TOTAL	. س. س. س. شد			G.L.5345.C?	
	-	\leq							
			5	20			Harri	···	
		شبيتر	=	2	53				
		\geq			EEE-	-			
	-		\cong					_	
==	===	=	\equiv				=======================================		
			<u> </u>			2200		- 2	
			: :		Andreas -				
		7	\sim	•==				<	
>			=	7.7				\rightarrow	
		=				23-	====	₹	
	-					====		· · · · · · · · · · · · · · · · · · ·	
						FRAS	F= -		=
		\equiv	>						
									+ 571
	2 1 2	5 Sc		800				- Z	1 3/1
		\equiv					= = =		
	15	\equiv							
	= =<	<u> </u>	==}					-: 3	
		<u> </u>	\equiv		<i>₹.</i>			5 :- :	: .:
- : :	1:	<u>:}:</u>	<u> </u>		· : : .	<u> </u>			
			<u> </u>	1-3-3					
	= 20	a D	ouglas	Creek				- S	+ 520
		\leq	:]			. مت	:	<u>: 5:</u>	
			>						
1	15	\leq				_+		در.	
	#	={	==					: : : : : : : : : : : : : : : : : : : :	
	==	=	30			-444	- نوی		
		7	===						
			5"/10	0'				TONE (2.68 G	k*CC)
CP 40 Ma	0.2 ain Pass		FILE	5		1995 21 n Pass		UP) Main Pa	
							Gas effec	t	
							100		<u>: 55 </u>
								~~~	G C3
							- 25	oc	
				<u> </u> -			- 25 NPORY/V	oc	25000
	CALIUN ) _			30000				oc	25000
5 0000	CALI(IN ) _ GR(GAPI)	 16	000	30000 70000			_ NEGATA.A	oc	25000

### SHOW REPORT

н С. Э		DRIL	L RATE	mpf .	TOTAL	L GAS u	nits	•	HROMATO	GRAPII pr	m ·	
· FM	DEPTH	before	during	after	before	peak	after	cl ·	c2	c3	c4	Remarks
2 md Garden Galch	3765-3775		1.2	. 8	8	160	20	All C.	Trace	Trace		55 Vf-fg, wht, sub a, no vis. str Traca dullyel flor, faint it yel ent. 25 V+-fg ting, it bro, a-t-
Y-4 Sand	4352-4362	3.0	1.6	3.0	2	120	14	17	.6%	.35%	.47	It orn stain, Pri yel flor, command strong white yel cot.
Ostracod Ls	4470-4474		2.0	3.0	2	20	2	AII C	Trace	Trace	Trace	15-about extravels, earthy to donce matrix-sect away to spotty stra, stryal floor food by
R-5 Sand	4792-4801		. 1.4	2.8	2	140	4	1.2%	.6%	.3%	.5%	se vig, itsing tang as etch poor par, pale to sto, boi watergal flow, alous it yak
B-1 Sand	5456-5466		2.0	3.8	8	100	6	.97	.27	.17	Trace	gra- ser, stricate, trons- gra-ber stri, fam alastos wij will yalk flos, slow cloud,
	5652-5666		2.0	3.0	4	40	2	.35%				so vify, it gry-born madeal faint yry-born-ten, otherin, dull yet flow, item cloudy w
-												
•												
÷												
					-				<del>                                     </del>			
<del></del>		-	1						1	-		
······································		-				,			-			
		+	-									

### PENETRATION CHART



MTY		<del></del> ,		FIELD	Jonah	Unit 6 R. H	STATE	to R	•	ECTION 7		TOWNS	HIP S	RANGI	7 <i>E</i>	LOCA	ATION	رري	(68	ı fn	l- 1	447	fwl)	Tederal
		esne.	Cillino UNDER INTER.	C.	onumer Rio H	o. OPERATOR	leron	Oil	 	2 m	as.	766		TOOLPU	zue	ي ا	ra	4	<u>,</u>	R	aon	_ <del>5</del> u	tters	ields. Verguso
. o . -2:	0 PM   3-95	NDER SUNF. 3:00 PM 5-24-95		SET SA	IND ST. REAC	Unit  A Butt  OPERATOR  BO PM  11-95 9.  16.60 16	no. 1 ardne	r no	nuer	ر برع ر	Y	X /4"	PUMP	NO. 2			1.0		LINER	LENGT	Tun	FOWE	7/ GMC	Hai f I H Cl (1)
L, PI	t"XH	٠.	TOOL JOINTS	64	" "	16.60 16	6	rade	E	DI CC	ILL OLLAR	s /	77		6"	,00000000000000000000000000000000000000	2	į "		\	-		34:	2 Cat
Т	SIZE	MAKE	TYPE	JET SZND IN		DEPTH OUT	FEET	HOURS	PT/HR	ACCUM DRLG. HRS.	WT. 1000 LBS.	RPM	VERT DEV.	PUMP PRESS	PUMP OPER- ATION	S F	M	WT.	MUE VIG.	W.L.			COND.	FORMAT
$\dagger$	124"	HTC	FB	OPEN		294	246	54	44.7	51/2	10	25		200						Poar	1-1			
	7 1/8		SBBCFH				3796	١.	ŧ	1	1 1	60		250				air	ŧā	6am	4	$\perp$	ļ	<del> </del>
$\int$	7 %"		ATJ-44	I	1.	· ·	1610	744	21.7	159	40	60		1075		54	-	K	e u	ater	4-	<del>                                     </del>	-	-
L								100	-	ļ	1.55	S. Carlos	-	<u> </u>		-	ļ	-			+	$\vdash$	-	-
ļ							4	59.	-	-	ļ	400	3			-	-	-		<del> </del>	+-	$\vdash$	+	
ł		_			<u> </u>	بير .	A.	-	-			710078	36.			-	-	<del>                                     </del>		-	+	$\vdash$	<del>                                     </del>	1
ł		· .		<del> </del>		and the second		33 Pres	7.7.44		7.00		-			-	<del>                                     </del>				$\top$			
t				<u> </u>		1		1	27.03			4			1									
t				<del>                                     </del>	البير ا			178		10		SA			3	>								
1		•				Pag				1 3						1_		ļ	ļ	ļ	┷	$\sqcup$		
						1				dian.	7	St. Sure	CIP AND	A.D.		-		_	ļ	-	$\dotplus$	$\vdash$	<del> </del>	<u> </u>
1			<del> </del>			A. C. C.	1 Marian	\$1,5 ³⁰ (4)			1,60	A APPENIE	A 1-1-1-18-18-18-18-18-18-18-18-18-18-18-1	Agence		-	-	┼-	-	┼	+	╁┼	+	
+		_4/	eviation	4	Sum	eya	<u> </u>	┼	-	-	+	ļ	╁┈	+	<del> </del>	+	╁┈	+	+	+	+	$\dagger \dagger$	+	_
1				+		1	-	+	+	+-	+		+-	+		+	$\dagger$	+-	$\dagger$	+	T	$\dagger \dagger$	1	
1		566	3/4"	<del>                                     </del>	3650	24.	1	1	+	+		1	+	1										
1		1625	3/4	1	4/00	13/40																$\prod$		
_		2135	13/4°		4650	13/40			]						<u> </u>	_		_	_	<del> </del>	1	+	-	
		2625	2 •	,	5073	14.		<u> </u>			1.	-				1	-	+	-	-	+	++		-
					5700	./•						ļ				$\perp$					$\bot$	11		

### WELL HISTORY

Day	Date 1995	Depth	Operation	Daily Activity (Prev. 24 hrs.6AM-6AM)
1		294	WOC	Move in S rig up. Drill 17½" conductor hole S set conductor. Nipple up flow line S sir bowel. Spud 12½" surface 5/23/95 @ 7:00 PM. Drill to 294'. Made 294' in 5½ hrs. Circulate. Trip out. Hun 8 5/8" csg to 274' KB S cement w/160 sxs. WOC.
2	5/25	905	Orilling	WOC. Cut off casing & weld on head. Nipple up BOPs & pressure test - held O.K. Trip in Bit 1 & pick up OCs. Drill cement plug, baffle & shoe - 2 hrs. Drill out from under surface 5/24/95 @ 3:00 PM. Drill from 294 to 566'. Survey. Trip to recover survey tool & line - ½ hr. Drill to 905'. Made 611' in 13½ hrs.
3	5/26	2160	Orilling	Drill & survey from 905 to 2160'. Made 1255' in 22 3/4 hrs.
4	5/27	3250	Orilling	Orill & survey from 2160 to 3250'. Made 2090' in 22 hrs.
5	5/28	4090	Tripping	Orill & survey from 3250 to 4090'. Made 840' in 21 hrs. Load hole w/water. Circulate. Trip out for Bit 2.
6	5/29	4493	Orilling	Complete trip - 4 hrs. Orill & survey from 4090 to 4493'. Made 403' in 18 3/4 hrs.
7	5/30	4997	Orilling	Drill & survey from 4493 to 4997'. Made 503' in 23% hrs.
8	5/31	5516	Orilling	Drill & survey from 4997 to 5516'. Made 519' in 22½ hrs.
9	6/1	5700	Lay Down	Orill & survey from 5516 to 5700'. Made 184' in 9 3/4 hrs. Reach T.D. 5/31/95 @ 4:00 PM. Circulate. Trip out. Logging - 6½ hrs. Trip in. Lay down pipe & drill collars.
10	6/2	5700		Complete laying down. Run 131 jts, 5½" production csg. Cemented w/615 sxs. Plug down 6/1/95 @ 2:00 PM. Rig released 6/1/95 @ 6:00 PM.

Balcron Oil Company
Monument Butte Federal No. 11-7J
NWNW Sec. 7-T9S-R17E
Duchesne County, Utah

### SAMPLE DESCRIPTION

1400-1450	Sandstone, very fine-fine grained, light gray, white	ļ
	and clear quart grains, sub-angular to sub-rounded,	
	fair-good sorting, no show.	

### GREEN RIVER 1452 (+3903)

- 1450-1500 Shale, gray, gray-tan, sub-platy, chunky, calcareous; streaks Shale, tan, light red-tan, platy, calcareous, occasional limey streaks Oil Shale.
- 1500-1550 Sandstone, very fine grained, light gray, well sorted, sub-rounded, loose quartz grains; streaks Shale, brown, reddish brown, tan, chunky, dolomitic <u>Oil</u> Shale.
- 1550-1650 Shale, bright reddish tan, light brown, blocky, chunky, trace disseminated pyrite, calcareous to limey Oil Shale; @ 1600 increased Shale, brown, graytan, chunky, pyritic, calcareous and dolomitic Oil Shale.
- Shale, bright red, reddish tan, chunky, moderately calcareous and dolomitic Oil Shale; @ 1700 Shale, as above; streaks Shale, pale tan, light gray-tan, dolomitic; occasionally grades to shaley Limestone Oil Shale; trace calcite crystals; trace Limestone, cryptocrystalline, cream-tan, argillaceous, dense.
- 1750-1800 Shale, as above Oil Shale; streaks Limestone, crypto-microcrystalline, tan, cream-tan, argillaceous to shaley, siliceous in part; trace chert, tan.
- 1800-1900 Shale, brown, reddish brown, gray-tan, tan, chunky, dolomitic and calcareous; grades to Marl <u>Oil Shale;</u>
  @ 1850 increased Shale, gray, gray-tan, chunky, moderately calcareous to limey; grading to shaley Limestone.
- 1900-1950 Shale, bright reddish tan, brown, gray-brown, blocky, chunky, silty, calcareous; grades to a Marl <u>Oil</u> Shale.
- 1950-2000 Shale, as above; increased shaley Limestone <u>Oil</u> <u>Shale.</u>
- 2000-2050 Shale, brown, reddish brown, gray-brown, chunky,

dolomitic, streaks moderately calcareous; grades to Marl - Oil Shale. Shale, reddish tan, tan, chunky, moderately 2050-2150 calcareous; grades to shaley Limestone; streaks Shale, gray, gray-brown, chunky, dolomitic - Oil Shale. Shale, gray, gray-green, chunky, silty, non-cal-2150-2200 careous streaks Sandstone, very fine grained, white, sub-rounded, silty, well sorted, scattered black accessory grains, moderately calcareous to limey; trace bright yellow fluorescence - mineral fluorescence in part - scattered chips with good light yellow cut. Shale, reddish brown, brown, chunky, calcareous - 011 2200-2250 Shale; streaks Siltstone-very fine grained Sandstone, as above, moderately calcareous to limey, no show. Shale, reddish brown, sub-platy, dolomitic; occasional 2250-2300 calcareous streaks - Oil Shale. Shale, as above; streaks Shale, brown, gray-brown, 2300-2350 chunky, lumpy, dolomitic, calcareous streaks - Oil Shale. Shale, brown, gray-brown, chunky, silty in part, 2350-2450 moderately calcareous - Oil Shale. Shale, as above; influx Shale, reddish tan, chunky, 2450-2500 moderately calcareous - Oil Shale. Shale, gray-tan, tan-light brown, chunky, silty, 2500-2550 dolomitic in part - Oil Shale; streaks moderately calcareous; grades to shaley Limestone, cryptocrystalline, tan, light brown, dense. Shale, gray-brown, reddish brown, sub-platy, limey 2550-2600 streaks - Oil Shale. Sandstone, very fine-fine grained, occasionally medium 2600-2650 grained, white, tan, sub-rounded, fair-good sorting, appears fairly tight, possible fair porosity; scattered pale tan stain, scattered dull yellow and yellow fluorescence, fair-good light yellow cut; streaks Shale, dark brown, reddish brown, as above -Oil Shale. Siltstone-very fine grained Sandstone, gray-brown, 2650-2700 light gray, argillaceous to shaley, calcareous; grades to sandy Shale, brown, gray-brown, chunky.

2700-2750

Sandstone, very fine grained, light gray, tan, silty,

well sorted, sub-angular, no show; streaks Shale, reddish tan, brown, chunky, calcareous - <u>Oil Shale</u>.

Shale, reddish brown, brown, gray-brown, dolomitic, calcareous streaks - <u>Oil Shale</u>; occasional streaks

Sandstone, light gray-tan, fair-good sorting, slightly

2800-2850 Shale, as above, moderately calcareous to limey - Oil Shale; occasional streaks Limestone, cryptocrystal-line, brown, tan, argillaceous, silty in part.

calcareous, tight.

2750-2800

- Shale, dark gray-green, chunky, pyritic, very silty and sandy in part, waxy in part; Sandstone, very fine-fine grained, occasionally medium grained, white, tan, fair to good sorting, sub-angular, slightly calcareous, loose quartz grains, no fluorescence, no cut.
- 2900-2950 Shale, medium-dark gray, gray-green, chunky, pyritic, very silty and sandy in part; occasional streaks Sandstone, as above.
- 2950-3000 Shale, tan, tan-cream, reddish brown, chunky, sub-platy, slightly calcareous to limey Oil Shale; scattered light yellow fluorescence, poor-fair light yellow cut.
- 3000-3050 Shale, tan, cream, moderately calcareous; grades to Limestone, earthy, microcrystalline, argillaceous; streaks Sandstone, very fine grained, white, light gray, silty, good sorting, calcareous to limey, tight.
- 3050-3100 Shale, light to medium gray, sub-platy, chunky, very silty in part; interbedded Sandstone, very fine grained, light gray, silty, good sorting, argillaceous, slightly calcareous, appears tight, no show.
- 3100-3150 Shale, gray, gray-tan, brown, platy, chunky, silty in part.
- 3150-3200 Shale, tan, light brown, platy, moderately calcareous to limey; streaks Limestone, cryptocrystalline, tan, earthy, argillaceous.
- 3200-3250 Limestone, earthy, cryptocrystalline, bright tan, reddish tan, argillaceous; streaks Shale, gray-green, chunky, waxy.
- 3250-3350 Limestone, micro-cryptocrystalline, fragmental, tan, argillaceous, earthy in part; streaks Shale, light gray-gray, gray-tan, chunky, sub-waxy, silty; streaks

Sandstone, very fine grained, light grayish white, well sorted, sub-angular, primarily loose quartz grains; @ 3300 occasional streaks Shale, gray-tan, gray-brown, chunky, calcareous and dolomitic - Oil Shale.

- 3350-3400 Limestone, as above; increased Shale, dark gray, gray-brown, brown, waxy, silty in part Oil Shale.
- 3400-3450 Shale, light-medium gray, sub-waxy, silty in part; influx Sandstone, very fine grained, light gray, silty, sub-angular, fair-good sorting, appears tight; streaks Limestone, as above.
- 3450-3500 Shale, bright green, light gray, pale gray-green, waxy, silty streaks; abundant Sandstone, very fine-fine grained, light grayish white, clear, fair sorting, sub-angular, primarily loose quartz grains; occasional streaks Limestone, as above.
- Shale, gray, gray-tan, brown, chunky, very silty in part; grades to argillaceous Siltstone Oil Shale; occasional streaks Sandstone, as above; occasional streaks Limestone, as above.
- 3550-3600 Shale, light gray-gray, gray-tan, very silty in part; streaks Shale, tan, light brown, reddish brown, sub-platy, slightly dolomitic Oil Shale.
- 3600-3650 Limestone, micro-cryptocrystalline, tan, earthy, argillaceous; streaks Shale, brown, reddish brown, gray-brown, calcareous and dolomitic Oil Shale.
- 3650-3750 Shale, gray, gray-green, waxy, silty in part; abundant Limestone, as above; streaks Sandstone, very fine-fine grained. light gray, sub-angular, fair sorting, primarily loose quartz grains, cavings? At 3700 increased Sandstone, as above.
- 3750-3800 Shale, pale gray-green, light gray, chunky, waxy, silty in part; streaks Sandstone, very fine grained, light grayish white, well sorted, sub-angular to sub-rounded, moderately calcareous, tight.

### 2nd GARDEN GULCH 3796 (+1559)

- Sandstone, very fine grained, tan, light gray-tan, sub-rounded, well sorted, primarily loose quartz grains, possible poor porosity, questionable pale tan stain, scattered dull yellow fluorescence, slow cloudy cut;) streaks Shale, as above.
- 3850-3900 Shale, gray-green, waxy, chunky, silty in part;

abundant loose quartz grains, very fine-fine grained, light gray, white, clear, sub-angular (cavings?).

- 3900-3950 Shale, reddish brown, brown, tan, gray-tan, chunky, dolomitic Oil Shale; Shale, as above; abundant loose quartz grains, as above.
- 3950-4050 Shale, pale gray, gray-tan, chunky, waxy, dolomitic in part, silty and sandy; abundant loose quartz grains, as above, no show.
- 4050-4090 Shale, pale gray-green, chunky, silty in part; streaks Sandstone, very fine-fine grained, light grayish white, fair-good sorting, sub-angular, slightly calcareous, no show.
- Sandstone, very fine-fine grined, light brown, fair-good sorting, sub-angular, rare dark brown accessory grains, slightly calcareous, silica cement, appears primarily tight, possible poor porosity; light brown-brown stain, faint dull yellow fluorescence, fairly weak light yellow persistent cut; Shale, reddish brown, tan, sub-platy, dolomitic and calcareous Oil Shale; streaks Shale, light-medium gray, pale gray-green, chunky, platy, silty, waxy in part, few streaks very silty. Poor sample from bit trip.
- 4130-4160 Shale, light-medium gray, chunky, sub-platy, waxy, very silty in part; occasional streaks Shale, reddish brown, chunky, blocky, dolomitic Oil Shale.
- 4160-4190 Shale, gray, gray-brown, chunky, silty; rare streaks Siltstone, light gray-tan, good sorting, tight; streaks Shale, reddish brown, as above Oil Shale.
- 4190-4220 Siltstone-very fine grained Sandstone, light gry, white, well sorted, argillaceous in part, sub-rounded, calcareous, tight, no show; Shale, as above, very silty in part.
- 4220-4250 Shale, dark brown, blocky, dolomitic, sharp; Shale, gray, light gray-green, chunky, waxy, silty in part; streaks Siltstone, as above.
- 4250-4280 Shale, dark brown, chunky, sub-platy, dolomitic, silty in part, carbonaceous; Shale, as above; streaks Shale, tan, platy, calcareous to limey; Shale, reddish tan, chunky, dolomitic Oil Shale.
- 4280-4310 Shale, dark gray, gray-brown, blocky, brittle, carbonaceous; rare streaks Siltstone-very fine grained Sandstone, gray, white, well sorted, sub-angular to

sub-rounded, argillaceous, slightly calcareous, tight.

- 4310-4340 Shale, dark brown, dark gray-brown, platy, blocky, carbonaceous; streaks Shale, reddish brown, light brown, platy, blocky, moderately calcareous, limey in part; streaks Siltstone-very fine grained Sandstone, light gray, white, well sorted, calcareous, argillaceous in part, tight.
- Sandstone, very fine-fine grained, tan, pale brown, well sorted, sub-angular to sub-rounded, contact silica cement, streaks of poor to fair porosity; tan to light brown stain, few brownish black specks, bright yellow-yellow fluorescence, instant strong whitish yellow cut; streaks Shale, as above.
- 4370-4400 Shale, gray, sub-platy, smooth, waxy in part, occasionally silty.
- 4400-4430 Shale, as above; streaks Siltstone, light gray, argillaceous, slightly calcareous; influx Shale, reddish bown, reddish tan, blocky, platy, dolomitic and calcareous Oil Shale cavings.

### YELLOW MARKER 4426 (+929)

- 4430-4460 Shale, pale gray-gray, greenish cast, waxy, silty in part; abundant Shale, reddish brown, as above Oil Shale cavings; occasional streaks Siltstone, as above; trace Limestone, earthy, tan, soft.
- Limestone, ostracods in microcrystalline to lime mud matrix, fragmental in part, tan, earthy in part, loose ostracods common in sample; scattered even to spotty brown stain, light yellow-yellow fluorescence with greenish cast, fair-good whitish yellow streaming cut, becomes cloudy; streaks Shale, bright tan, chunky, moderately calcareous to limey, very silty in part.
- 490-4520 Shale, pale green, pale gray, gray, waxy, silty; influx Siltstone-very fine grained Sandstone, white, sub-rounded, calcareous, tight; streaks Shale, red-brown, chunky, sub-blocky, calcareous to limey in part.
- 4520-4550 Siltstone-very fine grained Sandstone, as above, tight, no show; Shale, pale gray, gray, gray-green, waxy, smooth, silty in part; abundant Shale, reddish brown, reddish tan, chunky, dolomitic and calcareous Oil Shale.
- 4550-4580 Shale, light gray, platy, waxy and silty in part;

streaks Siltstone, light gray, gray, argillaceous, slightly calcareous, tight; streaks Siltstone-very fine grained Sandstone, as above, tight, no show; Shale, reddish brown, blocky, chunky, dolomitic and calcareous streaks - Oil Shale.

### DOUGLAS CREEK 4591 (+764)

- 4580-4610 Shale, brown, reddish brown, chunky, blocky, dolomitic and calcareous; Shale, gray, gray-tan, platy, chunky, smooth.
- 4610-4640 Shale, pale gray, pale green, platy, silty in part; streaks interbedded Siltstone, light gray, very argillaceous, slightly calcareous; Shale, reddish brown, blocky, platy, dolomitic.
- 4640-4670 Shale, brown, dark brown, gray-tan, sub-platy, chunky, calcareous in part; streaks Shale, as above.
- 4670-4700 Shale, light gray, pale gray-green, sub-waxy, occasionally silty; streaks Siltstone-very fine grained Sandstone, white, slightly calcareous, tight; Shale, reddish brown, chunky, platy, dolomitic in part, calcareous to limey in part Oil Shale.
- 4700-4760 Shale, light gray-gray, sub-platy, waxy, silty streaks; occasional streaks Siltstone-very fine grained Sandstone, light gray, white, well sorted, calcareous, appears tight; streaks Shale, reddish brown, as above Oil Shale; @ 4730 increased Siltstone-very fine grained Sandstone, as above, tight, no show.
- 4760-4790 Shale, medium gray, platy, chunky, sub-waxy, smooth; Shale, reddish tan, blocky, platy, moderately calcareous to limey.

### R-5 SAND 4784 (+571)

- 4790-4820 Sandstone, very fine grained, light gray-white, pale tan, occasionally becomes fine grained, fair sorting, sub-angular, slightly dolomitic, streaks poor porosity; pale tan stain, bright light yellow to whitish yellow fluorescence, slow faint light whitish yellow cut; streaks Shale and Siltstone, as above.
- 4820-4880 Shale, light-medium gray, sub-platy, smooth, pyritic; streaks Siltstone, light gray-tan, argillaceous, moderately calcareous to limey; streaks Shale, reddish brown, chunky, blocky, dolomitic Oil Shale.

- 4880-4910 Shale, as above; increased Siltstone, as above.
- 4910-4940 Shale, light-medium gray, platy, waxy in part, occasionally silty; trace Siltstone, light gray-tan; occasionally grades to very fine grained Sandstone, fair-good sorting, calcareous, appears tight; spotty tan to light brown stain, no fluorescence to faint dull yellow, occasional very faint pale whitish yellow cut.
- 4940-4970 Shale, dark gray-brown, platy, calcareous, limey streaks; trace Limestone, cryptocrystalline, tan, light brown, argillaceous.

### GREEN MARKER 4977 (+378)

- 4970-5000 Shale, light gray, occasionally medium gray, platy, silty streaks, calcareous, few limey streaks; Silt-stone, light gray, argillaceous to shaley, calcareous.
- 5000-5030 Shale, as above; influx Shale, reddish brown and tan, blocky, sub-platy, moderately calcareous in part, limey streaks.
- Shale, pale gray, chunky, waxy in part, calcareous streaks, very silty in part; streaks Siltstone, light gray, very argillaceous, calcareous; @ 5060 increased Siltstone-very fine grained Sandstone, light gray-gray, argillaceous, calcareous; streaks Shale, reddish brown and tan, blocky, dolomitic and calcareous.
- Siltstone-very fine grained Sandstone, light gray, tan, well sorted, slightly calcareous, appears tight, scattered light brown, brown stain, few clusters with faint dull yellow fluorescence, slight greenish cast, slow whitish yellow cloudy cut; Shale, reddish brown and tan, platy, blocky, chunky, moderately calcareous to limey.
- Shale, pale gray, platy, smooth, waxy, silty in part; occasional streaks Siltstone-very fine grained Sandstone, as above; trace stain, fluorescence and cut, as above; Shale, reddish tan, blocky, moderately calcareous to limey.
- 5150-5180 Shale, light-medium gray, sub-platy, waxy in part, silty streaks; Shale, reddish brown, occasionally reddish tan, blocky, dolomitic Oil Shale.
- 5180-5210 Shale, medium to dark gray, chunky, occasionally silty.

5210-5240 Shale, dark gray, gray-brown, blocky, chunky, firm Shale, brown, gray-brown, chunky, sub-platy, 5240-5270 occasionally silty, soft. 5270-5300 Shale, gray-tan, gray, chunky, sub-blocky, slightly calcareous, very silty in part; grades to shaley Siltstone. BSF 5288 (+67) Shale, black, dark gray, dark gray-brown, sub-platy, 5300-5360 carbonaceous, few chips with petroliferous appearance, firm. 5360-5390 Shale, dark gray-brown, brown, chunky, sub-platy, carbonaceous, slightly calcareous. 5390-5420 Shale, dark brown, blocky, platy, carbonaceous, calcareous in part, limey streaks. CARBONATE MARKER 5436 (-81) 5420-5450 Shale, brown, gray-brown, moderately calcareous; streaks Limetone, cryptocrystalline, brown, dark brown, argillaceous, dense; streaks Sandstone, very fine grained, grayish brown, fair sorting, subangular, calcareous, silty, appears tight, possible poor porosity; scattered spotty to even black stain, faint dull yellow fluorescence, slight greenish cast, very slow whitish yellow cut. Shale, pale gray, tan, smooth; occasional streaks 5450-5510 Sandstone, very fine grained, as above; scattered spotty dark brown and black stain, fluorescence and cut, as above; streaks Shale, pale gray, smooth; Shale, reddish tan, chunky, sub-blocky, dolomitic and calcareous, abundant cavings? At 5480 slight increased Shale, pale gray, platy, chunky, waxy. Shale, medium gray, occasionally dark gray, sub-platy, 5510-5540 chunky, smooth; streaks Siltstone, light gray, gray-brown, argillaceous, tight. Shale, as above; influx Siltstone, light gray, 5540-5570 gray-tan, argillaceous, calcareous; occasionally grades to very fine grained Sandstone, appears tight; trace spotty light brown stain, dull yellow, yellow-white fluorescence, slow faint light yellow cut; abundant Shale, reddish brown, cavings? Shale, as above; streaks Siltstone-very fine grained 5570-5600 Sandstone, as above; streaks Shale, dark gray, blocky,

carbonaceous, abundant cavings.

Sandstone, very fine grained, occasionally fine grained, white, light gray, fair sorting, rounded to sub-rounded, moderately calcareous; no show; Shale, pale gray, platy, smooth; abundant Shale, reddish tan, reddish brown, blocky, platy, moderately calcareous - cavings?

5630-5660 Sandstone, as above, no show; streaks Shale, pale gray, platy, smooth; abundant Shale, reddish tan, moderately calcareous, limey in part.

Shale, light-medium gray, gray-tan, chunky, very silty; streaks Siltstone-very fine grained Sandstone, well sorted, moderately calcareous to limey, appears tight, possible poor porosity; scattered grayish tan stain, faint dull yellow fluorescence, slow weak whitish yellow cut.

Shale, gray, gray-tan, platy, chunky, silty in part; occasional streaks Siltstone, as above; trace stain, fluorescence and cut, as above.

# STATE OF UTAH DIVISION OF OIL, GAS AND MINING DRILLING INSPECTION FORM

OPERATOR: EQUITABLE RESOURCES COMPANY REF: AL PLUNKETT						
WELL NAME: BALCRON MON FED 11-7J API NO: 43-013-31492						
GTR/GTR: NW/NW SECTION: 7 TWP: OBS RANGE: 17E						
CONTRACTOR: UNION DRILLING COMPANY RIG NUMBER: #17						
INSPECTOR: DENNIS L. INGRAM TIME: 2:45 PM DATE: 3/30/95						
SPUD DATE: DRY: 3/21/95 ROTARY: 5/21/95 PROJECTED T.D. 5700'						
OPERATIONS AT TIME OF VISIT: (5157' ON VISIT) DRILLING AHEAD.						
WELL SIGN: Y MUD WEIGHT 8.3+ LBS/GAL BOPE: Y BLOOIE LINE: Y FLARE PIT: Y H2S POTENTIAL: NO						
ENVIRONMENTAL:						
RESERVE PIT: Y FENCED: Y LINED: Y PLASTIC: Y						
RUBBER: BENTONITE; SANITATION: Y						
BOPE TEST RECORDED IN THE RIG DAILY TOUR BOOK: YES						
REMARKS:						
DRILLING WITH KCL WATER AND SHOULD T.D. ON THURSDAY MORNING.						
LAST SURVEY WAS ON WIRE LINE RAN AT 5073 AND WAS 1 1/4 DEGREES.						
UNION #17 WILL DRILL ONE MORE HOLE AND THEN GO TO SHAKE VALLEY						
IN UTAH ON THE NEVADA LINE.						

### **Durwood Johnson**


Petroleum Geologist



3118 AVENUE F BILLINGS, MONTANA 59102 (406) 656-4872

June 28, 1995

State of Utah Division of Oil, Gas, & Mining 355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, UT 84180



### Reference:

Balcron Oil Company
Federal No. 41-10Y
CNENE Sec. 10-T95-R16E
DuchesneCounty, Utah
43 0/3 3/478 PA
Gentlemen:

Balcron Oil Company Federal No. 32-19Y CSWNE Sec. 19-T8N-R17E Uintah County, Utah 43 047 32615 DRL

Balcron Oil Company
Monument Federal No. 11-7J
NWNW Sec. 7-T95-R17E
Duchesne County, Utah
43-0/3-3/492 DRC
0681 FNL 0447 FWC

Enclosed are two copies of the Geological Wellsite Report for each of the subject wells for your files.

If you have any questions, please contact me.

Sincerely,

Durwood Johnson

DJ/jb Enclosures CONFIDENTIAL

## STATE OF UTAH DIVISION OF OIL, GAS AND MINING

		<u> </u>			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	F	REPORT OF	WATER ENCOUNTERED	DURING DRILLING	AUG 1.4 1995
1. Well name and number:				≈, a ⊊ , g	OFOLERS III
API numbe	er:43-01.3-3	31492 			
			Township9S Range1	7E County <u>Duchesne</u>	
3. Well opera	ator: <u>Equitabl</u>	e Resources E	hergy Company, Balcron Oil Divi	sion	
Address:	1601. Lew	zis Avenue			
	Billings	s, Mr 59102	Phone: (406) 259-7860		
4. Drilling ∞	ntractor: Un	nion Drilling			
Address:		awer 40			
	Bu	ickhannon, W	26201	Phone: <u>(304) 4</u>	724610
S. Water enc	ountered (attac	th additional p	ages as needed):		
, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				QUALITY	
	FROM	РТН то	VOLUME (FLOW RATE OR HEAD)	(FRESH OR SALT	n
			No measurable water encounte	red	
			during drilling operations	·	
•					
	,				
			J		
6. Formation	tops:	ease see the 1	back side of the completion re	port.	
	_	· .			
	_			<u> </u>	
	Ç				
l an analysis	has been mad	e of the water	encountered, please attach a co	ppy of the report to this fo	rm.

Regulatory and Title: <u>Brvironmental Specialist</u>

I hereby certify that this report is true and complete to the best of my knowledge.

Bobbie Schuman, 💥

Name & Signature:

	TED STATES IT OF THE INTERIOR	FORM APPROVED Budget Bureau No. 1004-0135 Expires: March 31, 1993
	LAND MANAGEMENT	5. Lesse Designation and Serial No.
SUNDEY NOTICES	AND DEDOCTE ON WELLS	U-44426
SUNDHY NUTICES	AND REPORTS ON WELLS ill or to deepen or reentry to a different reservoir.	6. If Indian, Allottee or Tribe Name
Use "APPLICATION FO	R PERMIT—" for such proposals	n/a
CUDMIT	IN TRIPLICATE	7. If Unit or CA, Agreement Designation
	IN TRIFLICATE	_ Jonah Unit
I. Type of Well  Oil  Well  Other	•	8. Well Name and No.
2. Name of Operator		Balcron Monument Fed. #11-7J
Equitable Resources Energy Co	mpany, Balcron Oil Division	43-013-31492
3. Address and Telephone No. 1601 Lewis Avenue; Billings,	MT 59102 (406) 259-7860	10. Field and Pool, or Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey D		Monument Butte/Green River
NW NW Section 7, T9S, R17E		11. County or Parish, State
681' FNL, 447' FWL		Duchesne County, UT
	s) TO INDICATE NATURE OF NOTICE, REPO	
	TYPE OF ACTION	•
TYPE OF SUBMISSION		
Notice of Intent	Abandonment Recompletion	Change of Plans  New Construction
Subsequent Report	Plugging Back	Non-Routine Fracturing
	Casing Repair	Water Shut-Off
Final Abandonment Notice	Altering Casing Other	X_ Conversion to Injection  Dispose Water
		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)
Operator hereby requests p well. This will be hooked and will inject approximat	Ill pertinent details, and give pertinent dates, including estimated date of startin cal depths for all markers and zones pertinent to this work.)*  Dermission to convert this well to a wall up to the existing Jonah Unit water cely 150 STBWPD into the sands of the	ater injection injection system Douglas Creek Member
of the Green River formati injection wellbore diagram	on. See attached well data sheet and	proposed water
•	,	
	· ·	177 76 178 17 17 17 17 17 18 1 1 1 1 1 1 1 1 1
•		RUBINE
ORIGINAL: Bureau of Land	Management (Vernal, UT)	
COPY: Utah Division of Oi	I, Gas and Mining	AUG 1 4 1995
	•	
	in the state of th	The second of th
•	returns 1	sau garta sulaa kiristiin ∌aat Aleekka la talifa la 1800 tili
14. I hereby certify that the foregoing is true and correct	Regulatory and	) .v .a.=
Signed Dobbie Schuman	Tide Environmental Specialist	d by The State / 1995
(This space for Federal of Stall Office use)	of Utah	Division of
Approved by	TitleOII, Gas	Date
Conditions of approval, if any:	Dato:	
Title 10 10 00 Card 1991 and 1991 and 1991 and 1991	n knowingly and willfully to make to any department or agency of the Unite	d States any false, fictitious or fraudulent statements
or representations as to any matter within its jurisdiction.	Dougles Side	and the second of the second o

#### Jonah Unit Waterflood Attachment To Sundry Notice

Equitable Resources Energy Company, Balcron Oil Division is requesting permission to convert the Balcron Monument Federal #11-7J well to a water injection well. The well is located in the NW NW Section 7, T9S, R17E (Jonah Unit Waterflood), Duchesne County, Utah. The well will be hooked up to the existing Jonah Unit water injection system and will inject approximately 150 STBWPD into the sands of the Douglas Creek Member of the Green River Formation. Refer to the attached welldata sheet and proposed water injection wellbore diagram.



WELL NAME: Balcron Monument Federal #11-7J

FIELD: Monument Butte

FEDERAL LEASE NO.: U-44426

LOCATION: NW NW Sec.7, T9S, R17E

681' FNL & 447' FWL

COUNTY/STATE: Duchesne County, Utah

WORKING INTEREST: 0.805079506 PRODUCING FORMATION: Green River

**COMPLETION DATE: 6-14-95** 

**INITIAL PRODUCTION: Not Tested** 

PRESENT PROD STATUS: Waiting Conversion To Injection.

WATER INJECTION RATE:

**ELEVATIONS - GROUND: 5345'** 

TOTAL DEPTH: 5697' KB

SURFACE CASING

SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24# LENGTH: 265' (6 its)

DEPTH LANDED: 275' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI +

1/4#/sk celloflake

TURNIC RECORD

LODING KECOKD		•
	Length	Setting Depth
		w/ 10' KB
149 jnts 2 7/8", J-55, 6.5# Tubing	4668.33'	4678.33'
2 7/8" Seating Nipple	1.10'	4679.43'
2 3/8'x 2 7/8" Cross Over	0.75	4680.18'
Arrow Set-1 Packer	6.20'	4686.38'

Total String Length: 4676.38' Packer Landed: 4686.38' KB

Arrow Set-1 Packer set w/13" tension on 6-14-95.

Packer Fluid: 55 gals Champion Cortron-2383 mixed w/ 75 STB 2 % KCl water.

SN @ 2 7/8" x 2.25" ID

Logs: Dual Laterolog, Compensated Neutron Litho-Density, Cement Bond Log.

DATE: 8-8-95.17

API NO.: 43-013-31492

NET REVENUE INTEREST: 0.73831617 Oil

0.66359285 Gas

OIL GRAVITY: 34 deg

SPUD DATE: 5-24-95

KB: 5355' (10' KB) PLUG BACK TD: 5671' KB

#### PRODUCTION CASING

SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 5660.72 (143 its)

DEPTH LANDED: 5671' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 383 sxs super class "G" + (47#G + 20#Poz A +

17# CSE)/sk +3%salt + 2%gel +1/4 #/sk celloseal,

tail w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk

celloseal + 2 #/sk HiSeal 2

CEMENT TOP AT: 110' KB from CBL.

#### PERFORATION RECORD

6-12-95 Schlumberger

4784'- 87' 2 SPF (.38") 3 ft 6 holes 4790'- 96' 2 SPF (.38") 6 ft 12 holes

4926'- 28' 2 SPF (.38") 2 ft 4 holes

5075'- 79' 4 SPF (.38") 4 ft 16 holes

5089'- 94' 4 SPF (.38") 5 ft 20 hotes 5112'- 14' 4 SPF (.38") 2 ft 8 holes

#### ACID JOB / BREAKDOWN JOB

Schlumberger

6-8-95 BJ/Western

6-8-95

5075'- 5114': 2982 gals 2% KCI wtr w/ 100 balls,

ATR 4.0 bpm, ATP 2600 psig, ISIP 1850 psig.

6-12-95 BJ/Western

4784'- 4796': 2058 gals 2% KCl wtr w/ 2 balls/bbl,

ATR 4.5 bpm; ATP 2200 psig, ISIP 1350 psig.

6-12-95 BJ/Western

4926'- 4928': 1596 gais 2% KCI wtr w/ 2 balls/bbl,

ATR 3.1 bpm, ATP 4000 psig, ISIP 1950 psig.

#### FRAC JOB

6-8-95 BJ/Western 5075' - 5114': 12,684 gals 2% KCl wtr w/ 27,660 ibs 16-30 mesh sand, ATR 34.5 bpm, ATP 2400 psig,

ISIP 2300 psig, 15 min 2060 psig.

6-12-95 BJ/Western

4784' - 4928' : 15,162 gals 2% KCI wtr w/ 22,200 lbs

16-30 mesh sand, ATR 35.1 bpm, ATP 3400 psig,

ISIP 2150 psig, 15 min 1660 psig.



Baicron Monument Federal #11-7J 681' FNL & 447' FWL NW NW Sec.7, T9S, R17E Lease No. U-44426 Monument Butte Field Duchesne County, Utah

Elev. - 5345' GL Elev. - 5355' KB

#### **WELLBORE DIAGRAM**

DATE: 8-8-95 JZ

#### SURFACE CASING

SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24# LENGTH: 265' (6 jts) DEPTH LANDED: 275' KB HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI +

1/4#/sk celloflake

275' KB

#### PRODUCTION CASING

SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15.5# LENGTH: 5660.72 (143 jts) DEPTH LANDED: 5671' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 383 sxs super class "G" + (47#G + 20#Poz A + 17# CSE)/sk +3%salt + 2%gel +1/4 #/sk celloseal, tail w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk celloseal + 2 #/sk HiSeal 2

CEMENT TOP AT: 110' KB from CBL.

#### TUBING RECORD

	Length	Setting Depth
	_	w/ 10' KB
149 jnts 2 7/8", J-55, 6.5# Tbg	4668.33'	4678.33'
2 7/8" Seating Nipple	1.10	4679.43'
2 3/8'x 2 7/8" Cross Over	0.75'	4680.18'
Arrow Set-1 Packer	6.20'	4686.38'

Total String Length: 4676.38' Packer Landed: 4686.38' KB

Arrow Set-1 Packer set w/13" tension on 6-14-95.

Packer Fluid: 55 gals Champion Cortron-2383 mixed w/ 75 STB 2 % KCl water.

SN @ 2 7/8" x 2.25" ID

Logs: Dual Laterolog, Compensated Neutron Litho-Density, Cement Bond Log.

6-8-95	BJ/Western	5075'-5114': 2982 gals 2% KCl wtr w/ 100 balls, ATR 4.0 bpm, ATP 2600 psig, ISIP 1850 psig.						
6-12-95	BJ/Western	4784'- 4796': 2058 gals 2% KCi wtr w/ 2 balls/bbl, ATR 4.5 bpm, ATP 2200 psig, ISIP 1350 psig.						
6-12-95	BJ/Western	4926'- 4928': 1596 gals 2% KCl wtr w/ 2 balls/bbl, ATR 3.1 bpm, ATP 4000 psig, ISIP 1950 psig.						
FRAC JO	В							
6-8-95	BJ/Western	5075' - 5114' : 12,684 gals 2% KCI wtr w/ 27,660 l 16-30 mesh sand, ATR 34,5 bpm, ATP 2400 psig, ISIP 2300 psig, 15 min 2060 psig.						
6-12-95	BJ/Western	4784' - 4928' : 15,162 gals 2% KCl wtr w/ 22,200 lbs 16-30 mesh sand, ATR 35.1 bpm, ATP 3400 psig, ISIP 2150 psig, 15 min 1660 psig.						
PERFOR	ATION RECORD							
6-12-95	Schlumberger	4784'- 87' 2 SPF (.38") 3 ft 6 holes 4790'- 96' 2 SPF (.38") 6 ft 12 holes 4926'- 28' 2 SPF (.38") 2 ft 4 holes						

Retrievable Casing Packer @ 4686' KB

4784'- 4928' KB

5075'- 5114' KB

學

PBTD @ 5734' KB TD @ 5800' KB



Balcron Monument Federal #11-7J NW NW Sec.7, T9S, R17E 681' FNL & 447' FWL Lease No. U-44426 Monument Butte Field Duchesne County, Utah

#### PROPOSED INJECTION WELL COMPLETION DIAGRAM

Elev. - 5345' GL

Elev. - 5355' KB (10' KB)

DATE: 8-8-95 JZ

#### SURFACE CASING

SIZE: 8-5/8"

GRADE: J-55 WEIGHT: 24# LENGTH: 265' (6 jts)

DEPTH LANDED: 275' KB HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI +

1/4#/sk celloflake

275' KB

#### PERFORATION RECORD

6-12-95 Schlumberger

4784'- 87' 2 SPF (.38") 3 ft 6 holes 4790'- 96' 2 SPF (.38") 6 ft 12 holes 4926'- 28' 2 SPF (.38") 2 ft 4 holes

6-8-95 Schlumberger

5075'- 79' 4 SPF (.38") 4 ft 16 holes 5089'- 94' 4 SPF (.38") 5 ft 20 holes 5112'- 14' 4 SPF (.38") 2 ft 8 holes

#### PRODUCTION CASING

SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 5660.72 (143 jts) DEPTH LANDED: 5671' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 383 sxs super class "G" + (47#G + 20#Poz A +

17# CSE)/sk +3%salt + 2%gel +1/4 #/sk celloseal,

tail w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk

celloseal + 2 #/sk HiSeal 2

CEMENT TOP AT: 110' KB from CBL.

#### - Uinta Formation @ Surface to 1400'

- Green River Formation @ 1400'- 4100'

#### TUBING RECORD

SIZE / GRADE / WEIGHT: 2-7/8", J-55, 6.5#

SEAT NIPPLE : 2-7/8" X 1.1'

SN LANDED @ 4679' KB

RETRIEVABLE CSG PACKER

MODEL: Arrow Set-1
PACKER LANDED @ 4686' KB

- Douglas Creek Member @ 4100'- 5350'
RETRIEVABLBE CASING PACKER @ 4686' KB

4784' - 4928' KB

5075' - 5114' KB

- Wasatch Formation Transition @ 5350'- 6000'

PBTD @ 5671' KB TD @ 5697' KB

- Wasatch Formation @ 6000'

Form 3160-5 (June 1990)

X Notice of Intent

Subsequent Report

or representations as to any matter within its jurisdiction.

Final Abandonment Notice

#### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED Budget Bureau No. 1004-0135 Expires: March 31, 1993

5. Lease Designation and Serial No.

Change of Plans

New Construction

Water Shut-Off

Dispose Water

Non-Routine Fracturing

Conversion to Injection

U-44426

SUNDRY NOTICES AND REPORTS ON W
---------------------------------

6. If Indian, Allottee or Tribe Name Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals 7. If Unit or CA, Agreement Designation SUBMIT IN TRIPLICATE Jonah Unit 1. Type of Well 8. Well Name and No. X Well Balcron Monument Fed. #11-73 2. Name of Operator Equitable Resources Energy Company, Balcron Oil Division 9. API Well No. 43-013-31492 3. Address and Telephone No. 10. Field and Pool, or Exploratory Area. (406) 259-7860 1601 Lewis Avenue; Billings, MT 59102 Monument Butte/Green River 4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 11. County or Parish, State NW NW Section 7, T9S, R17E 681' FNL, 447' FWL Duchesne County, UT CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF ACTION TYPE OF SUBMISSION

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Abandonment

Recompletion

Plugging Back


Casing Repair

Altering Casing Lay injection line

Operator proposes to lay a water injection line in accordance with the attached procedure. A map is also attached.

ORIGINAL: Bureau of Land Management (Vernal, UT)

Utah Division of Oil Gas and Mining




	·			
14. I hereby certify that the foregoing is true and correct	Regulatory an	d	D. aud la	nac
Signed Bobbil Schuman	Tide <u>Environmenta</u>	d 1 Specialist <b>Accept</b>	and by the	993
(This space for Federal or State office use)		litah D	livision Of	
Approved by Conditions of approval, if any:	Title	Oll, Gas	and Mining	
		FOR DE	CARD AWY	
Title 18 11 S.C. Section 1001, makes it a crime for any person kno	wingly and willfully to make to any depar-	tment or agency f Mite the	any file, netinous or traudulent sta	ricment

#### Jonah Unit Waterflood Attachment To Sundry Notice

Equitable Resources Energy Company, Balcron Oil Division is requesting permission to install a high pressure water injection line from the Balcron Monument Federal #11-7J well to the existing Jonah Unit water injection system. The water injection line will be constructed as follows:

- 1) A two inch steel high pressure water injection line will be laid from the Balcron Monument Federal #11-7J to the existing Jonah Unit water injection system. The high pressure line will be tied to the main Jonah Unit injection line in the NW NE Section 12, T9S, R17E, Duchesne County, Utah.
- 2) The water injection line will be laid by constructing a 60 foot right-of-way and digging a trench with a trackhoe approximately five feet deep and three feet wide. Due to the topography it is not possible to estimate the amount of the ditch line that will require blasting, however it is reasonable to conclude that some blasting will be required.
- 3) The water injection line will be two inch high pressure steel linepipe that will be welded together, primed, taped, outer rock guarded, and laid in the bedded trench. The water injection line will then be shaded for protection from rocks. All bedding and shading material will be purchased and brought in from sources off BLM leases.
- 4) A two inch SDR-7 poly line will be installed in the same trench as the water injection line from the Balcron Monument Federal #41-12J oil production well to the tie in point in the NW SE of Section 12. This will allow the gathering of produced water at a later date without additional disturbance to the environment.
- 5) This proposed water injection line will supply a maximum of 300 STBWPD at an estimated line pressure of 2300 psig to the Balcron Monument Federal #11-7J.
- 6) All right-of-ways will be recontoured, shaped, and seeded as per the specific instructions set forth by the Vernal Buearu Of Land Management.
- 7) All right-of-way will be kept to a minimum and the requested 60 foot ROW will be reduced whenever possible.
- 8) See the attached topographic map for the exact route proposed for the Balcron Monument Federal #11-7J water injection line and how it ties in to the existing Jonah Unit facilities.





1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860

FAX: (406) 245-1365 FAX: (406) 245-1361

August 10, 1995

Bureau of Land Management Vernal District Office 170 South 500 East Vernal, UT 84078

Gentlemen:

RE:

Balcron Monument Federal #11-7J

NW NW Section 7, T9S, R17E

Duchesne County, Utah

Enclosed for your records on the subject well is the Completion Report.

Please feel free to contact me if you need any further information.

Sincerely,

Molly Conrad

**Operations Secretary** 

/mc

Enclosures

cc: State of Utah, Division of Oil, Gas, & Mining: also enclosed is

our Report of Water Encountered

Bobbie Schuman Lou, Ann Carlson Valeri Kaae Form 3160-4 (November 1983) (formerly 9-330)

## UN STATES SUBMIT IN DUPLIC

Form approved. Budget Bureau No. 1004-0137 Expires August 31, 1985

	DEPAR	REAU OF LA	OF THE III ND MANAGEN	NTERIO MENTAUG 1	R .4 19	structions/oreverse side	5. LEASE DE		ION AND SERIAL NO
	MPLETION			REPORT	ANI	D LOG*			TTRE OR TRIBE NAME
ia, TYPE OF WE	LL: OH. WE	LL X GAS	DRY C	Other		# Nikolane W	7. UNIT AGR	EEMENT	NAME
b. TYPE OF COM	IPLETION: WORK [ ] DE	sr- 🗀 rure	C DIER C	רוי	וחרו	<b>TENTIP</b>	Jonah U	nit	
NEW WELL X	OVER L EN	EP- PLUG BACK	DIFF. RESVR.	Other	11111		S. FARM OR		
	Resources Ehe	rgy Company.	Palcron Oil 1	Division			Balcron		ment Federal
3. ADDRESS OF OPE		<u> </u>			<del></del>		#11-7J		
	Avenue, Bill	•	•	06) 259-7860				ND POOL	, OR WILDCAT
4. LOCATION OF WE			accordance with	any State requ	irement	8)*			e/Green River
At surface	681' FNL & 4	47' FWL					11. SEC., T., OR AREA	R., M., C	R BLOCK AND SURVEY
At top prod. in	terval reported be	elow							; )CL_D17m
At total depth							Section	7, 19	5, KL/E
			14. PERMIT	NO.	DATE I	SSUED )	12. COUNTY	or	13. STATE
1			43-013-	-31492	3-7	<b>-</b> 95	Duchesne	2	Utah
15. DATE SPUDDED 5-23-95	16. DATE T.D. R	1	TE COMPL. (Read)	to prod.) 1	8. ELEV	ATIONS (DF, RKI	3, RT, GR, ETC.) *	19. E	LEV. CASINGHEAD
20. TOTAL DEPTH, MD	6-1-95	IG, BACK T.D., MD				3.2' GL			ı/a ————
5,700'	3	21' KB		MANY n/a	···	23. INTERVALS DRILLED BY		LS I	CABLE TOOLS
24. PRODUCING INTE	l i		P, BOTTOM, NAME	•	•	<del></del>	1 DIC ID	1 25	n/a . was directional
				,					SURVEY MADE
n/a									No
26. TYPE ELECTRIC DIL-CR CN	n rate of con					-		27. W	AS WELL CORED
	I-LDI-GR CE		muozo		<u> </u>	75			No
28.	WEIGHT, LB./		SING RECORD (A	eport all string	s set in	well)	a naconn		
8-5/8"	2/+//	275		:-1/4"	160		'G' w/additiv	700	None
5-1/2"	15.5#			7–7/8''	-		'G' w/additiv		
		3002					OZ w/additiv		None
						20/20	VO W/ COCCECT	<u>u</u> -	······································
29.	······································	LINER RECORI	)			30.	TUBING RECO	ORD	
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT	SCREEN (N	4D)	SIZE	DEPTH SET (M	(D)	PACKER SET (MD)
n/a					-	_2-7/8"_	4680.18'		4686.38' KB
31. PERFORATION RE	CORD (Interval, si	ze and number)	<u> </u>	1 82.	ACI	D. SHOT, FRA	CTURE, CEMEN	T GOIL	PER POR
5112' - 511	4' (4 SPF)	4784' - 47	87' (2 SPF)	DEPTH IN			AMOUNT AND KIN		<del>,</del>
5089' - 509				**5	ee Ati	tachment.	· · · · · · · · · · · · · · · · · · ·		······································
5075' - 507 4926' - 492									
4920' <b>-</b> 492 4790' <b>-</b> 479					·				
33.*	0 (2 511)		PR	ODUCTION	<del></del>	<del>!</del>			
DATE FIRST PRODUCT	ION PRODU	CCTION METHOD (	Flowing, gas lift,		and ty	pe of pump)	WELL	STATUS	(Producing or
n/a	1						<u>s</u> hu	t-in_)	WD Conversion
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL-BBL.		GAS-MCF.	WATER-BBI		GAS-OIL RATIO
FLOW, TUBING PRESS.	CASING PRESSU	I GALGULANA	<del></del>		1				
PLOW, IUDING PARGE.	CASING FRESSU	24-HOUR RA		GAS	-MCF.	WATE:	RBBL.	OIL GR	AVITY-API (CORR.)
34. DISPOSITION OF G	AB (Sold, used for	fuel, vented, etc.	<del>)</del>				TEST WITNE	SED BY	·
			•					· ·	
35. LIST OF ATTACH									
32. Acid, S	hot, Fracture	, cement Sque	eze, Etc.						
36. I hereby certify	<i>i)</i>		niormation is cor	nplete and corr Regulatory		determined from	n all available r	ecords	
SIGNED D	bbic Scho	man	TITLE .	Environment	யப. ≒த]_டு∝	acialist	DATE	8	-10-95
					vur op	الاللمست			

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity

)P	TRUE VERT. DEPTH	Surface	1452 1 3996 1 4076 1 424 1 4784 1 5074 1 5088 1 5656 1
TOP	MEAS. DEPTH	Surface	1452   2154   4076   4244   425   426   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   427   42
	NAME	Cintah	Green River Horseberch Sand 2nd Garden Gulch Y-2 Sand Y-4 Sand Yellow Marker Douglas Greek R-5 Sand 2nd Douglas Greek Green Marker G-4 Sand BSF Carborate Marker B-1 Sand B-1 Sand
DESCRIPTION, CONTENTS, ETC.			
DESCRI	180	No DST's run.	
BOTTOM			
TOP			
FORMATION			The second secon

# ATTACHMENT TO COMPLETION REPORT BALCRON MONUMENT FEDERAL #11-7J NW NW Section 7, T9S, R17E Duchesne County, Utah

	IN	T	E	R	V	AL
--	----	---	---	---	---	----

#### MATERIAL USED

5075'-5114'

Break down with 2,982 gallons 2% KCL water. with 27,660# 16/30 mesh sand with 12,684

gallons 2% KCL gelled water.

4784'-87' & 4790'-96'

Break down with 2,058 gallons 2% KCL water.

4926"-28' KB

Break down with 1,596 gallons 2% KCL water.

4784'-4928'

Frac with 22,200# 16/30 mesh sand with 15,162

gallons 2% KCL gelled water.

/mc

8-10-95

#### **ABSTRACT**

ż

An intensive cultural resource evaluation has been conducted for Balcron Oil Company of ten proposed well locations and access routes (Balcron Monument Federal wells #42-12J, 11-7J, 41-12J, 42-14J, 32-14J, 22-14J, 24-25, 34-25, 43-26 and 14-26). These evaluated locations are situated on federally administered lands located in the Monument Buttes and Pleasant Valley localities of Duchesne and Uintah Counties, Utah. This evaluation involved a total of 135.15 acres, of which 100 acres are associated with the well pads and an additional 35.15 acres are associated with access road rights-of-way. One additional well included in this report, (Monument Federal 12-7J) was previously inventoried in a forty acre intensive zone (inventory #013-163, Vernal BLM). The well pad and access road for that location have already been constructed. These evaluations were conducted by F.R. Hauck and Glade Hadden of AERC on December 15 and 20, 1994.

No previously recorded significant or National Register eligible cultural resources will be adversely affected by the proposed developments.

No newly identified cultural resource activity loci of either historic or prehistoric origin were discovered and recorded during the examinations.

Two isolated artifacts were noted during the investigations. An isolated Rose Spring style projectile point (Isolate 1461G/X1, see Figure 1) was recovered from the disturbance zone of well # 43-26 (see Map 3). A non-diagnostic biface chopping tool was discovered but not collected near the well pad for well # 42-12J. This tool is similar in appearance to others found in the area (Hauck and Hadden 1994d).

AERC recommends project clearance based on adherence to the stipulations noted in the final section of this report.

# CULTURAL RESOURCE EVALUATION OF PROPOSED WELL LOCATIONS AND ACCESS ROUTES IN THE MONUMENT BUTTES AND PLEASANT VALLEY LOCALITIES OF DUCHESNE & UINTAH COUNTIES, UTAH

Report Prepared for Balcron Oil Company

Dept. of Interior Permit No.: UT-94-54937 AERC Project 1461 (BLCR-94-11)

Utah State Project No.: UT-94-AF-775b

Principal Investigator F. Richard Hauck, Ph.D.

Authors of the Report F. Richard Hauck & Glade V Hadden



## ARCHEOLOGICAL-ENVIRONMENTAL RESEARCH CORPORATION (AERC)

181 North 200 West, Suite 5 P.O. Box 853 Bountiful, Utah 84011-0853

December 30, 1994

#### TABLE OF CONTENTS

							p	age
Abstract						•	•	ii
Table of Contents			•		•	•	•	iii
List of Maps of the Project Ar	rea			•	•	•	•	iv
General Information		•			•	•	•	1
Project Location .		•	•	•	•	ě	•	1
Environmental Descript	tion					•		6
Previous Research in the Loca	lity	•	•				•	7
File Search		•					•	7
Prehistory and History	of the	e Cultu	ral Reg	ion.	•	•		7
Site Potential in the Pro	oject ]	Develo	pment 2	Zone	•	•		7
Field Evaluations		•	•		•	•		8
Methodology			•		•	•		8
Site Significance Criter	ria		•	•	•	•	•	8
Results of the Inventor	y			•	•	•	•	9
Conclusion and Recommendat	ions			•	•		•	10
References		•	•		•	•		11

#### LIST OF MAPS OF THE PROJECT AREA

			page
MAP 1: General Balcron Project Locality in Duchesne and Uintah Counties, Utah			2
MAP 2: Cultural Resource Survey of Balcron Units 11-7J, 12-7J, 22-14J, 32-14J, 41-12J, 42-12J, and 42-14J in the Monument Buttes Locality of Duchesne County Utah	•		3
MAP 3: Cultural Resource Survey of Balcron Units 24-25, 34-25, and 43-26 in the Pleasant Valley Locality of Uintah County,	Utah	•	4
MAP 4: Cultural Resource Survey of Balcron Unit 14-26 in the Monument Buttes Locality of Duchesne County, Utah	•	•	5
LIST OF ARTIFACTS			
			page
EICUDE 1. Isolata 1/61G/v1			g

#### **GENERAL INFORMATION**

On December 15 and 20, 1994, AERC archaeologists F.R. Hauck and Glade Hadden conducted an intensive cultural resource evaluation for Balcron Oil Company of Billings, Montana. This examination involved ten proposed well locations and associated access roads (Balcron Monument Federal Units 42-12J, 11-7J, 41-12J, 42-14J, 32-14J, 22-14J, 24-25, 14-26, 34-25, 43-26 and 14-26), and an additional well (Balcron Monument Federal 12-7J which has been constructed and previously inventoried in a forty acre intensive survey zone (inventory 013-163, Vernal BLM). The project area is in the Monument Buttes and Pleasant Valley localities south east of Myton, Utah (see Map 1). Some 135.15 acres were examined which include 100 acres associated with the well pads and some 35.15 acres associated with the access routes, all of which are situated on federal lands administered by the Vernal District of the Bureau of Land Management, Diamond Mountain Resource Area, Vernal, Utah.

The purpose of the field study and this report is to identify and document cultural site presence and assess National Register potential significance relative to established criteria (cf., Title 36 CFR 60.6). The proposed development of these well locations and associated access routes requires an archaeological evaluation in compliance with U.C.A. 9-8-404, the Federal Antiquities Act of 1906, the Reservoir Salvage Act of 1960-as amended by P.L. 93-291, Section 106 of the National Historic Preservation Act of 1966-as amended, the National Environmental Policy Act of 1969, the Federal Land Policy and Management Act of 1979, the Archaeological Resources Protection Act of 1979, the Native American Religious Freedom Act of 1978, the Historic Preservation Act of 1980, and Executive Order 11593.

In addition to documenting cultural identity and significance, mitigation recommendations relative to the preservation of cultural data and materials can be directed to the Bureau of Land Management, Vernal District Office and to the State Antiquities Section.

#### Project Location

The project location is in the Monument Buttes locality of Duchesne County, and the Pleasant Valley locality of Uintah County. All of the evaluated wells and access routes are situated on the Myton SE and Pariette Draw SW 7.5 minute topographic quads (see Maps).

Balcron Monument Federal #11-7J is situated in the NW quarter of the NW quarter of Section 7, Township 9 South, Range 17 East SLBM, together with ca. 0.3 miles of access route (see Map 2).

Balcron Monument Federal #12-7J is situated in the SW quarter of the NW quarter of Section 7, Township 9 South, Range 17 East SLBM (see Map 2).

Balcron Monument Federal #41-12J is situated in the NE quarter of the NE quarter of Section 12, Township 9 South, Range 16 East SLBM, together with ca. 0.4 miles of access route (see Map 2).

MAP 1: GENERAL BALCRON PROJECT LOCALITY IN DUCHESNE AND UINTAH COUNTIES OF NORTHWESTERN UTAH 1

PROJECT: BLCR-94 - 11

SCALE:


see below

QUAD:

UG & MS Map 43

DATE:

12-30-94





T. multiple

R. multiple

UTAH P

Meridian: Salt Lake B & M


(After PHYSIOGRAPHIC SUBDIVISIONS OF UTAH by W.L. Stokes)

MAP 2: CULTURAL RESOURCE SURVEY OF BALCRON UNITS 11-7J, 12-7J, 22-14J, 32-14J, 41-12J, 42-12J, and 42-14J IN THE MONUMENT BUTTES LOCALITY OF DUCHESNE COUNTY, UTAH

PROJECT: BLCR-94-11 SCALE: 1: 24,000

> QUAD: Myton SE, Utah

DATE: 12 - 30 - 94



LEGEND:

**Existing Well Location** 9 South

Survey Plot

**Access Route** 

R. 16 East

T.

**UTAH** 

Meridian: Salt Lake B & M



MAP 3: CULTURAL RESOURCE SURVEY OF BALCRON UNITS 24-25, 34-25, and 43-26 IN THE PLEASANT VALLEY LOCALITY OF UINTAH COUNTY, UTAH PROJECT: BLCR-94-11

SCALE: 1:


1: 24,000

QUAD:

Pariette Draw SW, Utah

DATE:

12 - 30 - 94



#### LEGEND:

T. 8 South

R. 17 East

**UTAH** 

Meridian: Salt Lake B & M

**Isolated Artifact** 

**Survey Plot** 

**Access Route** 



MAP 4: CULTURAL RESOURCE SURVEY
OF BALCRON UNIT 14-26 IN THE
MONUMENT BUTTES LOCALITY OF
DUCHESNE COUNTY, UTAH

PROJECT: BLCR-94-11

SCALE: 1::


1:24,000

QUAD:

Myton SE, Utah

DATE:

12 - 30 - 94



T. 8 South

R. 16 East

Meridian: Salt Lake B & M


Existing Well Location

Survey Plot

**Access Route** 



**UTAH** 



Balcron Monument Federal #42-12J is situated in the SE quarter of the NE quarter of Section 12, Township 9 South, Range 16 East SLBM, together with ca. 0.3 miles of access route (see Map 2).

Balcron Monument Federal #22-14J is situated in the SE quarter of the NW quarter of Section 14, Township 9 South, Range 16 East SLBM, together with ca. 0.1 miles of access route (see Map 2).

Balcron Monument Federal #32-14J is situated in the SW quarter of the NE quarter of Section 14, Township 9 South, Range 16 East SLBM, together with ca. .03 miles of access route (see Map 2).

Balcron Monument Federal #42-14J is situated in the SE quarter of the NE quarter of Section 14, Township 9 South, Range 16 East SLBM, together with ca. 0.6 miles of access route (see Map 2).

Balcron Monument Federal #24-25 is situated in the SE quarter of the SW quarter of Section 25, Township 8 South, Range 17 East SLBM, together with ca. 0.1 miles of access route (see Map 3).

Balcron Monument Federal #34-25 is situated in the SW quarter of the SE quarter of Section 25, Township 8 South, Range 17 East SLBM, together with ca. 0.4 miles of access route (see Map 3).

Balcron Monument Federal #43-26 is situated in the NE quarter of the SE quarter of Section 26, Township 8 South, Range 17 East SLBM, together with ca. 0.2 miles of access route (see Map 3).

Balcron Monument Federal #14-26 is situated in the SW quarter of the SW quarter of Section 26, Township 8 South, Range 16 East SLBM, together with ca. 0.2 miles of access route (see Map 4).

#### **Environmental Description**

The project area is within the 5000 to 5500 foot elevation zone above sea level. Open rangeland terrain and eroded Eocene lakebed surfaces are associated with the project localities.

The vegetation in the project area includes Chrysothamnus spp. Artemisia spp., Sarcobatus vermiculatus, Ephedra viridis, Cercocarpus spp. Atriplex canescens, and a variety of grasses.

The geological associations within the project area consist of fluvial lake deposits which correlate with the Uinta Formation which is of Tertiary age.

#### PREVIOUS RESEARCH IN THE LOCALITY

#### File Search

A records search of the site files and maps at the Antiquities Section of the State Historic Preservation Office in Salt Lake City was conducted on December 19, 1994. A similar search was conducted in the Vernal District Office of the BLM on December 15, 1994. The National Register of Historic Places has been consulted and no registered historic or prehistoric properties will be affected by the proposed developments.

A variety of known cultural sites are situated in the Monument Buttes / Castle Peak Draw/ Eight Mile Flat/ Pariette Draw localities. Many of these prehistoric resources were identified and recorded by AERC during the Mapco River Bend survey (Hauck and Norman 1980). Other sites have been located and recorded by AERC and other archaeologists and consultants during oil and gas exploration inventories (cf. Fike and Phillips 1984, Hauck and Weder 1989).

#### Prehistory and History of the Cultural Region

Currently available information indicates that the Northern Colorado Plateau Cultural Region has been occupied by a variety of cultures beginning perhaps as early as 10,000 B.C. These cultures, as identified by their material remains, demonstrate a cultural developmental process that begins with the earliest identified Paleoindian peoples (10,000 -- 7,000 B.C.) and extends through the Archaic (ca. 7,000 B.C. -- A.D. 300), and Formative (ca. A.D. 400 -- 1100) Stages, and the Late Prehistoric-Protohistoric periods (ca. A.D. 1200 -- 1850) to conclude in the Historic-Modern period which was initiated with the incursion of the Euro-American trappers, explorers, and settlers. Basically, each cultural stage -- with the exception of the Late Prehistoric hunting and gathering Shoshonean bands -- features a more complex life-way and social order than occurred during the earlier stage of development (Hauck 1991:53). For a more comprehensive treatment of the prehistory and history of this region see Archaeological Evaluations in the Northern Colorado Plateau Cultural Area (Hauck 1991).

#### Site Potential in the Project Development Zone

Previous archaeological evaluations in the general project area have resulted in the identification and recording of a variety of cultural resource sites having eligibility for potential nomination to the National Register of Historic Places (NRHP). The majority of these sites are lithic scatters containing cobble reduction materials. Many of these quarry sites are of the "Tap and Test" variety, and extend for tens or hundreds of meters. Open occupations are also frequently being identified in this locality. Sites associated with the open rangeland generally appear to have been occupied during the Middle Plains Archaic Stage with occasional indications of Paleoindian activity based on the recovery of isolated Plano style projectile points. The north-south drainage canyons appear to contain the majority of Late Prehistoric (Numa) sites probably because those canyon floors were transportation corridors and convenient pastures for the Ute

horse herds. Evidence of Formative Stage occupation, i.e., Fremont, is rarely observed in the rangeland environment but is common within the Green River and White River canyons and their primary tributary canyons.

Site density in certain portions of the region appears to range from one to four sites per section. These densities increase in the canyon bottoms due to Ute rock art loci. Recent evaluations indicate that the site densities may reach 8 to 12 sites per section in certain localities on the upper benches which were apparently favored for hunting, lithic resource procurement, and camping. Prehistoric sites on the rangeland benches appear to be associated with water courses and aeolian deposits.

#### FIELD EVALUATIONS

#### <u>Methodology</u>

Intensive evaluations consisted of the archaeologists walking a series of 10 to 20 meterwide transects across a 10 acre area associated with each ten acre well pad area. Access routes are evaluated by the archaeologists walking a pair of 10 to 15 meter-wide transects on either side of the flagged access route rights of way. Thus, a 30 meter-wide or 100 foot-wide corridor (ca. 35.15 acres) was examined for the various proposed access roads, in addition to the 100 acres inventoried on the well pads.

Observation of cultural materials results in intensive examinations to determine the nature of the resource (isolate or activity locus). The analysis of each specific cultural site results in its subsequently being sketched, photographed, and appropriately recorded on standard IMACS forms. Cultural sites are then evaluated for significance utilizing the standards described below and mitigation recommendations are considered as a means of preserving significant resources which may be situated within the development zone.

#### Site Significance Criteria

Prehistoric and historic cultural sites which can be considered as eligible for nomination to the National Register of Historic Places have been outlined as follows in the National Register's Criteria for Evaluation as established in Title 36 CFR 60.6:

The quality of significance in American ... archaeology ... and culture is present in ... sites ... that possess integrity of location, design, setting, materials, workmanship, feeling, and association and:

- a. That are associated with events that have made a significant contribution to the broad patterns of our history; or
- b. that are associated with the lives of persons significant in our past; or
- c. that embody the distinctive characteristics of a type, period, or method of construction ...; or
- d. that have yielded, or may be likely to yield, information important in prehistory or history.

In addition to satisfying one or more of these general conditions, a significant cultural resource site in Utah will generally be considered as being eligible for inclusion in the National Register if it should advance our current state of knowledge relating to chronology, cultural relationships, origins, and cultural life ways of prehistoric or historic groups in the area.

In a final review of any site's cultural significance, the site must possess integrity and at least one of the above criteria to be considered eligible for nomination to the National Record of Historic Places.

#### Results of the Inventory

No prehistoric or historic cultural resource activity loci were observed and recorded during the archaeological evaluations.

No previously identified and recorded significant or National Register sites were noted or recorded during the survey.

One diagnostic isolated artifact was collected during the evaluation. Isolate 1461G/x1 is a Rose Spring style projectile point (see Figure 1) collected from the disturbance zone of well #43-26 (see Map 3). A detailed evaluation of the locality failed to yield any identifiable features or cultural contexts that would demonstrate the presence of an archaeological locus. A single non-diagnostic tool was noted in the area of well 42-12J. This tool was a simple chopper constructed by bifacially removing several flakes from one end of a hand-sized cobble. The occurrence of this tool fits a previously noted pattern (Hauck and Hadden 1994d), and may be related to the ambush hunting and subsequent butchering of large game animals, possibly during the Archaic period. A detailed evaluation of the locality failed to yield any identifiable features or cultural contexts that would demonstrate the presence of an archaeological locus.



FIGURE 1
Isolate 1461G/x1
(Actual Size)

#### CONCLUSION AND RECOMMENDATIONS

No known significant cultural resources will be adversely impacted during the development and operation of the Balcron Well Units as evaluated during this AERC project.

AERC recommends that a cultural resource clearance be granted to Balcron Oil Company relative to the development of these proposed drilling locations and the associated access routes based upon adherence to the following stipulations:

- 1. all vehicular traffic, personnel movement, construction and restoration operations should be confined to the flagged areas and corridors examined as referenced in this report, and to the existing roadways;
- 2. all personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area; and
- 3. the authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.

F. Richard Hauck, Ph.D.

President and Principal Investigator

#### **REFERENCES**

Fike, Richard E. and H. Blaine Phillips II

1984 "A Nineteenth Century Ute Burial from Northeast Utah." <u>Cultural Resource Series</u> No. 16, Bureau of Land Management, Salt Lake City.

Hauck, F. Richard

- Cultural Resource Inventory of Nine Proposed Well Locations and Access Roads in the Coyote Basin Locality of Uintah County, Utah, and in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Diamond Shamrock, DS-81-2, Archeological-Environmental Research Corporation, Bountiful.
- Cultural Resource Inventory of Five Proposed Well Locations and Access Roads in the Eightmile Flat and Castle Peak Localities of Uintah and Duchesne Counties, Utah. Report Prepared for Diamond Shamrock, DS-82-5, Archaeological-Environmental Research Corporation, Bountiful.
- 1984a Excavation (in) "A Nineteenth Century Ute Burial from Northeast Utah." <u>Cultural Resource Series</u> No. 16, Bureau of Land Management, (Richard E. Fike and Blaine Phillips II editors and principal authors) Salt Lake City.
- 1984b Cultural Resource Evaluations of Seven Proposed Well Locations Situated in the Castle Peak Draw Locality of Uintah County, Utah. Report Prepared for Overthrust Oil and Royalty Company, OORC-84-1, Archaeological-Environmental Research Corporation, Bountiful.
- Archaeological Evaluations on the Northern Colorado Plateau Cultural Area, AERC Paper No. 45, Archeological-Environmental Research Corporation, Bountiful.
- 1992a Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-2, Archeological-Environmental Research Corporation, Bountiful.
- 1992b Addendum to Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-4, Archeological-Environmental Research Corporation, Bountiful.

- 1992c Cultural Resource Evaluations of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-5, Archeological-Environmental Research Corporation, Bountiful.
- 1992d Cultural Resource Evaluation of a Proposed Water Pipeline Corridor in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-6, Archeological-Environmental Research Corporation, Bountiful.
- 1992e Cultural Resource Evaluation of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-8, Archeological-Environmental Research Corporation, Bountiful.
- 1993a Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-1, Archeological-Environmental Research Corporation, Bountiful.
- 1993b Addendum to Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-2, Archeological-Environmental Research Corporation, Bountiful.
- 1993c Cultural Resource Evaluation of a Pipeline Corridor Situated in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-3, Archeological-Environmental Research Corporation, Bountiful.

Hauck, F. Richard and Glade V Hadden

- 1993a Cultural Resource Evaluation of Seven Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-4, Archaeological-Environmental Research Corporation, Bountiful.
- 1993b Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-5, Archaeological-Environmental Research Corporation, Bountiful.
- 1993c Cultural Resource Evaluation of Eight Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil

- Company, BLCR-93-9, Archaeological-Environmental Research Corporation, Bountiful.
- 1993d Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-10, Archaeological-Environmental Research Corporation, Bountiful.
- 1993e Cultural Resource Evaluation of Seven Proposed Wells in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-11, Archaeological-Environmental Research Corporation, Bountiful.
- 1994a Cultural Resource Evaluation of Eight Proposed Wells in the Pleasant Valley Locality of Uintah County, Utah. Report prepared for Balcron Oil Company, BLCR-94-3 Archaeological-Environmental Research Corporation, Bountiful.
- 1994b Cultural Resource Evaluation of Proposed Water Injection Line Lateral Segments in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-94-4, Archaeological-Environmental Research Corporation, Bountiful.
- 1994c Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Pariette Draw Castle Peak Draw Eight Mile Flat Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-94-9, Archaeological-Environmental Research Corporation, Bountiful.
- 1994d Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Castle Peak Draw and Eightmile Flat Localities of Duchesne and Uintah Counties, Utah. Report Prepared for Balcron Oil Company, BLCR-94-10, Archaeological-Environmental Research Corporation, Bountiful.
- Hauck, F. Richard and Norman, V. Garth
  - 1980 Final Report on the Mapco River Bend Cultural Mitigation Study. <u>AERC Paper No. 18</u>, of the Archeological-Environmental Research Corporation, Bountiful.
- Hauck, F. Richard and Dennis Weder
  - 1989 Pariette Overlook -- A Paleo-Indian Quarry Site in the Pariette Draw Locality of Uintah County, Utah. <u>AERC Paper No. 42</u>, of the Archeological-Environmental Research Corporation, Bountiful.
- Stokes, W. L.
  - 1977 <u>Physiographic Subdivisions of Utah</u>. Map 43, Utah Geological and Mineral Survey, Salt Lake.

#### BALCRON OIL

43-013-31492Balcron Monument Federal #11-7J

NW NW Section 7, T9S, R17E, SLB&M

Duchesne County, Utah

# CONFIDENTIAL

PALEONTOLOGY REPORT

WELLPAD LOCATION AND ACCESS ROAD

BY

ALDEN H. HAMBLIN PALEONTOLOGIST 235 EAST MAIN VERNAL, UTAH 84078

DECEMBER 29, 1994

RESULTS OF PALEONTOLOGY SURVEY AT BALCRON MONUMENT FEDERAL #11-7J, NW, NW, Section 7, T9S, R17E, SLB&R, DUCHESNE COUNTY, UTAH.

Description of Geology and Topography-

This well location is approximately 10 miles south of Myton, Utah. It is located in Castle Peak Draw. The proposed access road leaves a dry hole and runs south .3 mile to the proposed wellpad. Rocks in the area are made up of layers of mudstone and sandstone. The wellpad sits on the east side on a small ridge between this ridge and Castle Peak Wash.

All rock outcrops in the area are of the Upper Eocene Uinta Formation, known for its fossil vertebrate fauna of mammals, turtles, crocodilians, and occasional fish remains and plant impressions.

Paleontological material found -

Two turtle sites were found along the proposed access road. One (A) is off the road alignment enough to be missed. The other (B) is around a small mound of reddish sandstone and mudstone in the flat area northwest of the well location. The road alignment as staked passes through this mound.

Only one small turtle shell fragment was found on the well location.


#### Recommendations-


It is recommended that the road be curved enough to the east as it approaches the mound with turtle shell material (B) so that it will pass it.

No other recommendations are made for this location and road.

Nolu H. Hamblen Date December 29, 1994

Page 1 of 1 plus map														
PALEONTOLOGY LOCALITY								State Local. No. 42 DC201V						
Data Sheet								y No.	BA	LCR	RON	MONUMENT	BU	TTE
Temp. No FEDERAL #11-7J														
1. Type of locali Invertebra		Plant		Verte	rate	е	х	Trac	е		0t	her		_
2. Formation: UINTA Horizon: Lower (B) Geologic Age: Late Eocene														
3. Description of Geology and Topography: The well is located in Castle Peak Draw. The proposed access road leaves a dry hole and runs south .3 mile to the proposed wellpad. Rocks in the area are made up of layers of mudstone and sandstone. The wellpad sits on the east side on a small ridge between this ridge and Castle Peak Wash.  All rock outcrops in the area are of the Upper Eocene Uinta Formation, known for its fossil vertebrate fauna of mammals, turtles, crocodilians, and occasional fish remains and plant impressions.														
4. Location of Ou							emain	s and p	Tant	1 mp	ress	TORS.		
	S Quad	Myton			o cu.	Т	Scal	e 7	. 5	Mi	in	Edition	T	1964
SW1/4& of SW1 NW1/4 of NW1	/4 of	SW1/4 NW1/4	01	f Sectn f Sectn	6 7		T	9 S	R	Т	6E	Merid	┸┰	SLB
6. State: UTAH	Count	y: DUCH	ESNE	COUNTY	BL	 M/I	FS D	istric	t:	VER	NAL-	- DIAMON	D M	Τ.
7. Specimens Coll	ected ar	d Field	Acc	ession I	lo.	NO	NE			•				
8. Repository:						_								
9. Specimens Obseroad. One (A) is off reddish sandstone and staked passes through	the road mudstone	alignment	enou	gh to be i	nisse	d.	The.	other (	B) i	s ar	ounc		noun	d of
10.0wner: Private	State	BLM	х	US FS	ı	NPS	5	INI	)		MI	L.	ОТН	R
11.Recommendation														
12.Type of Map Made by Recorder:														
13.Disposition of Photo Negatives:														
14.Published References: Hamblin, A. H., 1992, Paleontology Report on the Monument Butte EA Study Area, for Mariah Associates, Laramie, Wyoming.  Hamblin, A. H., 1994, Paleontology Report on the Monument Butte Expansion EA Study area, for Mariah Associates, Laramie, Wyoming.  Hamblin, A. H., 1987, Paleogeography and paleontology of the Myton Pocket, Uinta Basin, Utah (Uinta Formation - Upper Eocene): BYU Geology Studies vol. 34, no. 1, p. 33-60.														
15.Remarks:											,			<del></del>
16.Sensitivity:	Critica	1	Sig	nifican	t		Im	portar	ıt.	X	Ir	nsignifi	can ⁻	t
17.Recorded by: A	lden Ham Paleontol				Dat	te:	Dec	ember	10,	19	94			





### EQUITABLE RESOURCES CO.

BALCRON MONUMENT FEDERAL #11-7J SECTION 7, T9S, R17E, S.L.B.&M.
TOPO "B"

Land Surveying. Inc. **∆**(801) 781-2501

SCALE: 1" = 2000'

38 WEST 100 NORTH VERNAL, UTAH 84078



1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361 III

August 10, 1995

Mr. Dan Jarvis State of Utah Division of Oil, Gas and Mining 3 Triad Center, Suite 350 Salt Lake City, UT 84180

Dear Mr. Jarvis:

RE: Balcron Monument Federal #11-7J
NW NW Section 7, T9S, R17E
Duchesne County, Utah

Enclosed is our Application to convert the referenced well to injection. The Affidavit of mailing to other operators and interest owners will be sent to you shortly.

If you have questions or need additional information, please give either me or John Zellitti a call at (406) 259-7860.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

Enclosures

AUG 14 1995

#### APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR <u>Balcron Oil Division</u>

Equitable Resources Energy Company,

ADDRESS 1601 Lewis Avenue Billings. MT 59102
Well name and number: Balcron Monument Federal #11-7J
Field or Unit name: Monument Butte Field/Jonah Unit Lease no. U-44426
Well location: QQ <u>NW NW</u> section <u>7</u> township <u>9S</u> range <u>17E</u> county <u>Duchesne</u>
Is this application for expansion of an existing project? Yes [x] No []
Will the proposed well be used for: Enhanced Recovery? Yes [x] No [] Disposal? Yes [] No [x] Storage? Yes [] No [x]
Is this application for a new well to be drilled? Yes [] No [x]
If this application is for an existing well, has a casing test been performed on the well? Yes [] No [x] Date of test:  API number: 43-013-31492
Proposed injection interval: from 4784' KB to 5114' KB
Proposed maximum injection: rate <u>300 STBPD</u> pressure <u>2000</u> psig
Proposed injection zone contains & oil, [] gas, and/or [] fresh water within % mile of the well.

List of Attachments:

IMPORTANT: Additional information as required by R615-5-2 should

I certify that this report is true and complete to the best of my knowledge.

accompany this form.

Bobbie Schuman Signature Title Regulatory and Environmental Specialist Date Quaud 10, 1995
Phone No. (406) 259-7860

(State use only) Application approved by _____ __ Title Approval Date ___

Comments:

AUG 14 1995



Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

United States Environmental Protection Agency Region VIII 999 18th Street - Suite 500 Denver, CO 80202-2466 Attn: Chuck Williams 8-7-95

RE: Underground Injection Control (UIC)
Jonah Unit Waterflood
EPA Area Permit No. UT2642-0000
Duchesne County, Utah

Dear Mr. Williams,

Equitable Resources Energy Company, Balcron Oil Division received final permit approval for the Jonah Unit Section-6 Waterflood (EPA Area Permit No. UT2642-0000) located in Duchesne County, Utah in January, 1993. Balcron Oil Division is now proposing to convert the following oil production well to water injection:

Balcron Monument Federal #11-7J NW NW Section 7, T9S, R17E

This well falls within the initial area of review investigated under the EPA Area Permit No. UT2642-0000. As stated in Part II Specific Permit Conditions, Section A(2) of the subject permit, the permittee may convert and/or construct additional wells within the permitted area, provided that all additional wells meet all conditions as set forth in the permit. With this letter and the accompanying attachments, Balcron Oil Division is requesting the EPA's approval to convert the above listed well to water injection for secondary oil recovery purposes. This well will be converted to a water injection well according to the attached injection well completion diagram and the EPA Region VIII office will be notified in order that the mechanical integrity test (MIT) can be preformed and witnessed by EPA personnel.

Supporting documents are enclosed which include a well data sheet, a current wellbore completion schematic, a proposed injection well completion diagram, and a proposed plugging and abandonment diagram for the above listed well. The conversion work will be performed as soon as possible and the EPA will be contacted once this work is completed

in order for a date be set up to witness the MIT prior to commencement of injection operations. As outlined in Permit No. UT2642-0000, injection volumes will only be limited by the injection pressure of 2000 psig; however, actual volumes will only be in the 100 - 250 BWPD range. Please don't hesitate to contact me at (406)259-7860 if you have any questions or require additional information.

Respectfully,

John Jellitti John Zellitti

**Senior Production Engineer** 

**Attachments** 

Jelith.

8-9-95

!EPA Form 7520-14 (3-84)

Senior Production Engineer



WELL NAME: Balcron Monument Federal #11-7J

FIELD: Monument Butte

FEDERAL LEASE NO.: U-44426

LOCATION: NW NW Sec.7, T9S, R17E

681' FNL & 447' FWL

COUNTY/STATE: Duchesne County, Utah

WORKING INTEREST: 0.805079506 PRODUCING FORMATION: Green River

**COMPLETION DATE: 6-14-95** INITIAL PRODUCTION: Not Tested

PRESENT PROD STATUS: Waiting Conversion To Injection.

WATER INJECTION RATE:

ELEVATIONS - GROUND: 5345'

TOTAL DEPTH: 5697' KB

#### **SURFACE CASING**

SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 265' (6 jts)

DEPTH LANDED: 275' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI +

1/4#/sk celloflake

#### **TUBING RECORD**

	Length	Setting Depth
		w/ 10' KB
149 jnts 2 7/8", J-55, 6.5# Tubing	4668.33'	4678.33'
2 7/8" Seating Nipple	1.10	4679.43'
2 3/8'x 2 7/8" Cross Over	0.75'	4680.18'
Arrow Set-1 Packer	6,20'	4686.38'

Total String Length: 4676.38' Packer Landed: 4686.38' KB

Arrow Set-1 Packer set w/13" tension on 6-14-95.

Packer Fluid: 55 gals Champion Cortron-2383 mixed w/ 75 STB 2 % KCl water.

SN @ 2 7/8" x 2,25" ID

Logs: Dual Laterolog, Compensated Neutron Litho-Density, Cement Bond Log.

DATE: 8-8-95 JZ

API NO.: 43-013-31492

NET REVENUE INTEREST: 0.73831617 Oil

0.66359285 Gas

OIL GRAVITY: 34 deg SPUD DATE: 5-24-95

KB: 5355' (10' KB)

PLUG BACK TD: 5671' KB

#### PRODUCTION CASING

SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 5660.72 (143 jts) DEPTH LANDED: 5671' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 383 sxs super class "G" + (47#G + 20#Poz A +

17# CSE)/sk +3%salt + 2%gel +1/4 #/sk celloseal, tail w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk

celloseal + 2 #/sk HiSeal 2

CEMENT TOP AT: 110' KB from CBL.

#### PERFORATION RECORD

6-12-95	Schlumberger	4784'- 87'	2 SPF (.38") 3 ft	6 holes
		4790'- 96'	2 SPF (.38") 6 ft	12 holes
		4926'- 28'	2 SPF (.38") 2 ft	4 holes

6-8-95 Schlumberger

5075'- 79' 4 SPF (.38") 4 ft 16 holes 5089'- 94' 4 SPF (.38") 5 ft 20 holes 5112'- 14' 4 SPF (.38") 2 ft 8 holes

#### ACID JOB / BREAKDOWN JOB

6-8-95	BJ/Western	5075'- 5114' : 29

982 gals 2% KCI wtr w/ 100 balls, ATR 4.0 bpm, ATP 2600 psig, ISIP 1850 psig.

6-12-95 BJ/Western

4784'- 4796' : 2058 gals 2% KCI wtr w/ 2 balls/bbl, ATR 4.5 bpm, ATP 2200 psig, ISIP 1350 psig.

6-12-95 BJ/Western

4926'- 4928': 1596 gals 2% KCI wtr w/ 2 balls/bbl, ATR 3.1 bpm, ATP 4000 psig, ISIP 1950 psig.

#### FRAC JOB

6-8-95 B.I/Western 5075' - 5114' : 12,684 gals 2% KCi wtr w/ 27,660 lbs 16-30 mesh sand, ATR 34.5 bpm, ATP 2400 psig,

ISIP 2300 psig, 15 min 2060 psig.

6-12-95 BJ/Western

4784' - 4928' : 15,162 gais 2% KCl wtr w/ 22,200 lbs 16-30 mesh sand, ATR 35.1 bpm, ATP 3400 psig,

ISIP 2150 psig, 15 min 1660 psig.



ACID JOB / BREAKDOWN JOB

Balcron Monument Federal #11-7J 681' FNL & 447' FWL NW NW Sec.7, T9S, R17E Lease No. U-44426 Monument Butte Field **Duchesne County, Utah** 

Elev. - 5345' GL Elev. - 5355' KB

#### WELLBORE DIAGRAM

DATE: 8-8-95 JZ

#### SURFACE CASING

SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24# LENGTH: 265' (6 jts) DEPTH LANDED: 275' KB HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI + 1/4#/sk celloflake

275' KB

#### PRODUCTION CASING

SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15.5# LENGTH: 5660.72 (143 jts) DEPTH LANDED: 5671' KB HOLE SIZE: 7-7/8"

CEMENT DATA: 383 sxs super class "G" + (47#G + 20#Poz A + 17# CSE)/sk +3%salt + 2%gel +1/4 #/sk celloseal, tail w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk celloseal + 2 #/sk HiSeal 2

CEMENT TOP AT: 110' KB from CBL.

#### **TUBING RECORD**

	Length	Setting Depth
		w/ 10' KB
149 jnts 2 7/8", J-55, 6.5# Tbg	4668.33'	4678.33'
2 7/8" Seating Nipple	1.10'	4679.43'
2 3/8'x 2 7/8" Cross Over	0.75'	4680.18'
Arrow Set-1 Packer	6.20'	4686.38'

Total String Length: 4676.38' Packer Landed: 4686.38' KB

Arrow Set-1 Packer set w/13" tension on 6-14-95.

Packer Fluid: 55 gals Champion Cortron-2383 mixed w/ 75 STB 2 % KCl water.

SN @ 2 7/8" x 2.25" ID

Logs: Dual Laterolog, Compensated Neutron Litho-Density, Cement Bond Log.

6-8-95	BJ/Western	5075'- 5114': 2982 gals 2% KCl wtr w/ 100 balls, ATR 4.0 bpm, ATP 2600 psig, ISIP 1850 psig.	
6-12-95	BJ/Western	4784'- 4796' : 2058 gals 2% KCl wtr w/ 2 balls/bbl, ATR 4.5 bpm, ATP 2200 psig, ISIP 1350 psig.	
6-12-95	BJ/Western	4926'- 4928': 1596 gals 2% KCl wtr w/ 2 balls/bbl, ATR 3.1 bpm, ATP 4000 psig, ISIP 1950 psig.	
FRAC JO	В		
6-8-95	BJ/Western	5075' - 5114' : 12,684 gals 2% KCI wtr w/ 27,660 lbs 16-30 mesh sand, ATR 34.5 bpm, ATP 2400 psig, ISIP 2300 psig, 15 min 2060 psig.	
6-12-95	BJ/Western	4784' - 4928' : 15,162 gals 2% KCl wtr w/ 22,200 lbs 16-30 mesh sand, ATR 35.1 bpm, ATP 3400 psig, ISIP 2150 psig, 15 min 1660 psig.	
PERFOR	ATION RECORD		
6-12-95	Schlumberger	4784'- 87' 2 SPF (.38") 3 ft 6 holes 4790'- 96' 2 SPF (.38") 6 ft 12 holes	
		4926'- 28' 2 SPF (.38") 2 ft 4 holes	

Retrievable Casing Packer @ 4686' KB

4784'- 4928' KB

5075'- 5114' KB

PBTD @ 5734' KB TD @ 5800' KB



Balcron Monument Federal #11-7J NW NW Sec.7, T9S, R17E 681' FNL & 447' FWL Lease No. U-44426 Monument Butte Field Duchesne County, Utah

#### PROPOSED INJECTION WELL COMPLETION DIAGRAM

Elev. - 5345' GL

Elev. - 5355' KB (10' KB)

SURFACE CASING

SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24#

LENGTH: 265' (6 jts) DEPTH LANDED: 275' KB HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI +

1/4#/sk celloflake

275' KB

PRODUCTION CASING

SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15.5#

LENGTH: 5660.72 (143 jts) DEPTH LANDED: 5671' KB HOLE SIZE: 7-7/8"

CEMENT DATA: 383 sxs super class "G" + (47#G + 20#Poz A +

17# CSE)/sk +3%salt + 2%gel +1/4 #/sk celloseal, tail w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk

celloseal + 2 #/sk HiSeal 2 CEMENT TOP AT: 110' KB from CBL.

TUBING RECORD

SIZE / GRADE / WEIGHT: 2-7/8", J-55, 6.5# SEAT NIPPLE: 2-7/8" X 1.1' SN LANDED @ 4679' KB RETRIEVABLE CSG PACKER

MODEL: Arrow Set-1 PACKER LANDED @ 4686' KB

PERFORATION RECORD

6-12-95 Schlumberger 4784'- 87' 2 SPF (.38") 3 ft 6 holes

4790'- 96' 2 SPF (.38") 6 ft 12 holes 4926'- 28' 2 SPF (.38") 2 ft 4 holes

DATE: 8-8-95.JZ

6-8-95 Schlumberger 5075'- 79' 4 SPF (.38") 4 ft 16 holes

5089'- 94' 4 SPF (.38") 5 ft 20 holes 5112'- 14' 4 SPF (.38") 2 ft 8 holes

- Uinta Formation @ Surface to 1400'

- Green River Formation @ 1400'- 4100'

- Douglas Creek Member @ 4100'- 5350'

RETRIEVABLBE CASING PACKER @ 4686' KB

4784' - 4928' KB

5075' - 5114' KB

- Wasatch Formation Transition @ 5350'- 6000'

PBTD @ 5671' KB TD @ 5697' KB

- Wasatch Formation @ 6000'



Balcron Monument Federal #11-7J NW NW Sec.7, T9S, R17E 681 FNL & 447 FWL Lease No. U-44426 Monument Butte Field Duchesne County, Utah

#### PROPOSED PLUGGING & ABANDONMENT DIAGRAM

Elev. - 5345' GL Elev. - 5355' KB (10' KB) DATE: 8-8-95 JZ

SURFACE CASING

SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24# LENGTH: 265' (6 jts) DEPTH LANDED: 275' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI +

1/4#/sk celloflake

275' KB

Permanent P&A marker identifying well information

PLUG #2 SURFACE to 350 ft
Perforate csg at 100 ft below
the surface csg shoe & circulate
100 sx of Class-G Cement to surface.

- Uinta Formation @ Surface to 1400'

- Green River Formation @ 1400'- 4100'

PRODUCTION CASING

SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15.5# LENGTH: 5680.72 (143 jts) DEPTH LANDED: 5671' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 383 sxs super class "G" + (47#G + 20#Poz A + 17# CSE)/sk +3%salt + 2%gel +1/4 #/sk celloseal,

tail w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk

celloseal + 2 #/sk HiSeal 2

CEMENT TOP AT: 110' KB from CBL.

PERFORATION RECORD

6-12-95 Schlumberger

4784'- 87' 2 SPF (.38") 3 ft 6 holes 4790'- 96' 2 SPF (.38") 6 ft 12 holes 4926'- 28' 2 SPF (.38") 2 ft 4 holes

6-8-95 Schlumberger

5075'-79' 4 SPF (.38") 4 ft 16 holes 5089'-94' 4 SPF (.38") 5 ft 20 holes 5112'-14' 4 SPF (.38") 2 ft 8 holes

- Douglas Creek Member @ 4100'- 5350'

PLUG #1 TD to 3800 ft 260 sx of Class-G Cement

4784' - 4928' KB

5075' - 5114' KB


- Wasatch Formation Transition @ 5350'- 6000'

PBTD @ 5671' KB TD @ 5697' KB

- Wasatch Formation @ 6000'

#### PLUGGING PROCEDURE

Enter the well w/ tbg and wash to TD. If the well is not dead, circulate mud with sufficient weight to kill the well. Pump a balanced cement plug using 260 sacks across the Douglas Creek Member of the Green River Formation from TD to at least 300 ft above the upper most perfs. The production csg will be perforated for two feet using 4 SPF at a point 100 ft below the suface casing shoe. Circulation will be established to surface and cement will be circulated to fill the production casing and the annulus from the perforations to surface using 100 sacks class-G cement. The top of the second cement plug will be at the surface.



Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

August 18, 1995

Bureau of Land Management P.O. Box 45155 324 South State Street, Suite 301 Salt Lake City, Utah 84145-0155

Attention:

Mr. Robert Henricks

Chief, Bureau of Fluid Minerals

Re:

Application for Injection Well (UIC Form I)

Dear Mr. Henricks:

Equitable Resources Energy Company, Balcron Oil Division, as operator of the Balcron Monument Federal #11-7J well, is required to send a copy of UIC form I to all operators, owners and surface owners within a one-half mile radius of the proposed injection well.

Attached is a copy of our Application for Injection well (UIC Form I). The Utah Bureau of Land Management has an interest in the federal leases situated within the confines of the Jonah Unit, as indicated on the plat that accompanies this letter. This letter will serve as notification of our intentions to use the Balcron Monument Federal # 11-7J as an injection well within the confines of the Jonah Unit.

Please contact the undersigned if you have any comments or questions about this notification.

Sincerely,

D. Gary/Kabeary, CPL/ESA

Senior Landman

Enclosure

cc: Bobbie Schuman

Jonah Unit File

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

#### APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR	Equitable Resources Energy Company, Balcron Oil Division
ADDRESS	1601 Lewis Avenue
<del></del>	Billings, MT 59102

Well name and number: Balcron Monument Federal #11-7J		
Field or Unit name: Monument Butte Field/Jonah Unit Lease no. U-44426		
Well location: QQ <u>NW NW</u> section <u>7</u> township <u>9S</u> range <u>17E</u> county <u>Duchesne</u>		
Is this application for expansion of an existing project? Yes [x] No []		
Will the proposed well be used for: Enhanced Recovery? Yes [x] No [] Disposal? Yes [] No [x] Storage? Yes [] No [x]		
Is this application for a new well to be drilled? Yes [] No [x]		
If this application is for an existing well, has a casing test been performed on the well? Yes [] No [x] Date of test: API number: 43-013-31492		
Proposed injection interval: from 4784' KB to 5114' KB		
Proposed maximum injection: rate <u>300 STBPD</u> pressure <u>2000</u> psig  Proposed injection zone contains & oil, [] gas, and/or [] fresh water within % mile of the well.		
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.		
List of Attachments:		
I certify that this report is true and complete to the best of my knowledge.		
Name Bobbie Schuman Signature Bobbie Schuman Title Regulatory and Environmental Specialist Date Qual 10, 1995 Phone No. (406) 259-7860		
(State use only) Application approved by Title Approval Date		

Comments:



Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

August 21, 1995

Mr. Dan Jarvis State of Utah Division of Oil, Gas and Mining 355 West North Temple Salt Lake City, UT 84180

Dear Mr. Jarvis:

Enclosed is the Affidavit of mailing notice regarding our notice of intent to convert the Balcron Monument Federal #11-7J to injection. This was sent to all operators, owners, and surface owners within a one-half mile radius. A copy of the letter is also enclosed.

Sincerely,

Bobbie Schuman

Regulatory and

Environmental Specialist

/hs

Enclosure

#### AFFIDAVIT

COUNTY	OF	YELLOWSTONE	)
STATE	OF	MONTANA	)

D. Gary Kabeary, Senior Landman for Equitable Resources Energy Company, Balcron Oil Division, being first duly sworn on oath, deposes and says that on the 18th day of August 1995, he did cause to be mailed to all operators, owners and surface owners within a one-half mile radius of the proposed injection wells listed below, a copy of the State Application for Injection Well (UIC Form 1).

Balcron Monument Federal #11-7J NWNW of 7, T9S-R17E Duchesne County, Utah

Further affiant saith not.

D. Gary Kabeary

Subscribed and sworn to before me on this 18th day of Queguet, 1995.


My Commission Expires:

Lynda Wilson

Residing in Billings, MT 59105

SEAL

**R16E R17E** 34 35 T8S Dalen ML-22061 Dalen ML-22060 Tar Sands USA 8 UTU-72103 6 Dalen ML-21839 EREC EREC U-020252 U-64379 EREC 13 U-65208 **JONAH UNIT** Dalen 15 U-10760 EREC U-019985 11 12 19 **T9S** EREC 20 **EREC** U-64805 U-7978 21 23 22 24 17 15 14 26 EREC U-64379 Lomax U-15855




EREC 21 U-64381

**EREC** 

22 U-72105 EREC 23 U-72105 Surface Ownership Operator Map

Duchesne County, Utah August 17, 1995 Scale 1:48000





September 28, 1995

-- CERTIFIED, RETURN RECEIPT REQUESTED --

Mr. Chuck Williams (8WM-DW)
U.S. Environmental Protection Agency
Region VIII
999 - 18th Street, Suite 500
Denver, CO 80202-2466

Dear Mr. Williams:

RE: Balcron Monument Federal #11-7J 43.0/3.3/492

NW NW Section 7, T9S, R17E

Duchesne County, Utah

Our Application to convert the referenced well to injection under the Jonah Unit Section 6 Waterflood EPA Area Permit #UT2642-0000 was submitted to you August 10, 1995. That was more than 30 days ago and to date we have not had a response to that request.

In the past, it has taken as little as two weeks to approve such an action under an existing permit. I would appreciate it if you would please give us an indication of when we might receive approval of this Application.

Thank you.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

cc: R.J. Firth, Utah Division of Oil, Gas and Mining Dan Jarvis, Utah Division of Oil, Gas and Mining (UIC)



September 28, 1995



-- CERTIFIED, RETURN RECEIPT REQUESTED --

Mr. Chuck Williams (8WM-DW)
U.S. Environmental Protection Agency
Region VIII
999 - 18th Street, Suite 500
Denver, CO 80202-2466

Dear Mr. Williams:

RE: Section 2 Waterflood UIC Permit Application

Our Application to Permit the Section 2 Waterflood was submitted to your office July 26, 1995, with additional information being supplied on August 3 and August 7.

I would appreciate it if you would please give us an indication of when we might receive approval of this Application.

Thank you.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

cc: R.J. Firth, Utah Division of Oil, Gas and Mining
Dan Jarvis, Utah Division of Oil, Gas and Mining (UIC)

DIV. OF OIL, GAS & MINING

Office: (406) 259-7860 FAX: (406) 245-1365 ☐ FAX: (406) 245-1361 ☒

September 28, 1995

-- CERTIFIED, RETURN RECEIPT REQUESTED --

Mr. Chuck Williams (8WM-DW)
U.**\$**. Environmental Protection Agency
Region VIII
999 - 18th Street, Suite 500
Denver, CO 80202-2466

Dear Mr. Williams:

RE: Balcron Monument Federal #11-7J

NW NW Section 7, T9S, R17E

<u>Duchesne County, Utah</u>

Our Application to convert the referenced well to injection under the Jonah Unit Section 6 Waterflood EPA Area Permit #UT2642-0000 was submitted to you August 10, 1995. That was more than 30 days ago and to date we have not had a response to that request.

In the past, it has taken as little as two weeks to approve such an action under an existing permit. I would appreciate it if you would please give us an indication of when we might receive approval of this Application.

Thank you.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

cc: R.J. Firth, Utah Division of Oil, Gas and Mining
Dan Jarvis, Utah Division of Oil, Gas and Mining (UIC)

September 28, 1995



Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

-- CERTIFIED, RETURN RECEIPT REQUESTED --

Mr. Chuck Williams (8WM-DW)
U.S. Environmental Protection Agency
Region VIII
999 - 18th Street, Suite 500
Denver, CO 80202-2466

Dear Mr. Williams:

RE: Section 2 Waterflood UIC Permit Application

Our Application to Permit the Section 2 Waterflood was submitted to your office July 26, 1995, with additional information being supplied on August 3 and August 7.

I would appreciate it if you would please give us an indication of when we might receive approval of this Application.

Thank you.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs


cc: R.J. Firth, Utah Division of Oil, Gas and Mining
Dan Jarvis, Utah Division of Oil, Gas and Mining (UIC)

#### 143 SOUTH MAIN ST. P.O. BOX 45838 SALT LAKE CITY, UTAH 84145 FED. TAX I.D. #87-0217663



#### PROOF OF PUBLICATION

CUSTOMER'S



#### 143 SOUTH MAIN ST. P.O. BOX 45838 SALT LAKE CITY, UTAH 84145 FED. TAX I.D. # 87-0217663

## ewspaper Agency Corporated The Salt Lake Oribune (NA) DESERT NEWS

CUSTOMER'S COPY

#### PROOF OF PUBLICATION

		CUSTOMER NAME AND	ADDRESS	ACCOUNT NUMBER		
		DIV OF OIL, GAS & MIN 355 WEST NORTH TEMPLE	ING	D5385340L-07	09/29/95	
	og 1981¢ ombleg modfem A 300 Refudes bered ei beyti bredgerte molitaristu. A Bob, stillnom 01, seve eulit ei Bob, stillnom 101, seve eulit ei	3 TRIAD CENTER #350 SLC,	UT 84180	R	ECEIVE COCT 4 1995	
	Des 2 years old, 1500 (2.5) Dears old, 1500	ACCOL	UNT NAME	)VIV	OF OIL, GAS & MI	
	Dabers, \$150, CALL 392,6936 1 black male, \$200, or will out 1 black male, \$200, or will out	DIV OF OIL,	GAS & MINING	, viv.	OF VIL, GAOGINI	
	7. Video months and the control of t	TELEPHONE	INVOICE N	IUMBER		
	OG - SHAR PEL 3 years old good with klds, \$50 or best offer. Call 278-gods OG - German Shephera mix 7.	801-538-5340	TL9Q8200	201		
	NSHWASHER, stove, compactor, sink with garbage, compactor, micro-wave, \$200,0bc, 943-2012 wave, \$200,0bc, 943-9015 old, agood	SCI	HEDULE			
A TOP SHOW	Glass for Divine hear Divine Dod Dut good Divine Divine hear Divine hear	START 09/29/95 CUST.	END 09/29/95 REF. NO.			
	V Cholis, 2 leaves, \$200, 363-7273	U	IC-165		-	-
ļ	CHORING SELMOOD BLOOM SECTION	CA	PTION			
ļ	digas and maid table 4 leginal	NOTICE OF A	GENCY ACTIONCAUSE N			
Ş	DINING SET, FORM HOUSE SHABE ISBUS WITH 6 CHICAGO SACRETION CONCINON SECURITY OF THE PROPERTY	22	SIZE			
9	Thing good in the state of the	72 LINES	1.00 COLUMN RATE			
		1	1.64			
		MISC. CHARGES	AD CHAR			
		.00	118.0	8		
	_		TOTAL C	OST		
			118.0	8		

#### AFFIDAVIT OF PUBLICATION

AS NEWSPAPER AGENCY CORPORATION LEGAL BOOKKEEPER,	I CERTIFY THAT THE ATTACHED
ADVERTISEMENT OF NOTICE OF AGENCY ACTIONCAUSE N	FOR
DIV OF OIL, GAS & MINING WAS PUBLIS	SHED BY THE NEWSPAPER AGENCY
CORPORATION, AGENT FOR THE SALT LAKE TRIBUNE AND I	DESERET NEWS, DAILY NEWSPAPERS
PRINTED IN THE ENGLISH LANGUAGE WITH GENERAL CIRCU	JLATION IN UTAH, AND PUBLISHED
IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STATE O	OF UTAH.
PUBLISHED ON START 09/29/95 END 09/29/95	And the second s
SIGNATURE JOSEN Momen	MOTARY PUBLIC JOANNE MOUNTY 9626 Highford St
DATE 09/29/95	My Commission Expires March 31, 1996

#### 143 SOUTH MAIN ST. P.O. BOX 45838 SALT LAKE CITY, UTAH 84145 FED. TAX I.D. #87-0217663

### ewspaper Agency Corporation (N) DESERT NEWS

CUSTOMER'S

#### PROOF OF PUBLICATION

CUSTOMER NAME AND ADDRESS ACCOUNT NUMBER D5385340L-07 DIV OF OIL, GAS & MINING 09/29/95 355 WEST NORTH TEMPLE 3 TRIAD CENTER #350 UT 84180 SLC. OCT ACCOUNT NAME DIV OF OIL, GAS & MINING OFOIL, GAS & MININ TELEPHONE INVOICE NUMBER 801-538-5340 TL908200301 SCHEDULE START 09/29/95 END 09/29/95 NOTICE OF AGENCY ACTION CAUSE NO. UIC-164 BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES, STATE-OF UTAH CUST. REF. NO. UIC-164 CAPTION NOTICE OF AGENCY ACTIONCAUSE N SIZE 1.00 COLUMN 71 LINES TIMES RATE Notice, is hereby given that five Division is commencing an infoffinal adjusticative proceeding to consider the application of Chandler & Associates, inc. for Chandler & Associates, inc. for the Federal 31-30, and Federal 12-46 wells; located in Sections 30 and 5. Township, 8 South, Rarige-22 East, Ulintah County, Ulah, for conversion to Class II, the citier well. The proceeding will be conducted in accordance with Ulah Admin. R649-10, Administrative Procedures. 1.64 1 MISC. CHARGES AD CHARGES 116.44 .00 TOTAL COST The interval from 4746 feet to 4764 feet (Glen Bench Zone of the Green River Formation) will be selectively perforated for water Infection. The maximum 116.44 Any person desting to object to the application of otherwise in the proceeding. The proceeding must file a written protest of not vertice of intervention with the Division, within fifteen days following publication of this notice. It such a protest of the proceeding of this notice it such a protest of the proceeding of the notice of intervention with the Division, within fifteen days following publication of this notice. It such a protest or notice of intervention by the protest or notice of intervention of this notice. It such a protest or notice of intervention by the protest or notice of intervention of the notice of interven AFFIDAVIT OF PUBLICATION START 09/29/95 END 09/29/95 DATED this 21st day of Sep-BLISHED ON tember, 1995. HOTARY PUBLIC DIVISION OF OIL ON MINING //s/RJ. Firth Associate Director, Oil & Gas 99820030 GNATURE JOANNE MOONEY 2626 Hartford St. الكوروس أرسال والمراج المحمد المعدد DATE 09/291/95 My Commission Expires March 31, 1996 STATE OF UTAH

#### 143 SOUTH MAIN ST. P.O. BOX 45838 SALT LAKE CITY, UTAH 84145 FED. TAX I.D. #87-0217663

SIGNATURE

09/291/95

DATE

### ewspaper Agency Corporation (%) DESERT NEWS


PROOF OF PUBLICATION

CUSTOMER'S COPY

NOTARY PUBLIC

JOANNE MOONEY 2626 Hartford St. Mil. Lake Sity, U.S. 5-1158

My Commission Expires March 31, 1996 STATE OF UTAH



THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION"
PLEASE PAY FROM BILLING STATEMENT.

#### BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH

---00000---

IN THE MATTER OF THE APPLICATION

OF EQUITABLE RESOURCES ENERGY

COMPANY FOR ADMINISTRATIVE

APPROVAL OF THE MONUMENT FEDERAL

11-7J WELL LOCATED IN SECTION 7, TOWNSHIP 9 SOUTH, RANGE 17 EAST, S.L.M., DUCHESNE COUNTY, UTAH, AS

A CLASS II INJECTION WELL

---00000---

NOTICE OF AGENCY ACTION

CAUSE NO. UIC-165

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division is commencing an informal adjudicative proceeding to consider the application of Equitable Resources Energy Company for administrative approval of the Monument Federal 11-7J well, located in Section 7, Township 9 South, Range 17 East, Duchesne County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. R.649-10, Administrative Procedures.

The interval from 4784 feet to 5114 feet (Green River Formation) will be selectively perforated for water injection. The maximum requested injection pressure will be limited to 2000 psig with a maximum rate of 300 BWPD.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

DATED this 21st day of September, 1995.

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

Associate Director, Oil & Gas



# DIVISION OF OIL, GAS AND MINING

Governor Ted Stewart Executive Director James W. Carter Division Director 801-359-3940 (Fax) 801-538-5319 (TDD)

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax)

September 21, 1995

**Newspaper Agency Corporation** Legal Advertising Tribune Building, Front Counter 143 South Main Salt Lake City, Utah 84111

Notice of Agency Action - Cause No. UIC-165 Re:

Gentlemen:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisha Cordova Administrative Analyst

Enclosure





# State of Utah DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt Governor Ted Stewart Executive Director James W. Carter Division Director 355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

September 21, 1995

Uintah Basin Standard 268 South 200 East Roosevelt, Utah 84066

Re: Notice of Agency Action - Cause No. UIC-165

#### Gentlemen:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisha Cordova

Administrative Analyst

Lishe Cordora

**Enclosure** 



#### Equitable Resources Energy Company Monument Federal 11-7J Well Cause No. UIC-165

Publication Notices were sent to the following:

Newspaper Agency Corporation Legal Advertising Tribune Building, Front Counter 143 South Main Salt Lake City, Utah 84111

Uintah Basin Standard 268 South 200 East Roosevelt, Utah 84066

Bureau of Land Management 170 South 500 East Vernal, Utah 84078

Equitable Resources Energy Company P. O. Box 21017 Billings, Montana 59104

U.S. Environmental Protection Agency Region VIII Attn. Tom Pike 999 18th Street Denver, Colorado 80202-2466

Lisha Cordova

Administrative Analyst September 21, 1995

### DIVISION OF OIL, GAS AND MINING UNDERGROUND INJECTION CONTROL PROGRAM

### PERMIT DECISION DOCUMENT

Applicant:

Equitable Oil

Location:

Jonah Unit

Wells:

Federal 11-7J

Ownership Issues: The proposed well is located in section 7, township 9 south, range 17 east, Duchesne County, Utah. Surface ownership within the 1/2 mile area is held by the BLM and the State of Utah. The well is located on federal land. Mineral interests are held by private individuals, the State of Utah, and the federal government. Balcron Oil has submitted an affidavit stating that a copy of UIC form 1 was sent as notice to all surface owners and operators within a 1/2 mile radius of each of the proposed injection wells.

Well Integrity: The well proposed for conversion to injection has surface casing set at 275 feet, and was cemented to surface. Production casing was set at a depth of 5671 feet, and has a cement top at 110 feet, verified by a cement bond log. The interval from 4784-5114 feet (Green River Formation) will be perforated for water injection. A 2 7/8 inch tubing with a packer will be set above the perforations for injection of water. There are 4 producing wells and 4 injection wells in the 1/2 mile area of review. All wells in the AOR have sufficient cement behind the production string and have adequate surface casing to prevent migration of fluid up the hole. At the time of conversion the casing will be pressure tested. Casing/tubing annulus pressure will be monitored on a daily basis and reported on a monthly basis thereafter. Additional casing pressure tests shall be run every five years or whenever the tubing and packer assemblies are pulled for workover purposes.

**Ground Water Protection:** The base of moderately saline water in the area of the project is at a depth of approximately 300-500 feet. The injection well and offset producing wells have adequate surface casing and sufficient cement on the production casing to protect fresh water. The submitted fracture pressure for the field is .861 psi/ft resulting in a maximum allowed surface pressure of 2000 psi. Injection pressures for each of the injectors will be maintained below the fracture pressure so as not to initiate fractures in the overlying strata. The confining intervals above and below the injection zone consists of tight shales, siltstones and limestones of the Green River Formation. Water analysis indicate that the TDS of injection zone is greater than 10,000 TDS.

Oil/Gas & Other Mineral Resources Protection: Balcron is the operator of the Jonah Unit. A unit agreement was previously formed, correlative rights issues were addressed before the Board of Oil, Gas and Mining when the matter was heard.

#### Page 2 Equitable Oil

**Bonding:** Balcron is the operator of all wells within the project and is bonded by the Federal Government.

Actions Taken and Further Approvals Needed: This application is for a well in an existing waterflood unit, previously supplied data and information along with newly submitted data supports a decision to approve the wells for conversion to injection. A public notice will be published in both the Salt Lake Tribune and the Uinta Basin Standard. The applications for the injection wells are technically complete. A casing pressure test needs to be conducted when the well is converted and a casing\tubing pressure test run prior to injection. The casing tubing annulas needs to be pressured to 1000 psi. Following the 15 day comment period if no objections are received it is recommended to issue both an approval to convert the well and an injection permit. There are no special conditions or stipulations and the permit should be granted in accordance with the conditions set forth in the application.

DJJ	09-25-95	
Reviewers	Date	



# DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt Ted Stewart Executive Director James W. Carter Division Director 801-359-3940 (Fax) 801-538-5319 (TDD)

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax)

October 24, 1995

Equitable Resources Energy Company 1601 Lewis Avenue Billings, MT 59102

Monument Federal 11-7J Well, Section 7, Township 9 South, Range 17 East, Re:

Duchesne County, Utah

#### Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

- Compliance with all applicable requirements for the operation, maintenance 1. and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
- Conformance with all conditions and requirements of the complete 2. application submitted by Equitable Resources Energy Company ("Equitable").

If you have any questions regarding this approval or the necessary requirements, please contact Dan Jarvis at this office.

Sincerely.

Associate Director

Debra G. Ehlert, Environmental Protection Agency cc: Bureau of Land Management, Vernal





# DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt Governor Ted Stewart **Executive Director** James W. Carter Division Director 801-359-3940 (Fax) 801-538-5319 (TDD)

355 West North Temple 3 Triad Center, Suite 350 Sait Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax)

#### UNDERGROUND INJECTION CONTROL PERMIT

Cause No. UIC-165

Operator:

Equitable Resources Energy Company

Well:

Monument Federal 11-7J

Location:

Section 7, Township 9 South, Range 17 East,

Duchesne County

API No.:

43-013-31492

Well Type:

Enhanced Recovery (waterflood)

#### Stipulations of Permit Approval

- Approval for conversion to injection well issued on 1. October 24, 1995.
- Maximum Allowable Injection Pressure: 2000 psig. 2.
- Maximum Allowable Injection Rate: 300 bwpd. 3.
- Injection Interval: 4,784 feet to 5114 feet (Green 4. River Formation)

Approved by:

Associate Director, Oil and Gas

Form 3160-5 (June 1990)

FORM APPROVED Budget Bureau No. 1004-0135

	1 01 1112 11146360   00   20   1333	Expires: March 31, 1993
BUREAU OF	LAND MANAGEMENT	5. Lease Designation and Serial No.
	The state of the s	U-44426
	AND REPORTS ON WELLS GAS & MINING	6. If Indian, Allottee or Tribe Name
Do not use this form for proposals to dr Use "APPLICATION FO	ill or to deepen or <b>Perfet</b> to a different reservoir. R PERMIT—" for such proposals	n/a
	THE TRIPLICATE	7. If Unit or CA, Agreement Designation
	IN TRIPLICATE	Jonah Unit
1. Type of Well Oil Gas X Other injectio	n	8. Well Name and No.
2. Name of Operator		Balcron Monument Fed. #11-7J
•	Company, Balcron Oil Division	9. API Well No.
3. Address and Telephone No.		43-013-31492
1601 Lewis Avenue; Billing	s, MT 59102 (406) 259-7860	10. Field and Pool, or Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey D	escription)	Monument Butte/Green River
NW NW Section 7, T9S, R17E	11. County or Parish, State	
681' FNL, 447' FWL		Ducksons County UT
		Duchesne County, UT
12. CHECK APPROPRIATE BOX(	s) TO INDICATE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
Notice of Intent	Abandonment	Change of Plans
	Recompletion ·	New Construction
X Subsequent Report	Plugging Back	Non-Routine Fracturing
•	Casing Repair	Water Shut-Off
Final Abandonment Notice	Altering Casing	Conversion to Injection
,	Other <u>archy/paleo reports</u>	Dispose Water (Note: Report results of multiple completion on Well
· ·		Completion or Recompletion Report and Log form.)
13. Describe Proposed or Completed Operations (Clearly state a give subsurface locations and measured and true verti	Il pertinent details, and give pertinent dates, including estimated date of starting cal depths for all markers and zones pertinent to this work.)*	any proposed work. If well is directionally drilled
Attached are copies of the a	rchaeological and paleontological repo	rts which were

prepared for the water line for this well.

## CONFIDENTIAL

ORIGINAL: Bureau of Land Management (Vernal, UT) COPY: Utah Division of Oil, Gas and Mining

14. I hereby certify that the foregoing is true and correct Signed Schuman	Regulatory and Title Environmental Specialist	Date October 24, 1995
(This space for Federal or State office use)		D
Approved by	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

#### BALCRON OIL

MONUMENT BUTTE

LATERAL WATER LINE TO

BALCRON MONUMENT FEDERAL #11-7J

NWNW SECTION 11, 9S, R16E, SLB&M

DUCHESNE COUNTY, UTAH

PALEONTOLOGY REPORT

ΒY

ALDEN H. HAMBLIN PALEONTOLOGIST 235 EAST MAIN VERNAL, UTAH 84078

OCTOBER 16, 1995

RESULTS OF A PALEONTOLOGY SURVEY ON THE LATERAL WATER LINE TO BALCRON MONUMENT FEDERAL 11-7J, NWNW SECTION 11, T9S, R16E, DUCHESNE COUNTY, UTAH.

Description of Geology and Topography

The geological formation exposed at the surface in the study area is the Upper Eccene Uinta Formation. Environments of deposition vary from lacustrian to fluvial. The Uinta Formation is ranked number one on the vertebrate fossil list of paleontological sensitive strata in Utah by the State Paleontologist. It is also listed number 15 on the invertebrate list and number 4 on the trace fossil list. More than 70 genera of fish, reptiles and mammals are known from The mammalian fauna from the Uinta Formation is the basis for the designation of the Uintan North American Land Mammal Age. the Uinta Formation.

The most common vertebrate fossils from the Uinta Formation are turtles. In some areas numerous turtles can be seen eroding out of the formation. Because they are so numerous, their protection is not quite as critical as protection of fossil mammals when they are encountered in the formation. However, the presence of turtles indicates that the environment was right for fossilization, and quite often, fossil mammal material is found associated with fossil turtle shells. Therefore, the potential for finding fossil mammal bones is fairly high where there are abundant turtles.

Balcron Monument Federal #11-7J is located in Castle Peak Draw approximately 10 miles south of Myton, Utah. Rocks in the area are made up of layers of mudstone and sandstone. The proposed pipeline runs northwest up out of Castle peak Draw from 11-7J, then west to 41-12J.

Paleontological material found -

No new fossils were found during the current survey. However a fossil site (42DC201V) was identified during the survey of the access road to well 11-7J. Originally, the road to #11-7J was moved slightly east to avoid this site. Subsequently, it appears that a caterpillar was unloaded there and the site was partially damaged.


#### Recommendations

It is recommended that after the trench has been opened through this site, that the trench and spoil pile be examined by a paleontologist for fossil material.

There is always the possibility of encountering significant fossil material when ever working in the Uinta Formation. If significant looking fossil bone material is found during construction, a paleontologist should be called to evaluate it.

mblu

October 16, 1995 DATE



#### PALEONTOLOGY LOCALITY

Data Sheet

of plus map Page

State Local. No.

42 DC201V

BALCRON MONUMENT BUTTE Agency No.

Temp.	No	FEDERAL #11-	7 J

						Other			
1.	Type of locality Invertebrate	٠	Plant	Vertebrate	X	Trace			
	Formation: UINTA	Hori	zon: Lower (B)	)	Geologic Age: Late Eocene				

3. Description of Geology and Topography: The well is located in Castle Peak Draw. The proposed access road leaves a dry hole and runs south .3 mile to the proposed wellpad. Rocks in the area are made up of layers of mudstone and sandstone. The wellpad sits on the east side on a small ridge between this ridge and Castle Peak Wash.

All rock outcrops in the area are of the Upper Eccene Uinta Formation, known for its fossil vertebrate fauna of mammals, turtles, crocodilians, and occasional fish remains and plant impressions.

4. Location of Outcrop: 10 miles south of Myton, Utah.

5 Map Ref. USGS Quad		Myton S	Myton SE, Utah			e 7	7.5		Edition	1964
5. Map Ref. SW1/4& of NW1/4 of	SW1/4 of NW1/4 of	SW1/4	of Sectn of Sectn	6 7	Т	9 S	R	16E	Meridn	SLB

County: DUCHESNE COUNTY | BLM/FS District: VERNAL- DIAMOND MT. 6. State: UTAH

7. Specimens Collected and Field Accession No. NONE

8. Repository:

Two turtle sites were found along the proposed access 9. Specimens Observed and Disposition: road. One (A) is off the road alignment enough to be missed. The other (B) is around a small mound of reddish sandstone and mudstone in the flat area northwest of the well location. The road alignment as staked passes through this mound.

Staked passes t	111.00			1 1	1 I		<b>.</b>	1 1	ì	
40 Ownor!		<b>i</b> i	US	1 1	1	TAID	MIL	'	OTHR	l
10.Owner:	1 0	BLM	X FS	I NPS	1 .1	IND	1 11111		0,,,,,	
Private	State	DLIII	<u> </u>		<u> </u>					

11.Recommendations for Further Work or Mitigation: It is recommended that the road be curved enough to the east as it approaches the mound with turtle shell material (B) so that it will pass it.

12. Type of Map Made by Recorder:

13. Disposition of Photo Negatives:

14. Published 'References: Hamblin, A. H., 1992, Paleontology Report on the Monument Butte EA Study Area, for Mariah Associates, Laramie, Wyoming.

Hamblin, A. H., 1994, Paleontology Report on the Monument Butte Expansion EA Study area, for Mariah Hamblin, A. H., 1987, Paleogeography and paleontology of the Myton Pocket, Uinta Basin, Utah (Uinta Associates, Laramie, Wyoming.

Formation - Upper Eccene): BYU Geology Studies vol. 34, no. 1, p. 33-60.


15.Remarks:

Insignificant Important X Significant Critical 16.Sensitivity:

17. Recorded by: Alden Hamblin,

**Paleontologist** 

Date: December 10, 1994



#### CULTURAL RESOURCE EVALUATION

#### OF A PROPOSED WATER RETURN PIPELINE ROUTE

#### FOR UNIT 11-71

# IN THE CASTLE PEAK DRAW LOCALITY OF DUCHESNE COUNTY, UTAH

Report Prepared for Balcron Oil Division

Dept. of Interior Permit No.: UT-95-54937 AERC Project 1503 (BLCR-95-7B)

Utah State Project No.: UT-95-AF-0560b

Principal Investigator F. Richard Hauck, Ph.D.

Author of the Report F. Richard Hauck



### ARCHEOLOGICAL-ENVIRONMENTAL RESEARCH CORPORATION (AERC)

181 North 200 West, Suite 5 P.O. Box 853 Bountiful, Utah 84011-0853

October 16, 1995

#### **ABSTRACT**

An intensive cultural resource evaluation has been conducted for Balcron Oil Division of a water return pipeline route for Unit 11-7J situated on federally administered lands located in the Castle Peak Draw locality of Duchesne County, Utah. This evaluation involved a total of 2.4 acres. These evaluations were conducted by F. Richard Hauck and Michael Hauck of AERC on September 27-29, 1995.

No previously recorded significant or National Register eligible cultural resources will be adversely affected by the proposed developments.

No newly identified prehistoric cultural resource activity loci were discovered and recorded during the examinations.

No isolated artifacts were noted during the investigations.

AERC recommends project clearance based on adherence to the stipulations noted in the final section of this report.

#### TABLE OF CONTENTS

							page
Abstract			•			•	ii
Table of Contents			•				iii
List of Maps of the Project Area			•		•		iv
General Information .			•	•	•	•	1
Project Location .		•	•		•	•	1
Environmental Description				•			1
Previous Research in the Locality		•	•		•	•	4
File Search			•			•	4
Prehistory and History of the	he Cu	ltural R	egion			•	4
Site Potential in the Project	t Deve	elopmen	t Zone	•	• .	. •	4
Field Evaluations	•	•	•	•	•	•	5
Methodology		•					5
Site Significance Criteria	•	•					5
Results of the Inventory							6
Conclusion and Recommendations			•	٠		•	6
Dafaranças							7

## LIST OF MAPS OF THE PROJECT AREA

						page
MAP 1: General Project Locality in Duchesne County. Utah						2
MAP 2: Cultural Resource Survey of Pipeline Corridor for Unit 11- Locality of Duchesne County,	7J in the (	Castle P	Peak Dra	aw		3

#### **GENERAL INFORMATION**

On September 27 through 29, 1995, AERC archaeologists F. Richard Hauck and Michael Hauck conducted an intensive cultural resource evaluation for Balcron Oil Division of Billings Montana. This examination involved the proposed 1100 foot-long water return pipeline route for Unit 11-7J in the Castle Peak Draw locality south east of Myton, Utah (see Map 1). A total of 2.4 acres was examined on federal lands administered by the Vernal District of the Bureau of Land Management, Diamond Mountain Resource Area, Vernal, Utah.

The purpose of the field study and this report is to identify and document cultural site presence and assess National Register potential significance relative to established criteria (cf., Title 36 CFR 60.6). The proposed development of these pipeline routes requires an archaeological evaluation in compliance with U.C.A. 9-8-404, the Federal Antiquities Act of 1906, the Reservoir Salvage Act of 1960-as amended by P.L. 93-291, Section 106 of the National Historic Preservation Act of 1966-as amended, the National Environmental Policy Act of 1969, the Federal Land Policy and Management Act of 1979, the Archaeological Resources Protection Act of 1979, the Native American Religious Freedom Act of 1978, the Historic Preservation Act of 1980, and Executive Order 11593.

In addition to documenting cultural identity and significance, mitigation recommendations relative to the preservation of cultural data and materials can be directed to the Bureau of Land Management, Vernal District Office and to the State Antiquities Section.

## **Project Location**

The project location is in the Castle Peak Draw locality of Duchesne County, Utah. The evaluated .2 mile-long pipeline corridor is situated on the Myton SE 7.5 minute topographic quad (see Map 2).

### **Environmental Description**

The project area is at the 5350 to 5450 foot elevation zone above sea level. Open rangeland terrain and eroded Eocene lakebed surfaces are associated with the project localities.

The vegetation in the project area includes Chrysothamnus spp., Artemisia spp., Sarcobatus vermiculatus, Ephedra viridis, Cercocarpus spp. Atriplex canescens, and a variety of grasses.

The geological associations within the project area consist of fluvial lake deposits which correlate with the Uinta Formation which is of Tertiary age.

MAP 1: GENERAL PROJECT LOCALITY IN DUCHESNE COUNTY, UTAH


PROJECT: BLCR - 95 - 7B

SCALE: see below

QUAD: UG & MS Map 43

DATE:

October 16, 1995





T. multiple .....

R_s multiple

Meridian: Salt Lake B. & M.

(after PHYSIOGRAPHIC SUBDIVISIONS OF UTAH by W.L. Stokes)

MAP 2: CULTURAL RESOURCE SURVEY
OF BALCHON PIPELINE CORRIDOR FOR
UNIT 11-7J IN THE CASTLE PEAK DRAW
LOCALITY OF DUCHESNE COUNTY,
UTAH

PROJECT: BLCR - 95 - 78


SCALE: 1:24,000

Myton SE, Utah

DATE:

QUAD:

October 16, 1995



UTAH

T. 9 South

R. 16 & 17 East

Meridian: Salt Lake B. & M.

LEGEND:

Well Location

Access Route

**Cultural Site** 

Ten Acre Survey

Area

Pipeline

## PREVIOUS RESEARCH IN THE LOCALITY

#### File Search

A records search of the site files and maps at the Antiquities Section of the State Historic Preservation Office in Salt Lake City was conducted on June 16, 1995. A similar search was conducted in the Vernal District Office of the BLM on September 28, 1995. The National Register of Historic Places has been consulted and no registered historic or prehistoric properties will be affected by the proposed developments.

A variety of known cultural sites are situated in the Monument Buttes / Castle Peak Draw locality. Many of these prehistoric resources were identified and recorded by AERC during the Mapco River Bend survey (Hauck and Norman 1980). Other sites have been located and recorded by AERC and other archaeologists and consultants during oil and gas exploration inventories (cf. Fike and Phillips 1984, Hauck and Weder 1989, Hauck and Hadden 1993, 1994).

## Prehistory and History of the Cultural Region

Currently available information indicates that the Northern Colorado Plateau Cultural Region has been occupied by a variety of cultures beginning perhaps as early as 10,000 B.C. These cultures, as identified by their material remains, demonstrate a cultural developmental process that begins with the earliest identified Paleoindian peoples (10,000 -- 7,000 B.C.) and extends through the Archaic (ca. 7,000 B.C. -- A.D. 300), and Formative (ca. A.D. 400 -- 1100) Stages, and the Late Prehistoric-Protohistoric periods (ca. A.D. 1200 -- 1850) to conclude in the Historic-Modern period which was initiated with the incursion of the Euro-American trappers, explorers, and settlers. Basically, each cultural stage -- with the exception of the Late Prehistoric hunting and gathering Shoshonean bands -- features a more complex life-way and social order than occurred during the earlier stage of development (Hauck 1991:53). For a more comprehensive treatment of the prehistory and history of this region see Archaeological Evaluations in the Northern Colorado Plateau Cultural Area (Hauck 1991).

## Site Potential in the Project Development Zone

Previous archaeological evaluations in the general project area have resulted in the identification and recording of a variety of cultural resource sites having eligibility for potential nomination to the National Register of Historic Places (NRHP). The majority of these sites are lithic scatters containing cobble reduction materials. Many of these quarry sites are of the "Tap and Test" variety, and extend for tens or hundreds of meters. Open occupations are also frequently being identified in this locality. Sites associated with the open rangeland generally appear to have been occupied during the Middle Plains Archaic Stage with occasional indications of Paleoindian activity based on the recovery of isolated Plano style projectile points. The north-south drainage canyons appear to contain the majority of Late Prehistoric (Numa) sites probably because those canyon floors were transportation corridors and convenient pastures for the Ute

horse herds. Evidence of Formative Stage occupation, i.e., Fremont, is rarely observed in the rangeland environment but is common within the Green River and White River canyons and their primary tributary canyons.

Site density in certain portions of the region appears to range from one to six sites per section. These densities increase in the canyon bottoms due to Ute rock art loci. Recent evaluations indicate that the site densities may reach 8 to 12 sites per section in certain localities on the upper benches which were apparently favored for hunting, lithic resource procurement, and camping. Prehistoric sites on the rangeland benches appear to be associated with water courses and aeolian deposits.

## FIELD EVALUATIONS

### Methodology

Intensive evaluations consisted of the archaeologist walking a series of 10 to 20 meterwide transects associated with the flagged pipeline corridor examined to a 100' or 30 meter width.

Observation of cultural materials results in intensive examinations to determine the nature of the resource (isolate or activity locus). The analysis of each specific cultural site results in its subsequently being sketched, photographed, and appropriately recorded on standard IMACS forms. Cultural sites are then evaluated for significance utilizing the standards described below and mitigation recommendations are considered as a means of preserving significant resources which may be situated within the development zone.

## Site Significance Criteria

Prehistoric and historic cultural sites which can be considered as eligible for nomination to the National Register of Historic Places have been outlined as follows in the National Register's Criteria for Evaluation as established in Title 36 CFR 60.6:

The quality of significance in American ... archaeology ... and culture is present in ... sites ... that possess integrity of location, design, setting, materials, workmanship, feeling, and association and:

- a. That are associated with events that have made a significant contribution to the broad patterns of our history; or
- b. that are associated with the lives of persons significant in our past; or
- c. that embody the distinctive characteristics of a type, period, or method of construction ...; or
- d. that have yielded, or may be likely to yield, information important in prehistory or history.

In addition to satisfying one or more of these general conditions, a significant cultural resource site in Utah will generally be considered as being eligible for inclusion in the National Register if it should advance our current state of knowledge relating to chronology, cultural relationships, origins, and cultural life ways of prehistoric or historic groups in the area.

In a final review of any site's cultural significance, the site must possess integrity and at least one of the above criteria to be considered eligible for nomination to the National Record of Historic Places.

### **Results of the Inventory**

No newly identified prehistoric cultural resource activity loci were observed and recorded during the archaeological evaluation.

No previously identified and recorded significant or National Register sites were noted during the survey; Balcron's proposed development of the water return pipeline for Unit 11-7J will not have any adverse effect on existing known cultural resources situated in this locality.

No diagnostic or non-diagnostic isolated artifacts were observed or recorded during the evaluation.

## CONCLUSION AND RECOMMENDATIONS

No known significant cultural resources will be adversely impacted during the development and operation of Balcron's water return pipeline for Unit 11-7J as identified in this report.

AERC recommends that a cultural resource clearance be granted to Balcron Oil Division relative to the development of this proposed water return pipeline based upon adherence to the following stipulations:

all vehicular traffic, personnel movement, construction and restoration operations should be confined to the flagged areas and corridors examined as referenced in this report, and to the existing roadways;

2. all personnel should refrain from collecting artifacts and from disturbing any

significant cultural resources in the area; and

3. the authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.

F. Richard Hauck, Ph.D.

President and Principal Investigator

### **REFERENCES**

Fike, Richard E. and H. Blaine Phillips II

"A Nineteenth Century Ute Burial from Northeast Utah." <u>Cultural Resource Series</u>
 No. 16, Bureau of Land Management, Salt Lake City.

### Hauck, F. Richard

- Cultural Resource Inventory of Nine Proposed Well Locations and Access Roads in the Coyote Basin Locality of Uintah County, Utah, and in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Diamond Shamrock, DS-81-2, Archeological-Environmental Research Corporation, Bountiful.
- Cultural Resource Inventory of Five Proposed Well Locations and Access Roads in the Eightmile Flat and Castle Peak Localities of Uintah and Duchesne Counties, Utah. Report Prepared for Diamond Shamrock, DS-82-5, Archaeological-Environmental Research Corporation, Bountiful.
- 1984a Excavation (in) "A Nineteenth Century Ute Burial from Northeast Utah." <u>Cultural Resource Series</u> No. 16, Bureau of Land Management, (Richard E. Fike and Blaine Phillips II editors and principal authors) Salt Lake City.
- 1984b Cultural Resource Evaluations of Seven Proposed Well Locations Situated in the Castle Peak Draw Locality of Uintah County, Utah. Report Prepared for Overthrust Oil and Royalty Company, OORC-84-1, Archaeological-Environmental Research Corporation, Bountiful.
- Archaeological Evaluations on the Northern Colorado Plateau Cultural Area, AERC Paper No. 45, Archeological-Environmental Research Corporation, Bountiful.
- 1992a Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-2, Archeological-Environmental Research Corporation, Bountiful.
- 1992b Addendum to Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-4, Archeological-Environmental Research Corporation, Bountiful.

- 1992c Cultural Resource Evaluations of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-5, Archeological-Environmental Research Corporation, Bountiful.
- 1992d Cultural Resource Evaluation of a Proposed Water Pipeline Corridor in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-6, Archeological-Environmental Research Corporation, Bountiful.
- 1992e Cultural Resource Evaluation of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-8, Archeological-Environmental Research Corporation, Bountiful.
- 1993a Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-1, Archeological-Environmental Research Corporation, Bountiful.
- 1993b Addendum to Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-2, Archeological-Environmental Research Corporation, Bountiful.
- 1993c Cultural Resource Evaluation of a Pipeline Corridor Situated in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-3, Archeological-Environmental Research Corporation, Bountiful.

## Hauck, F. Richard and Glade V Hadden

- 1993a Cultural Resource Evaluation of Seven Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-4, Archaeological-Environmental Research Corporation, Bountiful.
- 1993b Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-5, Archaeological-Environmental Research Corporation, Bountiful.

- 1993c Cultural Resource Evaluation of Eight Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-9, Archaeological-Environmental Research Corporation, Bountiful.
- 1993d Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-10, Archaeological-Environmental Research Corporation, Bountiful.
- 1993e Cultural Resource Evaluation of Seven Proposed Wells in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-11, Archaeological-Environmental Research Corporation, Bountiful.
- 1994a Cultural Resource Evaluation of Eight Proposed Wells in the Pleasant Valley Locality of Uintah County, Utah. Report prepared for Balcron Oil Company, BLCR-94-3 Archaeological-Environmental Research Corporation, Bountiful.
- 1994b Cultural Resource Evaluation of Proposed Water Injection Line Lateral Segments in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-94-4, Archaeological-Environmental Research Corporation, Bountiful.
- 1994c Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Pariette Draw Castle Peak Draw Eight Mile Flat Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-94-9, Archaeological-Environmental Research Corporation, Bountiful.
- 1994d Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Castle Peak Draw and Eight Mile Flat Localities of Duchesne and Uintah Counties, Utah. Report Prepared for Balcron Oil Company, BLCR-94-10, Archaeological-Environmental Research Corporation, Bountiful.
- 1994e Cultural Resource Evaluation of Two Proposed Balcron Monument State Well Locations and Access Routes in the Castle Peak Draw Locality of Uintah County, Utah. Report Prepared for Balcron Oil Company, BLCR-94-10b, Archaeological-Environmental Research Corporation, Bountiful.
- 1994f Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report Prepared for Balcron Oil Company, BLCR-94-11, Archaeological-Environmental Research Corporation, Bountiful.

## Hauck, F. Richard and Norman, V. Garth

Final Report on the Mapco River Bend Cultural Mitigation Study. <u>AERC Paper No. 18</u>, of the Archeological-Environmental Research Corporation, Bountiful.

## Hauck, F. Richard and Dennis Weder

Pariette Overlook -- A Paleo-Indian Quarry Site in the Pariette Draw Locality of Uintah County, Utah. <u>AERC Paper No. 42</u>, of the Archeological-Environmental Research Corporation, Bountiful.

## Stokes, W. L.

1977 <u>Physiographic Subdivisions of Utah</u>. Map 43, Utah Geological and Mineral Survey, Salt Lake.

	UNITED STATES RTMENT OF THE INTERIOR U OF LAND MANAGEMENT	FORM APPROVED Budget Bureau No. 1004-0135 Expires: March 31, 1993  5. Lease Designation and Serial No.
Do not use this form for proposal	TICES AND REPORTS ON WELLS s to drill or to deepen or reentry to a different DN FOR PERMIT—" for such proposals	reservoir.  U-44426  6. If Indian, Allottee or Tribe Name  n/a
	JBMIT IN TRIPLICATE	7. If Unit or CA, Agreement Designation  Jonah Unit
1. Type of Well  Oil Well Well Well  Other  Inje	ction	8. Well Name and No.  Moriument Fed. #11-7J
•	y Company, Balcron Oil Division	9. API Well No. 43-013-31492
1601 Lewis Avenue, Billing 4. Location of Well (Footage, Sec., T., R., M., or NW NW Section 7, T9S, R17 681' FNL & 447' FWL	Survey Description)	
12. CHECK APPROPRIATE	BOX(s) TO INDICATE NATURE OF NOTIC	
TYPE OF SUBMISSION	TYPE (	OF ACTION
Notice of Intent  Subsequent Report	Abandonment Recompletion Plugging Back	Change of Plans New Construction Non-Routine Fracturing
Final Abandonment Notice	Casing Repair Altering Casing  Other Started Inject	(Note: Report results of multiple completion on Well
	rly state all pertinent details, and give pertinent dates, including estimate true vertical depths for all markers and zones pertinent to this work.)	
Operator started injectin water per day at 10:00 a.	g water into this well at an inject m. 2-26-96.	tion rate of 130 barrels of
	•	

Signed Molly Comach	Tille Operations Secretary	Date 3-1-96
(This space for Federal of State office use)  Approved by  Conditions of approval, if any:	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Form 3160-5 (June 1990)	DEPARTME	TED STATES IT OF THE INTERIOR LAND MANAGEMENT	FORM APPROVED Budget Bureau No. 1004-0135 Expires: March 31, 1993  5. Lease Designation and Serial No.
Do not use this f	orm for proposals to di	AND REPORTS ON WELLS  III or to deepen or reentry to a different rese R PERMIT—" for such proposals	rvolr.  U-44426  6. If Indian, Allottee or Tribe Name  n/a
	SUBMIT	IN TRIPLICATE	7. If Unit or CA. Agreement Designation  Jonah Unit
1. Type of Well Oil Gas Well Well	X Other Injection		8. Well Name and No.
2. Name of Operator Equitable Res	sources Energy Com	pany, Balcron Oil Division	Monument Fed. #11-7J 9. API Well No.
	venue, Billings,MI		43-013-31492 10. Field and Pool, or Exploratory Area
	ge, Sec., T., R., M., or Survey D n 7, T9S, R17E 47' FWL	escription)	Monument Butte/Green River
			Duchesne County, Utah
12. CHECK	APPROPRIATE BOX(	s) TO INDICATE NATURE OF NOTICE, R	EPORT, OR OTHER DATA
TYPE OF	SUBMISSION	TYPE OF AC	CONTRACTOR
Notice of Subsequ	of Intent	Abandonment Recompletion Plugging Back	Change of Plans New Construction Non-Routine Fracturing
Final A	bandonment Notice	Casing Repair Altering Casing X Other Started Injection	(Note: Report results of multiple completion on Well
give subsurface loc Operator star water per day	ations and measured and true vertice ted injecting wat rat 10:00 a.m. 2-	pertinent details, and give pertinent dates, including estimated date of all depths for all markers and zones pertinent to this work.)*  er into this well at an injection 26-96.	
14. I hereby certify that the Signed Moll	foregoing is true and correct	Title Operations Secretary	Date 3-1-96
(This space for Federal	of State office use)		

Tide 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.


Date_

Title ___

Approved by ________ Conditions of approval, if any:



1601 Lewis Avenue Billings, MT 59102



March 1, 1996

Bureau of Land Management Vernal District Office 170 Soutb 500 East Vernal, UT 84078

Gentlemen:

RE:

Balcron Monument Federal #11-71

NW NW Section 7, T9S, R17E

Duchesne County, Utah

Enclosed is our sundry reporting that Equitable Resources Energy Company, Balcron Oil Division started injecting water into this well on 2-26-96. I have also included a copy of the Well Rework Record and MIT that was submitted to the Environmental Protection Agency.

Please feel free to contact me if you require any additional information.

Sincerely,

Molly Conrad

**Operations Secretary** 

/mc

**Enclosures** 

cc:

Utah Division of Oil, Gas, & Mining

Bobbie Schuman

4			UNITED STATES				NCY.	
<b>⊕</b> EP/	Δ			VASHINGTON REWOR		ECORD		
	RESS OF PERMIT	TEE .	***************************************				OF CONTRACTOR	
Eaunitab	1e Resou	rces En	erosy Com	pany		~no~		NICE
Balcon		vision we	•		•		1335 Utah 84	2 - 7 - 2
1601 Leu Billings		59102	STATE	COUNTY	<u>۷</u> ور	m~1 1	UTAN 8	1018
LOCATE W	ELL AND OUTLINE	E UNIT ON	Vtah		- h - c	ine 6		PERMIT NUMBER
SECTI	ON PLAT 640 A	CRES	SURFACE LO				<u>unij</u>	VT 2642 - 0000
	N		NW 14 0				ECTION 7 T	OWNSHIP 9 S RANGE 17 E
			LOCATE WEL	L IN TWO DII	RECTION	IS FROM NEAR	EST LINES OF QUAR	ITER SECTION AND DRILLING UNIT
<del>                                    </del>		<del>-  </del>	Surface Location 6	<u>81</u> ft. from (f	N/S)_N	Line of quart	er section	
			and 447 ft	t. from (E/W)	W_LI	ne of quarter se	ection	
<del>  -</del>		<del></del>	WELL	ACTIVITY		Total Depth	Before Rework	TYPE OF PERMIT
	! ] !	! ! ! .	☐ Brine Di	sposal		56-	11' KB	☐ Individual
W		<del>     </del>   E		ed Recovery Irbon Storag		Total Depth	After Rework	Number of Wells 21
	<del></del>		La Tiyatoca		90	567	I' KB	
			Lease N	ame		1	k Commenced	Well Number
			Jonah	11:4	•	<del></del>	- 95	-Balcron Monument
		<del>                                     </del>	Johan	wii			k Completed 14 - 95	Federal #11-75
	s		l			1 6	11 12	
	· · · · · · · · · · · · · · · · · · ·	_	WELL CASIN				ORK T	
	ing	<del> </del>	nent Time	From	Perforation	To		Acid or Fracture Treatment Record
Size // 9 5/8 //	215' KB	Sacks \6O	Class-6	4784		4787	4184 - 4928	
5 1/2"	5671' KB	383	Class-6	4190		4796	gel KCI h	1+R & 22,200 164
3.6	26.11	232	50.50 POZ	49 20		4928	16-30 ME	sh sand.
				5019	-	5019	5075 - 511	4 Frac w/ 12,684 ga
				5080		5094	gel KCI V	Utr 4 27,660 lbs
				5112		5114	16-30 Mc	
		WELL CASING	3 RECORD - A	FTER REW	ORK (II	ndicate Additi	ons and Changes	Only)
Св	sing	Св	ment		Perforati		4	Acid or Fracture
Size	Depth	Sacks	Туре	From		To		Treatment Record
			<del> </del>		<del></del>	<del></del>		
ļ	<del> </del>		-				<del>-{</del>	
	<del> </del>		<u> </u>	<del> </del>				
<b></b>		<del>                                     </del>	1					
	ESCRIBE REWO			,		<del> </del>	WIRE LINE LOGS,	
<del> </del>	, , ,	AL SHEETS IF N		A		Log Tyr		Logged Intervals
Complet	e indica			Arrow	Dw.	oensate	d Neutron	TO to surtace
100 V (1)	ALKET G		68 , load	·		- Densi		······································
Champi	m betro	~· 2383	PKR fluid		(eme	1. 0	d Loa	
mixed w	N/ 15 51	18 2°/0 H	(c) water					
[				CERTIF	ICATI	ON		•
1	portify under	the nenalty n	f Ìaw that I ha	_			nd am familiar	with the information
								of those individuals
								ion is true, accurate,
								nformation, including
			nprisonment. (					
"	ים המפומווונא	o, milo uma m	.,	, 75 6	• •	·		
	1	·	1 212		<del></del>			DATE SIGNED
NAME AND OF	FICIAL TITLE (Place ZENIHi	se type or print)	SIGI	NATURE	/	<i>a</i>	1011	,
Senior	Product	ion Engi	neer	100	En	Jeli	litte	2-26-96
176~101	1,000	·	1 /			//		ì





WELL NAME: Balcron Monument Federal #11-7J

FIELD: Monument Butte

FEDERAL LEASE NO.: U-44426

LOCATION: NW NW Sec.7, T9S, R17E

681' FNL & 447' FWL

COUNTY/STATE: Duchesne County, Utah WORKING INTEREST: 0.805079506

PRODUCING FORMATION: Green River

**COMPLETION DATE: 6-14-95** 

INITIAL PRODUCTION: Not Tested

PRESENT PROD STATUS: Waiting Conversion To Injection.

WATER INJECTION RATE:

**ELEVATIONS - GROUND: 5345'** 

TOTAL DEPTH: 5697' KB

SURFACE CASING

SIZE: 8-5/8'

GRADE: J-55

WEIGHT: 24# LENGTH: 265' (6 jts)

DEPTH LANDED: 275' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI +

1/4#/sk celloflake

**TUBING RECORD** 

	Length	Setting Depth
a ·		w/ 10' KB
149 jnts 2 7/8", J-55, 6.5# Tubing	4668.33'	4678.33'
2 7/8" Seating Nipple	1.10'	4679.43'
2 3/8'x 2 7/8" Cross Over	0.75'	4680.18'
Arrow Sel-1 Packer	6.20'	4686.38'

Total String Length: 4676.38' Packer Landed: 4686.38' KB

Arrow Set-1 Packer set w/13" tension on 6-14-95.

Packer Fluid: 55 gais Champion Cortron-2383 mixed w/ 75 STB 2 % KCI water.

SN @ 2 7/8" x 2.25" ID

Logs: Dual Laterolog, Compensated Neutron Litho-Density, Cement Bond Log.

DATE: 8-8-95 JZ

API NO.: 43-013-31492

NET REVENUE INTEREST: 0.73831617 OIL

0.66359285 Gas

OIL GRAVITY: 34 deg SPUD DATE: 5-24-95

KB: 5355'- (10' KB) PLUG BACK TD: 5871' KB

PRODUCTION CASING

SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 5660.72 (143 Jts)

DEPTH LANDED: 5671' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 383 sxs super class "G" + (47#G + 20#Poz A +

17# CSE)/sk +3%sall + 2%gel +1/4 #/sk celloseal.

tall w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk

celloseal + 2 #/sk HiSeal 2

CEMENT TOP AT: 110' KB from CBL.

PERFORATION RECORD

6-12-95 Schlumberger

4784'-87' 2 SPF (.38") 3 ft 6 holes

4790'- 96' 2 SPF (.38") 6 ft 12 holes

4926'- 28' 2 SPF (.38") 2 ft 4 holes

6-8-95 Schlumberger 5075'- 79' 4 SPF (.38") 4 ft 16 holes

5089'- 94' 4 SPF (.38") 5 ft 20 holes

5112'- 14' 4 SPF (.38") 2 ft 8 holes

ACID JOB / BREAKDOWN JOB

BJ/Western

5075'- 5114': 2982 gals 2% KCl wtr w/ 100 balls,

6-12-95 BJ/Western

ATR 4.0 bpm, ATP 2600 psig, ISIP 1850 psig.

4784'- 4796': 2058 gais 2% KCI wtr w/ 2 balls/bbl, ATR 4.5 bpm, ATP 2200 psig, ISIP 1350 psig.

6-12-95 BJ/Western

4926'- 4928': 1596 gais 2% KCl wir w/ 2 bails/bbi,

ATR 3.1 bpm, ATP 4000 psig, ISIP 1950 psig.

FRAC JOB

6-8-95 B.I/Western 5075' - 5114': 12,684 gals 2% KCl wtr w/ 27,660 lbs

16-30 mesh sand, ATR 34.5 bpm, ATP 2400 pslg,

ISIP 2300 psig, 15 min 2060 psig.

6-12-95 BJ/Western

4784' - 4928' : 15,162 gals 2% KCI wir w/ 22,200 lbs

16-30 mesh sand, ATR 35.1 bpm, ATP 3400 pslg,

ISIP 2150 psig, 15 min 1660 psig.





Balcron Monument Federal #11-7J 681' FNL & 447' FWL NW NW Sec.7, T9S, R17E Lease No. U-44426 Monument Butte Field Duchesne County, Utah

Elev. - 5345' GL Elev. - 5355' KB

#### WELLBORE DIAGRAM

DATE: 8-8-95 JZ

#### **SURFACE CASING**

SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24# LENGTH: 265' (6 Jts) DEPTH LANDED: 275' KB HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G" + 2% CCI +

1/4#/sk celloflake

275' KB

#### PRODUCTION CASING

SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15.5# LENGTH: 5660.72 (143 jts)

DEPTH LANDED: 5671' KB

HOLE SIZE: 7-7/8" CEMENT DATA: 383 exs super class "G" + (47#G + 20#Poz A + 17# CSE)/sk +3%salt + 2%gel +1/4 #/sk celloseal,

tall w/ 232 sk 50-50 POZ + 2%gel + 1/4 #/sk

celloseal + 2 #/sk HiSeal 2

CEMENT TOP AT: 110' KB from CBL.

#### **TUBING RECORD**

	Length	Setting Depth
		w/ 10' KB
149 Ints 2 7/8", J-55, 6.5# Tbg	4668.33'	4678.33'
2 7/8" Seating Nipple	1.10'	4679.43
2 3/8'x 2 7/8" Cross Over	0.75'	4680.18'
Arrow Set-1 Packer	6.20'	4686,38'

Total String Length: 4676.38' Packer Landed: 4686,38' KB

Arrow Set-1 Packer set w/13" tension on 6-14-95.

Packer Fluid: 55 gals Champion Cortron-2383 mixed w/ 75 STB 2 % KCl water.

SN @ 2 7/8" x 2.25" ID

Logs: Dual Laterolog, Compensated Neutron Litho-Density, Cement Bond Log.

ACID JOB / BREAKDOWN JOB	,
	_

6-8-95 BJ/Western 5075'- 5114': 2982 gals 2% KCI wir w/ 100 balls. ATR 4.0 bpm, ATP 2600 pslg, ISIP 1850 psig.

4784'- 4796': 2058 gals 2% KCl wir w/ 2 balls/bbl, 6-12-95 BJ/Western ATR 4.5 bpm, ATP 2200 psig, ISIP 1350 psig.

6-12-95 BJ/Western 4926'- 4928': 1596 gals 2% KCl wtr w/ 2 balls/bbl. ATR 3.1 bpm, ATP 4000 psig, ISIP 1950 psig.

FRAC JOB

5075' - 5114' : 12,684 gals 2% KCl wlr w/ 27,660 lbs 16-30 mesh sand, ATR 34.5 bpm, ATP 2400 psig, BJ/Western 6-8-95 ISIP 2300 pslg, 15 min 2060 pslg.

4784' - 4928' : 15,162 gals 2% KCl wir w/ 22,200 lbs 16-30 mesh sand, ATR 35.1 bpm, ATP 3400 psig, 6-12-95 BJ/Western

ISIP 2150 psig, 15 min 1660 psig.

#### PERFORATION RECORD

4784'- 87' 2 SPF (.38") 3 ft 6 holes 4790'- 96' 2 SPF (.38") 6 ft 12 holes 4926'- 28' 2 SPF (.38") 2 ft 4 holes 6-12-95 Schlumberger 5075'-79' 4 SPF (.38") 4 ft 16 holes 5089'-94' 4 SPF (.38") 5 ft 20 holes 5112'-14' 4 SPF (.38") 2 ft 8 holes Schlumberger

Retrievable Casing Packer @ 4686' KB

4784'- 4928' KB

5075'- 5114' KB

PBTD @ 5734' KB TD @ 5800' KB

STATE OF UTAH
Division of Oil, Gas and Mining
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

## INJECTION WELL - PRESSURE TEST

Test Date: $\frac{\partial}{\partial 3}/96$ Well Owner/Operat	•
Disposal Well: Enhanced Recovery	y Well: <u>W/W</u> Other:
API No.: 43-0/3-3/492 Well Name/Number	:: MONUMENT FEDERAL #11-7J
Section: 7 Township: 09	
Initial Conditions:	
	essure: <u>400 RST</u> psi
Casing/Tubing Annulus - Pressure:	O psi
Conditions During Test:	
Time (Minutes) Annulus Pr	essure Tubing Pressure
5 1000 F	OST UDOPSI
$\frac{7000}{100}$	SI YOUPSI
$\frac{10}{15} \qquad \frac{7000}{1000}$	SI 400 PSI
20 /000/	SI 400 PSI
25 <u>/000</u> /	VOOPST VOOPST
30 1000 F	ST 400PSF
Results: Pass/Fail	
Conditions After Test:	
Tubing Pressure: //000 psi	
Casing/Tubing Annulus Pressure: 400	psi
REMARKS: TESTED FROM 11:30 1	em autic NOON
No LEAK OFF.	· · · · · · · · · · · · · · · · · · ·
( su tours wall	Wenns of
Operator Representative	DOGM Witness

STATE OF UTAH INVENTORY OF INJECTION WELLS

OPERATOR	API NO.	WELL	TNS	RGE	SE	WELLTYPE	INDIAN COUNT
*******	******	*****	***	***	* *	*****	******
CROSS CREEK	43-037-20117	NAVAJO A #1	41S	26E	5	INJD	Y
CROSS CREEK	43-037-20164	NAVAJO A #3	41S	26E	5	INJI	Y
ENSERCH EXPL	43-013-31240	FEDERAL 43-3	08S	16E	33	INJW	N
ENSERCH EXPL	43-013-31269	FEDERAL 34-3	08S	16E	33	INJW	N
ENSERCH EXPL	43-013-31229	FEDERAL 14-3	088	16E	33	INJW	N
ENSERCH EXPL	43-613-31225	FEDERAL 14-3	088	16E	34	INJW	N
ENSERCH EXPL	43-013-31272	FEDERAL 21-4	09S	16E	4	WLNI	N N
ENSERCH EXPL	43-013-30670	FEDERAL 32-5	09S	16E	5	INJW	N N
ENSERCH EXPL	43-013-31205	FEDERAL 41-5	098	16E	5 26	INJW ' INJG	N N
ENSERCH EXPL	43-047-32248	1-26B	09S	19E	20 5	INJW	N
ENSERCH EXPL	43-013-30913	44-5H	09S	17E 17E		INJW	N
ENSERCH EXPL	43-013-30678	42-8H	09S	17E	8	INJW	N
ENSERCH EXPL	43-013-31457	22-8H	09S 09S	17E	8	INJW	N
ENSERCH EXPL	43-013-30679	31-8H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-31049	22-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-30682	24-9H 11-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-30887 43-013-31108	33-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-31106	13-9H	09S	17E	9	INJW	N
ENSERCH EXPL	43-013-30350	FEDERAL 11-6	09S	17E	6	INJW	Y
EQUITABLE RE EQUITABLE RE	43-013-31362	FEDERAL 33-6	09S	17E	6	INJW	Ÿ
EQUITABLE RE	43-013-31363	FEDERAL 24-6	09S	17E	6	INJW	Ÿ
EQUITABLE RE	43-013-31364	FEDERAL 42-6	09S	17E	6	INJW	Ÿ
EQUITABLE RE	43-013-31304	FEDERAL 22-6	09S	17E	6	INJW	Ÿ
EQUITABLE RE	43-013-30313	FEDERAL 1-6	09S	17E	6	INJW	Y
EQUITABLE RE	43-013-30918	FEDERAL 13-6	09S	17E	6	INJW	Y
EQUITABLE RE	43-047-15681	PARIETTE BEN	09S	19E	7	INJD	Y
EQUITABLE RE	43-013-31404	42-1J	09S	16E	1	INJW	Y
EQUITABLE RE	43-013-31415	44-1J	09S	16E	1	INJW	Y
EQUITABLE RE	43-013-30702	FEDERAL 1-13	09S	16E	1	INJW	N
EQUITABLE RE	43-013-30735	FEDERAL 1-33	09S	16E	1	INJW	N
EQUITABLE RE	43-013-30701	1-24	09S	16E	1	INJW	N
EQUITABLE RE	43-013-31384	22-5	09S	-16E	5	INJW 17E	Y
EQUITABLE RE	43-013-31416	34-10J	09S	16E	10	WLNI	N
EQUITABLE RE	43-013-31002	43-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31369	23-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31417	12-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31386	32-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31003	FEDERAL 34-1	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31374	14-11J	09S	16E	11	INJW	N
EQUITABLE RE	43-013-31410	12-12J	09S	16E	12	WLNI	N
EQUITABLE RE	43-013-31411	14-12J	09S	16E	12	INJW	N
EQUITABLE RE	43-013-30742	GOVT C&O #4	09S	16E	12	INJW	N
EQUITABLE RE	43-013-31419	32-12J	09S	16E	12	INJW	N
EQUITABLE RE	43-013-31408		09S	16E	14	INJW	N
EQUITABLE RE	43-013-31421		09S	16E	14	INJW	N
EQUITABLE RE	43-013-31367	41-15J	09S	16E	15	WLNI	N
EQUITABLE RE	43-013-31373	23-15J	09S	16E	15	INJW	N N
EQUITABLE RE	43-013-31368	32-15J	09S	16E	15	INJW	N Y
EQUITABLE RE	43-013-31375	24-5	09S	17E	5	INJW	Y Y
EQUITABLE RE	43-013-31370	FEDERAL 13-5	09S	17E	5	INJW	N
EQUITABLE RE	43-013-31195	ALLEN FEDERA	09S	17E	6	INJW	Y Y
EQUITABLE RE	43-013-31405	31-7J	09S	17E	7	INJW	
EQUITABLE	43-013-31492	11-79	95	ME	7	INGW	N

Page No. 03/07/96

4



Office: (406) 259-7860

FAX: (406) 245-1365  $\square$ FAX: (406) 245-1361 🗘

April 1, 1996

1601 Lewis Avenue

Billings, MT 59102

Mr. Dan Jarvis Utak Division of Oil, Gas and Mining UIC Program 355 West North Temple Salt Lake City, UT 84180

Dear Dan:

Effective April 1, 1996, our name will change from Equitable Resources Energy Company, Balcron Oil Division to Equitable Resources Energy Attached is a listing of permits which we have with your This change will apply to those. If you note that I have missed some or if you have any questions, please do not hesitate to give me a call at (406) 259-7860, extension 240 to discuss this.

This change affects only our company name. The physical locations of our offices and the personnel remain the same.

If you have any questions, please do not hesitate to give me a call.

Sincerely,

Bobbie Schuman

Regulatory and

Environmental Specialist

/hs


Enclosures



1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

March 22, 1996

Utah Division of Oil, Gas and Mining 355 West North Temple Salt Lake City, UT 84180



Gentlemen:

Effective April 1, 1996, our name will change from Equitable Resources Energy Company, Balcron Oil Division to Equitable Resources Energy Company. Attached is a sundry notice reflecting that change. To simplify paperwork, I have done one sundry notice with copies for each of the wells. To this letter I have attached a list of our wells for your ease in filing the sundry notices in the well files. This should be sufficient for your purposes.

I have the listings on a spreadsheet so if it would be easier for you to have them sorted differently (for example, the Montana Board of Oil and Gas prefers them sorted by API number), please give me a call at (406) 259-7860, extension 240 and I would be glad to provide a list to your specifications.

This change affects only our company name. The physical locations of our offices and the personnel remain the same. We will be changing our well signs and ask for your patience and cooperation as this will be done as soon as possible but may take some time since we do have so many properties at which to make the change.

If you have any questions, please do not hesitate to give me a call.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

Enclosures

Balcron Coyote Fed. #42-6X	Coyote Basin	SE NE	1 6	88	25E	Uintah	UT	osi	lo. 5:					
Balcron Coyote Fed. #44-6	Coyote Basin	SE SE	+-;	-	25E	Uintah	UT		Green River	U-017439-B	43-047-32346	1987' FNL, 682' FEL	Vernal	Coyote Basin
Balcron Federal #12-20Y	8 Mile Flat N.	SWNW	20		18E	Uintah	UT		Green River	U-017439B	43-047-32421	560' FSL, 760' FEL	Vemal	Coyote Basin
Balcron Federal #12-22Y	8 Mile Flat N.	SW NW	22	<del></del>	17E	Duchense	UT		Green River	U-64917	43-047-32617	1980' FNL, 660' FWL	Vernal	
Balcron Federal #21-13Y	Monument Butte	NE NW	13	-	16E	+	-		Green River	U-66191	43-013-31476	2105' FNL, 660' FWL	Vernal/	Priv.sfc.
Balcron Federal #21-25Y	Monument Butte	NE NW	25		16E	Duchesne	UT		Green River	U-64805	43-013-31400	703' FNL, 1831' FWL	Vemal	
Balcron Federal #21-9Y	Monument Butte	NE NW	9		16E	Duchesne	UT		Green River	U-64380	43-013-31994	500' FNL, 1980' FWL	Vernal	
Balcron Federal #22-10Y	Monument Butte	SE NW	10	+	17E	Duchesne	UT		Green River	U-65207	43-013-31396	476' FNL, 2051' FWL	Vernal	
Balcron Federal #24-3Y	Monument Butte	SE SW	3	+		Duchesne	UT		Green River	U-65210	43-013-31395	1980' FNL, 1980' FWL	Vernal	
Balcron Federal #31-14Y	Undesignated	NW NE	14	98	17E	Duchesne	ரு		Green River	U-64381	43-013-31397	562' FSL, 1887' FWL	Vemal	
Balcron Federal #31-19Y	8 Mile Flat N.	NW NE	-	+	19E	Uintah	UT		WASATCH	U-66193		500' FNL, 2740' FWL	Vernal/I	Priv.sfc.
Balcron Federal #31-5Y	8 Mile Flat N.	NW NE	19		18E	Duchesne	UT		Green River	U-65635	43-047-32614	660' FNL, 1880' FEL	Vernal	1
Balcron Federal #32-19Y	8 Mile Flat N.		5	1	18E	Uintah	UT		Green River	U-65970	43-047-32503	660' FNL, 1980' FEL	Vernal	
Balcron Federal #41-19Y	Monument Butte	SW NE	19	+	18E	Uintah	UT		Green River	U-65635	43-047-32615	1980' FNL, 1980' FEL	Vernal	
Balcron Federal #41-21Y	Monument Butte	NE NE	19	1	17E	Duchesne	υT	Oil	Green River	U-65967	43-047-32504	660' FSL, 660' FEL	Vernal	
Balcron Federal #42-19Y	8 Mile Flat N.	SE NE	21	98	16E	Duchesne	UT	Oil	Green River	U-64379	43-013-31392	970' FNL, 894' FEL	Vernal	
Balcron Federal #44-14Y	Monument Butte		19		18E	Uintah	UT	Oil	Green River	U-65635	43-047-32616	2100' FNL, 500' FEL	Vernal	
Balcron Federal #44-4Y	8 Mile Flat N.	SE SE	14	98	17E	Uintah	UT	Oil	Green River	U-64806	43-047-32438	1008' FSL, 832' FEL	Vernal	
Balcron Monument Fed. #11-10-9-17Y	o Mile Plat N.	SE SE	4	98	17E	Duchesne	UT	Oil	Green River	U-65635	43-013-31452	660' FNL, 660' FEL	Vemai	
Balcron Monument Fed. #11-20-9-18Y	Manuscat D. H.	NW NW	10	98	17E	Duchesne	ய	PND	Green River				Vemal	<del></del> -
Balcron Monument Fed. #11-22-8-17Y	Monument Butte	NW NW	20	98	18E	Uintah	UT	OIL	Green River	U-64917	43-047-32712	500' FNI, 500' FWL	Vemal	
Baicron Monument Fed. #11-25	Monument Butte	NW NW	22	88	·	Duchesne	UΤ	OIL	Green River	U-66191	43-013-31539	635' FNL, 658' FWL	Vernal	
Balcron Monument Fed. #11-6	Monument Butte	NW NW	25	88		Uintah	UΤ	Oil	Green River	U-67845	43-047-32455	739' FNL, 648' FWL	Vernal	
Balcron Monument Fed. #11-7J	Monument Butte	NW NW	6	98	17E	Duchesne	UΤ	wiw	Green River	U-020252-A	43-013-31362	804' FNL, 696' FWL	1	Jonah
	Monument Butte	NW NW	7	98	17E	Duchesne	UT	COMPL-WIW	Green River	U-44426	43-013-31492	681' FNL, 447' FWL		Jonah
Balcron Monument Fed. #12-10-9-17Y Balcron Monument Fed. #12-11J	Monument Butte	SW NW	10	98	17E	Duchesne	UT	COMPL	Green River	U-65210	43-013-31536	1994' FNL, 618' FWL	Vernal	Jonan
	Monument Butte	SWNW	11	98	16E	Duchesne	UΤ	WIW	Green River	U-096550	43-013-31417	2128' FNL, 689' FWL	-	Jonah
Balcron Monument Fed. #12-12J	Monument Butte	SW NW	12	98	16E	Duchesne	UΤ	wiw	Green River	U-096550	43-013-31410	739' FNL, 648' FWL	+	
Balcron Monument Fed. #12-14J	Monument Butte	SW NW	14	98	16E	Duchesne	UT	PND	Green River	U-096547	43-013-31488		-	Jonah
Balcron Monument Fed. #12-17	Monument Butte	SW NW	17	98	17E	Duchesne	υT	Oil	Green River	UTU-72106	43-013-31431	2004' FNL, 658' FWL	<del> </del>	Jonah -
Salcron Monument Fed. #12-25	Undesignated	SW NW	25	88	17E	Uintah	UT	Oil	Green River	U-67845	43-047-32526	1980' FNL, 660' FWL		Beluga
Balcron Monument Fed. #12-7J	Monument Butte	SW NW	7	98	17E	Duchesne	+	Oil	Green River	U-44426	<del> </del>	1486' FNL, 875.7' FWL	Vernal	
Balcron Monument Fed. #13-11J	Monument Butte	NW SW	11	98		Duchesne	+	Oil	Green River	U-096547	43-013-31493 43-013-15790	1965' FNL, 620' FWL		Jonah
Balcron Monument Fed. #13-5	Monument Butte	NW SW	5	98		Duchesne	<del></del>	wiw	Green River	U-020252		1819' FSL, 658' FWL	<del></del>	Jonah
Balcron Monument Fed. #13-8	Monument Butte	NW SW	8	98		Duchesne	<del> </del>	Oil	Green River		43-013-31370	1980' FSL, 660' FWL		Jonah
Balcron Monument Fed. #14-11	Monument Butte	SW SW	11	98		Duchesne	<del> </del>	<del></del>	Green River	UTU-74108	43-013-31382	2060' FSL, 694' FWL		Beluga
-	<del></del>						٠,	144144	Green Kiver	U-096547	43-013-31374	1048' FSL, 446' FWL	Vernal .	Jonah

ORM 8	ST OF UTAH				
	DIVISION OF OIL, GAS AND MIN	NING	5, Lease Designation and Serial Number:		
•	•		See attached listing		
CHNDDY	NOTICES AND REPORTS	ON WELLS	8. If Indian, Allottee or Tribe Name:		
SONDAT	TOTIOLS AND REPORTS	ON WELLS	n/a		
Do not use this form for proposa Use APPLIC	als to drill new wells, deepen existing wells, or to rec ATION FOR PERMIT TO DRILL OR DEEPEN form fo	enter plugged and abandoned wells. If such proposals.	7. Unit Agreement Name: See attached listing		
Type of Well: OIL GAS	OTHER: See attached li	isting	8. Well Name and Number: See attached listing		
Name of Operator;		· · · · · · · · · · · · · · · · · · ·	9. API Well Number;		
Equitable Resou	rces Energy Company, Bal	Icron Oil Division	See attached listing		
Address and Telephone Number: 1601 Lewis Aven	nue Avenue; Billings, MT	59102 (406) 259-7860	10. Field and Pool, or Wildcat: See attached listing		
Location of Well	attached listing		county: See attached list		
•	a out one				
QQ, Sec.,T.,R.,M.:			State: UTAH		
CHECK APPROP	PRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPO	RT, OR OTHER DATA		
	OF INTENT		NUENT REPORT Original Form Only)		
Abandon	☐ New Construction	☐ Abandon *	☐ New Construction		
Repair Casing	☐ Pull or Alter Casing	☐ Repair Casing	☐ Pull or Alter Casing		
Change of Plans	☐ Recomplete	☐ Change of Plans	☐ Reperforate		
Convert to Injection	☐ Reperforate	☐ Convert to Injection	☐ Vent or Flare		
Fracture Treat or Acidize	☐ Vent or Flare	Fracture Treat or Acidize	☐ Water Shut-Off		
Multiple Completion	☐ Water Shut-Off	☑ OtherOperator name	cnange		
Other		Date of work completion			
proximate date work will start _		Report results of Multiple Completions and Recompletions to different reservoirs on WELL.			
		Must be accompanied by a cement verification report.			
Other  oproximate date work will start  DESCRIBE PROPOSED OR COMPLETED OF Vertical depths for all markers and zones per  Effective April	PERATIONS (Clearly state all pertinent details, and ritinent to this work.)  1, 1996, operator will	Date of work completion  Report results of Multiple Completions an COMPLETION OR RECOMPLETION REPO  Must be accompanied by a cement verificate or the companied by a c	d Recompletions to different reservoirs of RT AND LOG form. ation report. give subsurface locations and measured		

Bobbie Schuman

Regulatory and
Title: Environmental Specialist Date: March 27, 1996

(This space for State use only)

	ion of Oil, Gas an <b>\TOR CHANGE HO</b>						Routing:
		n received by the m when completed.			able.		2-DZS8-FILE 3-VLD GILZ 4-RJF
	ange of Operato signation of O	or (well sold) perator		Designation of <b>Operator Name</b>			5-1 Equit
The c	pperator of the	e well(s) liste	d below has	changed (EFFEC	CTIVE DATE:	4-1-96	)
TO (n	(address) <u>I</u> —	1601 LEWIS AVE BILLINGS MT 59	102-4126	COEROM (former	operator) (address)	BALCRON OII 1601 LEWIS BILLINGS M	AVE F 59102-4126
		hone <u>(406 )259</u> ccount no. <u>N9</u>				phone <u>(406</u> account no.	) 259-7860 - <u>N</u> 9890
		onal page if neede		* .			
Name:		APT.		Entity:	_ SecIWP	Kng L	ease Type:ease Type:ease Type:ease Type:ease Type:ease Type:ease Type:
Le 1.		-10) Sundry o tach to this fo -10) Sundry or	Creco 9-	1-16 \$ 7-8-16/			ed from <u>former</u> om <u>new</u> operator
<i>I/A</i> 3.	operating any	nt of Commerce / wells in Uta npany file numb	II. IS COMPA	my registered	new operat with the	tor above is state? (yes	not currently /no) If
	comments sect	tion of this f	orm. Manage	to this repo ement review o	rt). Make of <b>Federal</b>	note of and Indian	BLM status in well operator
LC 5.	Changes have <del>listed above</del> .	been entered i	n the Oil an	d Gas Informat	tion System	ı (Wang/IBM)	<del>-for each well</del>
<u>lie</u> 6.	Cardex file h	<i>C4-10-9L/</i> as been updated	for each w	ell listed abo	ve. (4-11-967	)	
£C7.	Well file lab	els have been ι	updated for e	each well liste	ed above. (	4-11-967	
ec8.	Changes have for distribut	been included ion to State La	on the monti unds and the	nly "Operator, Tax Commission	Address, (	and Account	Changes" memo
<u>v</u> 29.	A folder has placed there f	been set up fo for reference d	r the Operai	cor Change file	e, and a co	opy of this	page has been

C(

OPERATOR CHANGE WORKSHEET (CONTINUED) Initial each item when completed. Write N/A if item is not applicable.
ENTITY REVIEW
(Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/ho) (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
№ 2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.
BOND VERIFICATION (Fee wells only) # 5578314 (\$80,000) Seleco Ins. C. (Bond Rider In Progress)
1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
2. A copy of this form has been placed in the new and former operators' bond files.
3. The former operator has requested a release of liability from their bond (yes/no)  Today's date 19 If yes, division response was made by letter dated 19
LEASE INTEREST OHNER NOTIFICATION RESPONSIBILITY
1. (Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated
2. Copies of documents have been sent to State Lands for changes involving State leases.
1. All attachments to this form have been microfilmed. Date: May 20 1990.
ILING
1. Copies of all attachments to this form have been filed in each well file.
2. The <u>original</u> of this form and the <u>original</u> attachments have been filed in the Operator Change file.
COMMENTS
9/004/10 Blm/BIA Formal approved not necessary"

WE71/34-35

Form 3160-5 (June 1990)

1. Type of Well

Oil Well

2. Name of Operator

3. Address and Telephone No.

### D STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

	Budget	Bure	au No.	100	4-013
	Exp	ires:	March	31, 1	993
Le	se Des	ionati	on and	Seri	al No.

FORM APPROVED

	Expires:	M	arch	31, 195	13
. Lease	Designat	ion	and	Serial	No.
11-114	426				

_	44420		
6.	If Indian, Allottee	or Tribe	Name

SUNDRY	NOTICES AND REPORTS ON WELLS
	and the state of t

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

Other WIW

Equitable Resources Energy Company

4: Location of Well (Footage, Sec., T., R., M., or Survey Description)

1601 Lewis Avenue; Billings, MT 59102

n/a 7. If Unit or CA, Agreement Designation

Jonah Unit

8. Well Name and No.

NW NW Section 7, 195, RI7E 681' FNL, 447' FWL CHECK APPROPRIATE BOX(s)	TO INDICATE NATURE OF NOTICE, REF	Duchesne County, UTAH PORT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACT	
Notice of Intent  Subsequent Report  Final Abandonment Notice	Abandonment Recompletion Plugging Back Casing Repair Altering Casing Request variance Other Trinent details, and give pertinent dates, including estimated date of s	Change of Plans  New Construction  Non-Routine Fracturing  Water Shut-Off  Conversion to Injection  Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

(406) 259-7860

Balc. Mon. Fed. #11-7J 9. API Well No. 43-013-31492

10. Field and Pool, or Exploratory Area Monument Butte/Green River 11. County or Parish, State

give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)* 13. Describe Proposed or Completed Operations

Operator has an approved sundry notice to lay a water injection line. In the Conditions of Approval to that sundry notice, it is specified that the seed for reclamation will be drilled, broadcasted, and hydromulched. Operator requests that the Condition for hydromulching be waived. The area to be reclaimed is very similar to the rest of the area where Operator has just drilled and broadcasted, and the reclamation has been successful in those areas without hydromulching. Óperator does not see that hydromulching will add value to the area and the cost of adding the hydromulching is

excessive.

or representations as to any matter within its jurisdiction.

ORIGINAL: Bureau of Land Management (Vernal, Utah)

COPY: Utah Division of Oil, Gas and Mining

IAN 0 6 1997 DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct	Title _	Regulatory and Environmental Specialist	Date _	January 2, 1997
(This space for Federal or State office use)  Approved by Conditions of approval, if any:	Tide _	Accepted by Utah Division	) OT	•
Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly	and will	fully to make to any department or agency of the United State	s any false	, fictitious or fraudulent statements

*See Instruction on Reverse SOR RECORD



**WESTERN REGION** 

1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860 FAX: (406) 245-1365 [] FAX: (406) 245-1361 [2]

DIV. OF OIL, GAS & MINING

February 10, 1997

Mr. Dan Jarvis
State of Utah
UIC Program
Division of Oil, Gas and Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

Dear Mr. Jarvis:

Attached are copies of the results of Mechanical Integrity Tests (MIT) recently run on the following wells:

Balcron Monument Federal #41-14J Monument State #14-2 Monument State #22-2 Monument Federal #11-7J

Sincerely,

Bobbie Schuman Regulatory and

**Environmental Specialist** 

/hs Attachments

cc: Bureau of Land Management (Vernal, UT)

U.S. Environmental Protection Agency (MAIL CODE: 8 WM-DW)

STATE OF UTAH
Division of Oil, Gas and Mining
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

## INJECTION WELL - PRESSURE TEST

Tubing - Rate:		:			
Disposal Well:   Enhanced Recovery Well:	Test Date: $\frac{\partial}{\partial 3}/96$	Well Owner/Operator:	EQUITABLE A	ESOUACES ENE	NGY
Township:   O9   Range:	Disposal Well:	Enhanced Recovery W	/ell: <u>      /                               </u>	Other:	
Township:   O9   Range:	API No.: 43- <u>0/3-3/49</u> 2	2 Well Name/Number: /	MONUMENT	FEDELAL 4	11-7J
Tubing - Rate:	Section: 7	Township: 095		Range: 17E	
Tubing - Rate:	Initial Conditions:	ACCOUNT.			
Casing/Tubing Annulus - Pressure:	. 4	Pressu	ire: <u>400 R</u> -	SZ psi	÷
Time (Minutes)	Casing/Tubing Annulu	s - Pressure:	) psi		
10	Conditions During Test:				
10		Annulus Press	sure Z	Tubing Pressure	•
15	5	1000 PS	Ž.	HOOPSI	
20		1000 PS	<u></u>	400 PSI	•
Results: Pass/Fail  Conditions After Test:  Tubing Pressure:	<del></del>	1000/5	I	400 PST	•
Results: Pass/Fail  Conditions After Test:  Tubing Pressure:		1000 PS	<del>\frac{1}{L_{}}</del>	400PSF	
Conditions After Test:  Tubing Pressure: / 00 δ psi  Casing/Tubing Annulus Pressure: 40 δ psi	30	7000 7 54			
Tubing Pressure: /000 psi  Casing/Γubing Annulus Pressure: 400 psi	Results: Pass/Fail				
Casing/Tubing Annulus Pressure: 400 psi	Conditions After Test:				
,	Tubing Pressure: //	000 psi			**************************************
REMARKS: TESTED FROM 11:30 AM UNTIL NOON	Casing/Tubing Annul	us Pressure: 408	psi		•
	REMARKS: TESTED	FROM 11:30 AM	n UNTIL N	100N/	
				•	
1 la final Manne Chi			1 lenn	2	
Operator Representative DOGM Witness	Operator Representative		DOGM Witne	ess	

Page No. 5 06/16/97

# STATE OF UTAH INVENTORY OF INJECTION WELLS

OPERATOR *******	API NO.	WELL ******	TNS	RGE ***	SE **	WELLTYPE ******	INDIAN COUNT
EQUITABLE RE	43-013-31410		09S				********
EQUITABLE RE		41-14J	09S	16E 16E	12	INJW	N
EQUITABLE RE			09S	16E	14 14	INJW	N
EQUITABLE RE	43-013-31373	23-15J	09S	16E	15	INJW	N
EQUITABLE RE		32-15J	09S	16E	15	WLNI	·N
EQUITABLE RE	43-013-31367	41-15J	09S	16E	15	INJW	N
EQUITABLE RE	43-013-31370	FEDERAL 13-5	09S	17E		INJW	N
	√43-013-31375	24-5	09S	17E	5 5	INJW	Y
	√43-013-31384	22-5	09S	17E	5	INJW	Ä
	√43-013-31195	ALLEN FEDERA	09S	17E	6	INJW	Y
	V43-013-31492	11-7J	09S	17E	7	INJW	N
EOUITABLE RE	<b>43-013-31405</b>	31-7J	09S	17E	7	INJW INJW	Y
EQUITABLE RE	43-047-20252	E. RED WASH	08S	25E	5	INJW	Y
EQUITABLE RE	43-047-20261	ERW 4-6	085	25E	6	INJW	N
EQUITABLE RE	43-047-32346	42-6X	08S	25E	6	INJW	Y
EQUITABLE RE	43-047-20245	AMERADA GUIN	08S	25E	7	INJW	N Y
EQUITABLE RE	43-013-30666	44-7	09S	17E	7	INJW	Y
EQUITABLE RE	43-013-31382	13-8	09S	17E	8	INJW	
EQUITABLE RE	43-013-31427	33-8	09S	17E	8		Y
EQUITABLE RE	43-013-30675	24-8	09S	17E	8	INJW	Y
EQUITABLE RE	43-013-30643	44-8-17B	09S	17E	8	INJW	Y
EQUITABLE RE	43-013-31580	13-16-9-17B	09S	17E	16	WUNI WUNI	Y Y
EQUITABLE RE	43-013-30616	11-16-9-17B	09S	17E	16	INJW	Y
EQUITABLE RE	43-013-31145	22-16-9-17B	09S	17E	16	INJW	Y
EQUITABLE RE	43-013-30518	11-17	09S	17E	17	INJW	Y
EQUITABLE RE	43-013-30499	POMCO 5	09S	17E	17	INJW	Y
EQUITABLE RE	43-013-30516	11-17	09S	17E	17	INJW	Y
EQUITABLE RE	43-013-31428	31-17	09S	17E	17	INJW	Y
EQUITABLE RE	43-013-31581	33-17-9-17B	09S	17E	17	INJW	Y
EQUITABLE RE	43-013-31429	22-17	09S	17E	17	WUNI	Y
EQUITABLE RE	43-013-31467	42-17	09S	17E	17	INJW	Y
EQUITABLE RE	43-047-32610	22-2	09S	17E	2	INJW	Ÿ
EQUITABLE RE	43-013-31425	14-2	09S	17E	2	WUNI	Y
GIANT EXPLOR	43-037-15042	GOTHIC MESA	41S	23E	16	INJD	Y
GIANT EXPLOR	43-037-20292	SENTINEL PEA	41S	26E	27	INJD	Ϋ́
GIANT EXPLOR	43-037-16452	9-24	41S	23E	9	INJI	Y
HAY HOT OIL	43-037-30521	MCCRAKEN PT	40S	23E	19	INJI	Ň
INLAND PRODU	43-013-30843	MONUMENT BUT	08S	16E	34	INJW	Y
INLAND PRODU	43-013-31559	15-25	08S	16E	25	INJW	Ŋ
INLAND PRODU	43-013-30693	FEDERAL 3-33	08S	16E	33	INJW	N
INLAND PRODU	43-013-30808	FED 1-34	08S	16E	34	INJW	N
INLAND PRODU	43-013-30686	FEDERAL 5-35	08S	16E	35	INJW	N
INLAND PRODU	43-013-30606	MONUMENT BUT	08S	16E	35	INJW	N
INLAND PRODU	43-013-30745	MONUMENT BUT	08S	16E	35	INJW	N
INLAND PRODU	43-013-31514	1A-35	08S	16E	35	INJW	Y
INLAND PRODU	43-013-30605	MONUMENT BUT	08S	16E	35	INJW	N
INLAND PRODU	43-013-31264	MONUMENT FED	08S	16E	35	INJW	N
INLAND PRODU	43-013-30608	MONUMENT BUT	08S	16E	35	INJW	N
INLAND PRODU	43-013-30624	STATE 5-36	08S	16E	36	INJW	N
INLAND PRODU	43-013-30592	STATE 1-36	08S	16E	36	INJW	N
INLAND PRODU	43-013-30787	12-32	08S	17E	32	INJW	Y
INLAND PRODU	43-013-30779	FED 15-28	08S	16E	28	INJW	N
INLAND PRODU	43-013-31372	14A-28	08S	16E	28	WUNI	N
						- '-	

## STATE OF UTAH

	DIVISION OF OIL, GAS AND MIN	ING		
			5. Lease Designation and Serial Number:	
			See Attached	
SHNDRY	NOTICES AND REPORTS	ON WELLS	6. If Indian, Allottee or Tribe Name:	
SONDIT	NOTICES AND REPORTS	ON WELLS	n/a	
Do not use this form for propose	als to drill new wells, deepen existing wells, or to reen		7. Unit Agreement Name:	
Use APPLIC	ATION FOR PERMIT TO DRILL OR DEEPEN form for	on pugged and abandoned wells. such proposals.	See Attached	
1. Type of Well: OIL T GAS	OTHER:		B. Well Name and Number:	
	DECENIED			
2. Name of Operator:			9. API Well Number:	
Inland Pr	oduction Company	0CT 1.3 <b>1997</b>	See Attached	
3. Address and Telephone Number:			10. Field and Pool, or Wildcat:	
475 - 17t	h Street, Suite 1500, Der	nver, CO 80202	See Attached	
4. Location of Well				
Footages: See Attac	hed Exhibit		County:	
QQ, Sec.,T.,R.,M.;			State:	
11. CHECK APPROD	DIATE DOVED TO THE			
CHECK APPROP	PRIATE BOXES TO INDICATE N	IATURE OF NOTICE, REPO	RT, OR OTHER DATA	
	OF INTENT	SUBSEC	QUENT REPORT	
nmaue)	in Duplicate)	(Submit	Original Form Only)	
☐ Abandon	□ New Construction	☐ Abandon *	□ New Construction	
Repair Casing	Pull or Alter Casing	☐ Repair Casing	Pull or Atter Casing	
☐ Change of Plans	☐ Recomplete	Change of Plans	☐ Reperforate	
Convert to Injection	☐ Reperforate	☐ Convert to Injection	☐ Vent or Flare	
☐ Fracture Treat or Acidize	☐ Vent or Flare	Fracture Treat or Acidize	☐ Water Shut-Off	
☐ Multiple Completion	☐ Water Shut-Off	Other Change of Ope		
☑ Other <u>Change of Oper</u>	cator		24001	
		Date of work completion9_	.30_971	
Approximate date work will start				
		COMPLETION OR RECOMPLETION REPO	nd Recompletions to different reservoirs on WELL OHT AND LOG form.	
		Must be accompanied by a cement verifical	ation report.	
12. DESCRIBE PROPOSED OR COMPLETED OF vertical depths for all markers and zones pertical.	PERATIONS (Clearly state all pertinent details, and give timent to this work.)	re pertinent dates. It well is directionally drilled	, give subsurface locations and measured and true	
Effective September	30, 1997, Inland Product:	ion Company will take	over operations of the	
wells on the attache	ed list. The previous ope			
		Equitable Resolution 1601 Lewis Avo	ources Energy Company	
		Billings, MT	59102	
		_		
and condictions of the	30, 1997, Inland Producti e leases for operations of	conducted on the lease	ible under the terms d lands Or a portion	
chereor mider state	of Utah Statewide Bond No	· 4471291.		
			OCT 1 6 1997	
13.		•		
Name & Signature:	SA CHRIS	A. POTTER, ATTORNEY-IN-F	FACT Date: 9/30/97	

(This space for State use only)

RECENTO

OCT 1 0 1997

DECEINED

TRANSFER OF AUTHORITY TO INJECT - UIC FORM 5

OCT 1 3 1997

	e e constant de la co
Well name and number: See Attached	**JONAH (GREEN RIVER) UNIT
Field or Unit name: See Attached	API no. See Attached
Well location: QQ section towns	hip range county
See Attached  Effective Date of Transfer:September	30, 1997
CURRENT OPERATOR	
Transfer approved by:	·
Name David M. McCoskery	Company Equitable Resources Energy Co.
Signature All Many	Address 1601 Lewis Avenue
Title Director of Operations & Engineering	g <u>Billings, MT 59102</u>
Date 9-30-97	Phone ( 406 ) 259–7860'
Comments:	
· · ·	
NEW OPERATOR	
Transfer approved by:	
Name Christ Patter	Company Inland Production Company
Signature LAB 24	Address 475 - 17th Street, Suite 1500
Title CHRIS A. POTTER, ATTORNEY-IN-FACT	Denver, CO 80202
Date <u>9-30-97</u>	Phone ( 303 ) 292-0900
Comments:	
(State use only) Transfer approved by	Title Envisor, Manger
Approval Date 1-20-98	(AUS # 728-2
	CCT 26 1997

Injection Wells for Inland Change of Op							
WELL NAME	LOCATION	COUNTY	ST	FIELD NAME	API NUMBER	LEASE NO.	AGREEMENT NO
AMERADA GUINAND #1	SWNW 7 8S 25E	UINTAH	117	COVOTE BACINI	40.047.00045.00	1171104007414	LITUTOOFA
COYOTE BASIN #42-6X			·	COYOTE BASIN	43-047-20245-00	UTU016271V	UTU72085A
EAST RED WASH FED. #4-6	SENE 6 8S 25E	UINTA	UT	COYOTE BASIN	43-047-32346-00	UTU017439B	UTU72085A
EAST RED WASH #2-5	SWSE 6 8S 25E	UINTAH		COYOTE BASIN	43-047-20261-00	UTU020309D	UTU72085A
EAST RED WASH #2-5	NWNW 58S 25E	UINTA	UT	COYOTE BASIN	43-047-20252-00	UTU063597A	UTU72085A
ALLEN FEDERAL #1	SESE 6 9S 17E	DUCHESNE	IIT	MONUMENT BUTTE (J)	43-013-15779-00	UTU020252A	UTU72086A
ALLEN FEDERAL #13-6	NWSW 69S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30918-00	UTU020252A	UTU72086A
ALLEN FEDERAL #22-6	SENW 6 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-30919-00	UTU020252A	UTU72086A
ÁLLEN FEDERAL #31-6	LOT2 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)		UTU020252A	UTU72086A
MONUMENT BUTTE FED. #11-6	NWNW 69S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31195-00 43-013-31362-00	UTU020252A	UTU72086A
MONUMENT FEDERAL #11-7J	NW NW 7 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31492-00	UTU44426	UTU72086A
MONUMENT BUTTE #13-5	NWSW 5 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31492-00	01044426	UTU72086A
MONUMENT BUTTE #22-5	SENW 5 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31384-00	UTU020252	
MONUMENT BUTTE #24-5	SESW 5 9S 17E	DUCHESNE		MONUMENT BUTTE (J)			UTU72086A
MONUMENT BUTTE FED. #24-6	SESW 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31375-00	UTU020252	UTU72086A
MONUMENT BUTTE #31-7	NWNE 7 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31363-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #33-6	NWSE 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31405-00	UTU72106	UTU72086A
MONUMENT BUTTE FED. #42-6	SENE 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31361-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #12-11	SWNW 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31364-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #14-11	SWSW 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31417-00	UTU096550	UTU72086A
MONUMENT BUTTE #12-12	SWNW 129S 16E				43-013-31374-00	UTU096547	UTU72086A
MONUMENT BUTTE #14-12	SWSW 129S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31410-00	UTU096550	UTU72086A
MONUMENT BUTTE #21-14	NENW 149S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31411-00		UTU72086A
MONUMENT BUTTE #21-14		DUCHESNE	01	MONUMENT BUTTE (J)	43-013-31421-00		UTU72086A
MONUMENT BUTTE FED. #23-15	NESW 119S 16E	DUCHESNE	UI	MONUMENT BUTTE (J)	43-013-31369-00	UTU096550	UTU72086A
MONUMENT BUTTE #32-11	NESW 159S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31373-00	UTU017985	UTU72086A
MONUMENT BUTTE #32-11	SWNE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31386-00		UTU72086A
MONUMENT BUTTE #41-14	SWNE 129S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31419-00		UTU72086A
MONUMENT BUTTE #41-14	NENE 149S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31408-00	UTU096550	UTU72086A
	NESE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31002-00	UTU096550	UTU72086A
MONUMENT BUTTE FED. #32-15	SWNE 159S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31368-00	UTU017985	UTU72086A
MONUMENT BUTTE FED. #34-10	SWSE 109S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31416-00	UTU017985	UTU72086A
MONUMENT BUTTE FED. #41-15	NENE 159S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31367-00	UTU017985	UTU72086A
MONUMENT BUTTE FED. #42-1	SENE 1 9S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31404-00	UTU40652	UTU72086A
MONUMENT BUTTE FED. #44-1J	SESE 1 9S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31415-00	UTU44426	UTU72086A
C&O GOV'T #4	NESW 129S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-30742-00	UTU035521A	UTU72086A
MONUMENT BUTTE FED. #1-13	NWSW 1 9S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-30702-00	UTU18399	UTU72086A
MONUMENT BUTTE FED. #1-33	NWSE 1 9S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-30735-00	UTU52013	UTU72086A
MONUMENT BUTTE #1-24	SESW 1 9S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30701-00	UTU18399	UTU72086A
WALTON FEDERAL #34-11	SWSE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31003-00	UTU096550	UTU72086A
MONUMENT STATE #11-2-9-17CD	NW NW 2 9S 17E	DUCHESNE		MONUMENT BUTTE (CD)	43-013-42685	ML 45555	



(406) 259-7860 Telephone (406) 245-1361 Fax

December 10, 1997

Lisha .
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, UT 84114-5801

Dear Lisha:

RE: Equitable Sale of Utah Properties

Effective September 30, 1997, Equitable Resources Energy Company sold all of its Utah properties to Inland Production Company.

Please feel free to contact me if you require additional information.

Sincerely,

Molly Conrad

Agent for Equitable Resources

**Energy Company** 

/mc



Crazy Mountain Oil & Gas Services P.O. Box 577 Laurel, MT 59044 (406) 628-4164 (406) 628-4165

TO: Lishar St of Wan.

FROM.

Molly Conrad

Crazy Mountain Oil & Gas Services

(406) 628-4164

Pages Attached - Including Cover Sheet 2.

NOTE: Here is the letter you requested. Callief you need anything



### United States Department of the Interior

#### **BUREAU OF LAND MANAGEMENT**

Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155 1/4 1/4 1998

IN REPLY REFER TO UT-931

January 13, 1998

Inland Production Company 475 17th Street, Suite 1500 Denver, Colorado 80202

Re:

Jonah (Green River) Unit

Duchesne County, Utah

#### Gentlemen:

On January 13, 1998, we received an indenture dated November 17, 1997, whereby Equitable Resources Energy Company resigned as Unit Operator and Inland Production Company was designated as Successor Unit Operator for the Jonah (Green River) Unit, Duchesne County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective January 13, 1998. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under Jonah (Green River) Unit Agreement.

Your statewide (Utah) oil and gas bond No. 0056 will be used to cover all operations within the Jonah (Green River) Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks Chief, Branch of Fluid Minerals

**Enclosure** 

bcc: District Manager - Vernal (w/enclosure)

Division of Oil Gas & Mining

Minerals Adjudication Group U-932

File - Jonah (Green River) Unit (w/enclosure)

MMS - Data Management Division

Agr. Sec. Chron

Fluid Chron

U-931:TAThompson:tt:1/13/98

Page No. 01/13/98

UTU72086A

UTU72086A

UTU72086A

UTU72086A

UTU72086A

UTU72086A

UTU72086A

UTU72086A

UTU72086A

## WELL STATUS REPORTS UTAH STATE OFFICE

INSPECTION ITEM

APT NO.

430133137300S1 23-15

430133138300s1 23-5

430133055800s1 23-6

430133140900s1 24-12J

430133063100s1 24-15

430133137500s1 24-5

430133136300s1 24-6

430133061300s1 31-15

430131579100s1 3

WELL (

QTQT SEC TWN RNG WELL

LEASE NAME

**OPERATOR** 

EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG

EQUITABLE RESOURCES ENERG

11101 20110		ALL RO.	MLLL	4141	JLC		M KNO	MULL	LLASE MANE	OF EXATOR
			NUMBER					STATUS	3	
** INSPECTION	ITEM UTU72086A	<b>L</b>	JONAH (G	R) SECO	NDAR	Y R	ECOVERY	UNIT		
UTU72086A	4	30131511100s1	1	NWSW	12	9s	16E	POW	UTU035521A	EQUITABLE RESOURCES ENERG
UTU72086A	4	30131578000s1	1	NWNW	5	9s	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	4	30131577900s1	1	SESE	6	98	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG

UTU72086A	430131578000s1	1 NWN	W 5	98	17E	POW	UTU020252	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430131577900s1	1 SES	E 6	98	17E	WIW	UTU020252A	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430131578900s1	1 SES	W 11	<b>9</b> S	16E	POW	UTU096547	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430131579200\$1	1 SES	E 11	<b>9</b> S	16E	POW	UTU096550	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133070200\$1	1-13 NWS	W 1	98	16E	WIW	UTU18399	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133070300\$1	1-14 SWS	W 1	98	16E	POW	UTU18399	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133064600\$1	1-23 NES	W 1	98	16E	POW	UTU18399	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133070100s1	1-24 SES	W 1	98	16E	WIW	UTU18399	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133073500s1	1-33 NWS	E 1	98	16E	WIW	UTU52013	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133073600s1	1-34 SWS	E 1	98	16E	POW	UTU52013	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133073400s1	1-43 NES	E 1	98	16E	POW	UTU52013	EQUITABLE R	ESOURCES	ENERG
UTU72086A	43013313620081	11-6 L4	6	9\$	17E	WIW	UTU020252A	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133149200\$1	11-7J NWN	<b>u</b> 7	' 9s	17E	WIW	UTU44426	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133088900\$1	12-1 NWN	E 12	<b>9</b> \$	16E	POW	UTU44426	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133141700\$1	12-11J SWN	J 11	9\$	16E	WIW	UTU096550	EQUITABLE RE	ESOURCES	ENERG
UTU72086A	430133141000\$1	12-12J SWN	J 12	<b>9</b> \$	16E	WIW	UTU096550	EQUITABLE R	ESOURCES	ENERG
UTU72086A	430133061100s1	12-5 SWN	d 5	9\$	17E	POW	UTU020252	EQUITABLE RE	ESOURCES	ENERG
UTU72086A	430133058200\$1	12-6 SWN	1 6	98	17E	POW	UTU020252A	EQUITABLE RE	ESOURCES	ENERG
UTU72086A	430133149300\$1	12-7J SWN	J 7	98	17E	POW	UTU44426	EQUITABLE RE	ESOURCES	ENERG
UTU72086A	43013157900081	13-11J NWSI	i 11	9s	16E	POW	UTU096547	EQUITABLE RE	ESOURCES	ENERG
UTU72086A	43013313700081	13-5 NWS	<b>1</b> 5	9s	17E	WIW	UTU020252	EQUITABLE RE	ESOURCES	ENERG
UTU72086A	430133091800s1	13-6 NWSI	1 6	9\$	17E	WIW	UTU020252A	EQUITABLE RE	ESOURCES	ENERG
UTU72086A	430133137400s1	14-11 SWSI	/ 11	9\$	16E	WIW	UTU096547	EQUITABLE RE	ESOURCES !	ENERG
UTU72086A	430133141100s1	14-12J SWS	<b>1</b> 12	9s	16E	WIW	UTU035521A	EQUITABLE RE	ESOURCES 1	ENERG
UTU72086A	430133138500s1	14-5 SWSI	1 5	9s	17E	POW	UTU020252	EQUITABLE RE	ESOURCES !	ENERG
UTU72086A	430131511200s1	2 NWSI	12	<b>9</b> S	16E	POW	UTU035521	EQUITABLE RE	ESOURCES	ENERG
UTU72086A	430131579300s1	2 NWNE	14	<b>9</b> \$	16E	POW	UTU096550	EQUITABLE RE	ESOURCES !	ENERG
UTU72086A	430133060300s1	2-1 L1	1	9s	16E	POW	UTU33992	EQUITABLE RE	ESOURCES I	ENERG
UTU72086A	<del>430133140600X1</del>	<del>21-12J NENI</del>	<del>/ 12</del>	<del>-9s</del>	16E	ABD	UTU096550	EQUITABLE-RE	ESOURCES I	ENERG-
UTU72086A	430133142100s1	21-14J NEN	1 14	<b>9</b> S	16E	WIW	UTU096547	EQUITABLE RE	ESOURCES F	ENERG
<del>UTU72086∧</del> -	<del>430133142200x1</del>	<del>21-15J NEN</del> I	<del>/ 15</del>	-93	16E	ABD	UTU017985	EQUITABLE RE	ESOURCES (	ENERG-
UTU72086A	430133061200s1	21-5 NENV	1 5	<b>9</b> S	17E	POW	UTU020252	EQUITABLE RE	ESOURCES F	ENERG
UTU72086A	430133058400s1	21-6 L3	6	98	17E	POW	UTU020252A	EQUITABLE RE	ESOURCES F	ENERG
UTU72086A	430131579600s2	22-12J SEN	<i>i</i> 12	98	16E	POW	UTU096550	EQUITABLE RE	ESOURCES F	ENERG
UTU72086A	430133063400s1	22-15 SEN	<i>i</i> 15	98	16E	POW	UTU017985	EQUITABLE RE	ESOURCES 1	ENERG
UTU72086A	430133138400s1	22-5 SENI	1 5	98	17E	WIW	UTU020252	EQUITABLE RE	ESOURCES (	ENERG
UTU72086A	430133091900s1	22-6 SENI	1 6	9\$	17E	WIW	UTU020252A	EQUITABLE RE	ESOURCES (	ENERG
UTU72086A	430133136900s1	23-11 NESI	1 11	<b>9</b> S	16E	WIW	UTU096550	EQUITABLE RE	ESOURCES (	ENERG

NESW 15 9s

5 9s

6 9s

12 9s

15 9s

5 98

6 9s

14 9s

NWNE 15 9S

NESW

NESW

SESW

SESW

SESW

SESW

NUNU

WIW

POW

POW

POW

POW

WIW

WIW

POW

POW

16E

17E

17E

16E

16E

17E

17E

16E

16E

UTU017985

UTU020252

UTU020252A

UTU035521A

UTU017985

UTU020252

UTU020252A

UTU096547

UTU017985

Page No. 2 01/13/98


## WELL STATUS REPORTS UTAH STATE OFFICE

INSPECTION ITEM	API NO.	WELL NUMBER	QTQT	SEC	TWN	RNG	WELL STATUS	LEASE NAME	OPERATOR
UTU72086A	430133141300s1	31-1J	L2	1	9s	16E	POW	UTU <b>33</b> 992	EQUITABLE RESOURCES ENERG
UTU72086A	430133119500s1	31-6	L2 .	6	9S	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133140500s1	31-7J	NWNE	7	9\$	17E	WIW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133138600s1	32-11	SWNE	11	98	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133141900s1	32-12J	SWNE	12	9s	16E	WIW	UTU035521	EQUITABLE RESOURCES ENERG
UTU72086A	430133136800s1	32-15	SWNE	15	9s	16E	WIW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133141400s1	32-1J	SWNE	1	<b>9</b> S	16E	POW	UTU33992	EQUITABLE RESOURCES ENERG
UTU72086A	430133055900s1	32-6	SWNE	6	9s	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133145100s1	33-11J	NWSE	11	9s	16E	120	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133063200s1	33-15	NWSE	15	<b>9</b> S	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133136100s1	33-6	NWSE	6	9s	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133141600s1	34-10J	SWSE	10	9s	16E	WIW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133100300s1	34-11	SWSE	11	9s	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133058600s1	34-6	SWSE	6	9s	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133074200s1	4	NESW	12	<b>9</b> S	16E	WIW	UTU035521A	EQUITABLE RESOURCES ENERG
UTU72086A	430131579500s1	4	SENW	11	9s	16E	POW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133148700s1	41-12J	NENE	12	9s	16E	POW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133140800s1	41-14J	NENE	14	9\$	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133136700s1	41-15	NENE	15	9s	16E	WIW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133058100s1	41-6	NENE	6	9s	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133006600s1	42-11J	SENE	11	9s	16E	POW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133148600s1	42-12J	SENE	12	9s	16E	POW	UTU035521	EQUITABLE RESOURCES ENERG
UTU72086A	430133063300\$1	42-15	SENE	15	9s	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133140400s1	42-1J	SENE	1	98	16E	WIW	UTU40652	EQUITABLE RESOURCES ENERG
UTU72086A	430133136400s1	42-6	SENE	6	9s	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133100200s1	43-11J	NESE	11	9s	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133058300s1	43-6	NESE	6	9S	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133063000\$1	44-10	SESE	10	9s	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133141500s1	44-1J	SESE	1	9S	16E	WIW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133092600s1	7-A	NENE	7	9s	17E	POW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133096100s1	7-c	NENW	7	98	17E	POW	UTU44426	EQUITABLE RESOURCES ENERG

# JONAH (GREEN RIVER) UNIT

## DUCHESNE COUNTY, UTAH

EFFECTIVE: JULY 1, 1993



16E

UNIT OUTLINE (UTU72086A)

4,221.61 ACRES

SECONDARY ALLOCATION FEDERAL 100.00% Division of Oil, Gas and Mining

#### **OPERATOR CHANGE WORKSHEET**

Attach all documentation received by the division regarding this change. Initial each listed item when completed. Write N/A if item is not applicable.

Routing:	
1-11pde	64 Ace
2-04-11	7-KAS V
3-DT87/5	8-SI
4-VLD	9-FILE
5-JP#S	

								L-5-	JR4S	
		ange of Opera signation of O	tor (well sold) perator		gnation of rator Name	_	Only	ν 		
The	ope	erator of the w	vell(s) listed below	has changed, et	ffective: _	9-30-97				
ТО	: (ṇ¢	ew operator) (address)	INLAND PRODUCT PO BOX 1446 ROOSEVELT UT	CION COMPANY 84066	FROM:	•	rator) address)	PO BOX 5 LAUREL M	77 T 59044	ES ENERGY
			Phone: <b>(801) 722</b> Account no. <b>N51</b>		•				Y MTN 0&G (406)628- no. N9890	
WE	LL	(S) attach addition	onal page if needed:		*JONAH	(GREEN	RIVER)	INIT		
Nam Nam Nam Nam Nam Nam	e: _ e: _ e: _ e: _		HED** API: 4 API: API: API: API: API: API: API: API:	[3-013-314	Entity: Entity: Entity: Entity: Entity: Entity: Entity: Entity: Entity:		S T S T S T S T S T S T S T	R - R - R - R - R - R - R - R - R - R -	Lease: Lease: Lease: Lease: Lease: Lease: Lease: Lease:	
OPI	ER <i>A</i>	TOR CHAN	GE DOCUMENT	TATION				· · · · · · ·		
Lec Lec	<ol> <li>2.</li> </ol>	form). (f:	Sundry or other legan $(2 - 12 - 10 - 97)$ Sundry or other least							
11/0	3.		(d 10-13-97)	h h	.44. 1 '64				41	
MA	3.	wells in Utal	ment of Commerch. Is the company	registered wit	h the state	ne new ce? (yes/n	operator al	If yes, show	v company	perating any file number
fec.	4.	note of BLN	— N AND FEDERA If status in commendation ordinarily taken below.	nts section of t	his form.	BLM app	proval of	Federal an	d <b>Indian</b> v	vell operator
fic he	<ul><li>5.</li><li>6.</li></ul>	Changes hav (1-14-98) Cardex file	re been entered in the χ U(C/Que lo Pro has been updated for	he Oil and Gas 1-14-98 & Licor each well lis	s Informat 1/DB452 1- ted above.	t <b>ion Syst</b> -14-98.	<b>em</b> (3270	) for each w	vell listed a	bove.
fic fec	7.		els have been upda							
	8.	Changes have to Trust Land	e been included on t ds, Sovereign Land	the monthly "Os, UGS, Tax Co	perator, Ao ommission	ddress, ai	nd Accour -14-98)	nt Changes'	' <b>memo</b> for	distribution
Jec.	9.	A folder has reference dur	been set up for the	ne <b>Operator</b> Cocessing of the	hange file	e, and a ocuments	copy of th	nis page has	s been plac	ed there for

(yes/no) If entity assignments were changed, attach copies of Form 6, Entity Action Form.  Entity   1492   Grach (Gr) Un; f'    2. Trust Lands, Sovereign Lands, Tax Commission, etc., have been notified through normal procedures of entichanges.  BOND VERIFICATION - (FEE WELLS ONLY)  1. (r649-3-1) The NEW operator of any fee lease well listed above has furnished a proper bond.  2. A copy of this form has been placed in the new and former operator's bond files.  3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's da If yes, division response was made to this request by letter dated	ENT	IT	Y REVIEW
BOND VERIFICATION - (FEE WELLS ONLY)  1. (r649-3-1) The NEW operator of any fee lease well listed above has furnished a proper bond.  2. A copy of this form has been placed in the new and former operator's bond files.  3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's data. If yes, division response was made to this request by letter dated  LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY  LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY  1. Copies of documents have been sent on at Trust Lands for change involving State leases, in order to remind that agency of their responsibility to review for proper bonding.  2. (r649-2-10) The former operator of any fee lease wells listed above has been contacted and informed by lett dated 19, of their responsibility to notify all interest owners of this change.  FILMING  1. All attachments to this form have been microfilmed. Today's date: 2 3 / 8  2. The original of this form, and the original attachments are now being filed in the Operator Change file.	Lic	1.	(r649-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made (yes(no)) If entity assignments were changed, attach copies of Form 6, Entity Action Form.
1. (r649-3-1) The NEW operator of any fee lease well listed above has furnished a proper bond.  2. A copy of this form has been placed in the new and former operator's bond files.  3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's da If yes, division response was made to this request by letter dated  LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY    A	<u>N/A</u>	2.	Trust Lands, Sovereign Lands, Tax Commission, etc., have been notified through normal procedures of enti-
2. A copy of this form has been placed in the new and former operator's bond files.  3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's da If yes, division response was made to this request by letter dated  LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY    A  1. Copies of documents have been sent on to at Trust Lands for change involving State leases, in order to remind that agency of their responsibility to review for proper bonding.  2. (r649-2-10) The former operator of any fee lease wells listed above has been contacted and informed by letter dated 19, of their responsibility to notify all interest owners of this change.  FILMING  1. All attachments to this form have been microfilmed. Today's date: 2 3 8  ELLING  1. Copies of all attachments to this form have been filed in each well file.  2. The original of this form, and the original attachments are now being filed in the Operator Change file.	BON	D V	
3. The FORMER operator has requested a release of liability from their bond (yes/no), as of today's da If yes, division response was made to this request by letter dated  LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY  1. Copies of documents have been sent on to at Trust Lands for change involving State leases, in order to remind that agency of their responsibility to review for proper bonding.  2. (r649-2-10) The former operator of any fee lease wells listed above has been contacted and informed by letter dated 19, of their responsibility to notify all interest owners of this change.  FILMING  1. All attachments to this form have been microfilmed. Today's date: 2.3 8.  FILMING  2. The original of this form, and the original attachments are now being filed in the Operator Change file.	4 <u>4</u> 14	1.	(r649-3-1) The <b>NEW</b> operator of any fee lease well listed above has furnished a proper bond.
LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY  1. Copies of documents have been sent on		2.	A copy of this form has been placed in the new and former operator's bond files.
Copies of documents have been sent on to at Trust Lands for chang involving State leases, in order to remind that agency of their responsibility to review for proper bonding.  (r649-2-10) The former operator of any fee lease wells listed above has been contacted and informed by lett dated 19, of their responsibility to notify all interest owners of this change.  FILMING  1. All attachments to this form have been microfilmed. Today's date:		3.	The <b>FORMER</b> operator has requested a release of liability from their bond (yes/no), as of today's dat If yes, division response was made to this request by letter dated
involving State leases, in order to remind that agency of their responsibility to review for proper bonding.  2. (r649-2-10) The former operator of any fee lease wells listed above has been contacted and informed by lett dated	LEAS	SE I	INTEREST OWNER NOTIFICATION OF RESPONSIBILITY
dated	VA/ V4c	1.	Copies of documents have been sent on to at Trust Lands for change involving State leases, in order to remind that agency of their responsibility to review for proper bonding.
1. All attachments to this form have been microfilmed. Today's date: 2.3.98  1. Copies of all attachments to this form have been filed in each well file.  2. The original of this form, and the original attachments are now being filed in the Operator Change file.	<u>u4</u> 2	2.	(r649-2-10) The former operator of any fee lease wells listed above has been contacted and informed by lette dated
1. Copies of all attachments to this form have been filed in each well file.  2. The original of this form, and the original attachments are now being filed in the Operator Change file.  COMMENTS	TILM	IN	G
<ol> <li>Copies of all attachments to this form have been filed in each well file.</li> <li>The original of this form, and the original attachments are now being filed in the Operator Change file.</li> </ol> COMMENTS	Ø 1	1.	All attachments to this form have been <b>microfilmed</b> . Today's date: 2.398.
2. The <b>original of this form</b> , and the <b>original attachments</b> are now being filed in the Operator Change file.	FILIN	G	
COMMENTS	1	l.	Copies of all attachments to this form have been filed in each well file.
	2	2.	The original of this form, and the original attachments are now being filed in the Operator Change file.
9801/4 B/m /S4 aprv. eff. 1-13-98.	COM	ME	NTS
	9801	14	B/m /54 aprv. eff. 1-13-98.



October 1, 2000

State of Utah
Division of Oil, Gas & Mining
Attn: Dan Jarvis
1594 West North Temple - Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Step-Rate Test

Jonah Monument Federal 11-7J-9-17

Permit #: UT04281-2642

43-013-31499

Sec. 7, 95, 17 E

Dear Dan:

Find enclosed the Step-Rate Test (SRT) results for the subject well that was conducted on September 13, 2000. Attached are the SRT graph and a copy of the test chart.

Inland is requesting that the Maximum Allowable Injection pressure be adjusted from 2200 psi to 2025 psi due to the results of the test. If you have any questions or require further information you may contact me at (435) 646-3721.

Sincerely,

Michael Guinn District Engineer

cc:

Roosevelt files Denver files Approved by the Utah Division of Oil, Gas and Mining

D.

COPY SENT TO OPERATOR
Date: 10-12-00
Initials:


011 01 1000

DIVISION OF OIL, GAS AND MINING

# MONUMENT FED. 11-7J-9-17 JONAH UNIT


Step Pate Test

September 13, 2000



1435	psi
2250	psi
2025	psi
4784	
0.858	psi/ft
	2250 2025 4784

Step	Rate(bpd)	Pressure(psi)
1	15	1510
2	30	1610
3	60	1745
4	120	1940
5	180	2085
6	240	2200
7	300	2300



STATE OF UTAH

DIVISION OF OIL,				
	GAS, AND MINING		5. LEASE DESIGNATION AND SERIA UTU-44426	L NO.
I. SUNDRY NOTICES	AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBAL	NAME
(Do not use this form for proposals to dr	rill or to deepen or plug back to ERMIT" for such proposals.)	N/A		
			7. UNIT AGREEMENT NAME	
OIL GAS WELL OTHER X Inject	ction		JONAH	
2. NAME OF OPERATOR INLAND PRODUCTION	COMPANY			MENT FEDERAL 11-7J-9-17
3. ADDRESS OF OPERATOR Rt. 3 Box 3630, Myton Uta 435-646-3721	h 84052		9. WELL NO. BALCRON MONU	MENT FEDERAL 11-7J-9-17
<ol> <li>LOCATION OF WELL (Report location clearly See also space 17 below.)</li> </ol>	and in accordance with any Sta	te requirements.*	10. FIELD AND POOL, OR WILDCAT	
At surface	. D17F		MONUMENT BUT	TE
NW/NW Section 7, T09S 681 FNL 447 FWL	KI/E		11. SEC., T., R., M., OR BLK. AND	
			NW/NW Section 7,	T09S R17E
14 API NUMBER 43-013-31492	ATIONS (Show whether DF, F	T, GR, etc.)	12. COUNTY OR PARISH DUCHESNE	13. STATE UT
16. Check Appropriate B NOTICE OF INTENTION TO:	Box To Indicate Nature of I	Notice, Report, or Other Data	QUENT REPORT OF:	
TEST WATER SHUT-OFF PULL OR ALTER O	CASING	WATER SHUT-OFF	REPAIRING WELL	
FRACTURE TREAT MULTIPLE COMP	PLETE	FRACTURE TREATMENT	ALTERING CASING	
SHOOT OR ACIDIZE ABANDON*		SHOOTING OR ACIDIZING	ABANDONMENT*	
REPAIR WELL		(OTHER)	X Recompletion	
(OTHER)			sults of multiple completion on Well ecompletion Report and Log form.)	
17 DESCRIBE PROPOSED OR COMPLETED OP proposed work. If well is directionally drilled.  The subject well was recomp perforated, the GB-6 4086'-4 On 06/27/01 Mr. Al Craver w conduct a MIT on the casing. w/ no pressure loss. No gove waiting on permission to injection.	give subsurface locations and obleted in the Green 101' w/ 4 jspf for a w/ EPA and Mr. Dec. On 06/27/01 the ernmental agencies	neasured and true vertical depths for al River Formation. One: a total of 60 shots. ennis Ingram w/ State D casing was pressured to	new Green River interv OGM was contacted of 1150 psi and charted f	al was The intent to for 30 minutes
18 I hereby certify that the foregoing is true and corn SIGNED Krisha Russell	reet	Production Clerk	DATE	6/27/01
SIGNED Kusha Rus	nn. 11	Production Clerk	DATE	6/27/01
SIGNED Krisha Russell	nn. 11	Production Clerk	DATE	6/27/01
Krisha Russell	nn. 11	Production Clerk	DATE DATE	6/27/01

## Mechanical Integrity Test

# Cusing of Annulus Pressure Wechanical Integrity Test U.S. Environmental Protection Agency Underground Injection Control Program, UIC Direct Implementation Program 8P-W-GW 999 18 Street, Suite 500 Denver, CO 80202-2466

EPA Witness: None	
Test conducted by: Rose Shuck	Date: 6 1 271 0/
Others present: None	
Weil Name: Menument Federal 11-77	29-17 - (2)
II FIEID JONAA	James, AC IA UL
Location: NW/NW Sec: 7 T 9 N/	S R 17 E)W County: Duchesne State: UT
Operator: In land Production	State: UT
II T and A ATTY	um Allowable Pressure: PSIG
	an Anowable Pressure:PSIG
Is this a regularly scheduled test? [ ] You	≈s [X] No
Initial test for permit? [ ] Ye	≍ [X] No
Test after well rework? [X] Ye	≈ [ ] No
Well injecting during test? [ ] Ye	es [X] No If Yes, rate:bpd
Pre-test casing/tubing annulus pressure:	They 600 castry psig

MIT DATA TABLE	Test #1	Test #2	Tool 42
TUBING	PRESSURE	1000	Test #3
Initial Pressure	1 = 2		
Fed of test pressure	6-5	PSIS	psig
CASING / TUBING	ANNULUS	PRESSURE psig	nsig
0 minutes	1050 psig		·
5 minutes	11 =		psig
10 minutes			psig
15 minutes	1150 psig	psig	psig
20 minutes	1150 nsig	psig	psig
25 minutes	//50 psig	psig	psig
	1150 psig	psig	psig
30 minutes	1150 psig	psig	
minutes	psig		psig
minutes	ne'n	nsig	DSig
RESULT	Pass []Fail	Pass [ ]Fail	nsig

Does the annulus pressure build back up after the

## 


itional comments for	11-75-9-17	arae a 7	2.	411. 11	
Inland on 6-	25-01 Shot	Tana	-Neetlen	00011.	<del></del>
Conducted This	MIT	Marie Ministra	TI PEVYS O	well on	id .
waiting on p	Joseph Jan	Lasing.	The We,	11 18 Shn.	t-in
The state of the s		To re_	Niject.		·
	<u> </u>	·	<del></del>		
<del></del>			<u> </u>	-	
				<del></del>	<u> </u>
· .		<del></del>			
				· · · · · · · · · · · · · · · · · · ·	<del></del>
· · ·					
	<del></del>		·		
	·				
					,
· · · · · · · · · · · · · · · · · · ·					
					<del></del>
		,			
		•		-	
			·		•
ICE USE ONLY - CO	MPHLANCE FOI	LOWUP St	aff	Date	
You agree that t	he well pass	sed/failed	the test?	[]Yes	[1]
TISECT OF CAMPERS				~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	
inge in operating			ate) [ ] Ye	8	_ [] 1
sible violation	identified?		[ ] No		
If YES - Followur		[ ] Yes			[]1

This is the back side of two sides.

[ ] 2nd Data Entry [ ] Hard Copy Filing

[ ] Compliance Staff

[ ] Data Entry





## **United States Department of the Interior**



# BUREAU OF LAND MANAGEMENT Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155 http://www.blm.gov

IN REPLY REFER TO: 3106 (UT-924)

September 16, 2004

Memorandum

To:

Vernal Field Office

From:

Acting Chief, Branch of Fluid Minerals

Subject:

Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Milas Llouters

Michael Coulthard Acting Chief, Branch of Fluid Minerals

#### Enclosure

1. State of Texas Certificate of Registration

cc:

MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225 State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114

Teresa Thompson Joe Incardine

Connie Seare

間合 工事





### Office of the Secretary of State


The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:


Newfield Production Company Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.





Secretary of State

# ARTICLES OF AMENDMENT TO THE ARTICLES OF INCORPORATION OF INLAND PRODUCTION COMPANY

In the Office of the Secretary of State of Texas

SEP 02 2004

Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

#### ARTICLE 1 - Name

The name of the corporation is Inland Production Company.

#### ARTICLE 2 - Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE - The name of the corporation is Newfield Production Company."

ARTICLE 3 - Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

Susan G. Riggs, Treasurer

					* · · ·
UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	630730	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357 [.]	76189X
05843	33992	65207	74398	77359	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553·	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013·	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	•
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	•
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833 [,]	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	•
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	:
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		•
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		•
13905	52018	73087	76241		
15392	58546	73807	76560	•	
			•		

## STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

**UIC FORM 5** 

	TRANSFER OF A	UTHORITY TO	INJECT
Vell Name an See Attach	d Number		API Number
ocation of We	oll		Floid or Unit Name
Footage :		County:	See Attached List
QQ, Section	n, Township, Range:	• .	Lease Designation and Number
		State: UTAH	
EFFECTIVE	DATE OF TRANSFER: 9/1/2004		
URRENT O	PERATOR		
Company:	Inland Production Company	Name:	Brian Harris
Address:	1401 17th Street Suite 1000	Signature:	Bro Jan
	city Denver state Co zip 80202	Title:	Engineering Tech.
Phone:	(303) 893-0102	Date:	9/15/2004
Comments	<b>;</b>		
EW OPERAT	TOR  Newfield Production Company		
Company: Address:	1401 17th Street Suite 1000	Name;	Brian Harris
	City Denver state Co zip 80202	Signature:	Tima from
Phone:	State 40 Zip 50202	Title:	Engineering Tech. 9/15/2004
Comments:		Date:	9/10/2004
s space for Sta Transfer app Comm	proved by: Sales Services Manager Title: Ferli Services Manager ents: Note: Indean Country a	Approval Da	ne; 9-10-04
	we surean courty of	rus wu	require EtH approval.
			DEOCU

(5/2000)

RECEIVED SEP 2 0 2004

#### Division of Oil, Gas and Mining

#### **OPERATOR CHANGE WORKSHEET**

ROUTING 1. GLH 2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

#### X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:	9/1/2004
FROM: (Old Operator):	TO: ( New Operator):
N5160-Inland Production Company	N2695-Newfield Production Company
Route 3 Box 3630	Route 3 Box 3630
Myton, UT 84052	Myton, UT 84052
Phone: 1-(435) 646-3721	Phone: 1-(435) 646-3721

	CA No.			Unit:		IONAH (G	REEN RIV	ER)
WELL(S)								
NAME	SEC 7	TWN	RNG	API NO	ENTITY	LEASE	WELL	WELL
					NO	TYPE	TYPE	STATUS
MONUMENT FED 31-1J	01 0	)90S 1	60E	4301331413	11492	Federal	OW	P
MONUMENT FED 32-1J	01 0	90S 1	60E	4301331414	11492	Federal	OW	P
MON FED 44-1J	01 0	90S 1	60E	4301331415	11492	Federal	WI	A
MON FED 34-10J	10 0	90S 1	60E	4301331416	11492	Federal	WI	A
MON FED 12-11J	11 0	90S 1	60E	4301331417	11492	Federal	WI	A
MONUMENT FED 33-11J	11 0	90S 1	60E	4301331451	11492	Federal	OW	P
MONUMENT FED 24-12J	12 0	90S 1	60E	4301331409	11492	Federal	OW	P
MON FED 12-12J	12 0	90S 1	60E	4301331410	11492	Federal	WI	A
MON FED 14-12J	12 0	90S 1	60E	4301331411	11492	Federal	WI	A
MON FED 32-12J	12 0	90S 1	60E	4301331419	11492	Federal	WI	A
MON FED 42-12J	12 0	90S 1	60E	4301331486	11492	Federal	WI	A
MONUMENT FED 41-12J	12 0	90S 1	.60E	4301331487	11492	Federal	OW	P
MON FED 41-14J	14 0	90S 1	60E	4301331408	11492	Federal	WI	A
MON FED 21-14J	14 0	90S 1	60E	4301331421	11492	Federal	WI	Α
MONUMENT FED 21-15J	15 0	90S 1	60E	4301331422	11492	Federal	NA	PA
MON FED 31-7J	07 0	90S 1	70E	4301331405	11492	Federal	WI	Α
MON FED 11-7J	07 0	90S 1	70E	4301331492	11492	Federal	WI	A
MONUMENT FED 12-7J	07 0	90S 1	70E	4301331493	11492	Federal	OW	P
JONAH 6-7	07 0	90S 1	70E	4301331987	11492	Federal	WI	A
JONAH 7-7	07 0	90S 1	70E	4301331988	11492	Federal	OW	P

#### **OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

(R649-8-10) Sundry or legal documentation was received from the FORMER operator on: 9/15/2004
 (R649-8-10) Sundry or legal documentation was received from the NEW operator on: 9/15/2004

3. The new company was checked on the Department of Commerce, Division of Corporations Database on: 2/23/2005

4. Is the new operator registered in the State of Utah:

YES Business Nu

YES Business Number: 755627-0143

5. If NO, the operator was contacted contacted on:

	IN PLACE		
o. Inspections of LA PA state/fee well sites complete on:	waived		
Federal and Indian Lease Wells: The BLM and o	r the BIA has approve	d the merger,	name change,
or operator change for all wells listed on Federal or Indian	eases on: B	BLM	BIA
. Federal and Indian Units:			
The BLM or BIA has approved the successor of unit oper	ator for wells listed on:	<u>n/a</u>	
. Federal and Indian Communization Agreeme	nts ("CA"):	· · · · · · · · · · · · · · · · · · ·	
The BLM or BIA has approved the operator for all wells		na/	<del></del>
0. Underground Injection Control ("UIC")	he Division has approved	UIC Form 5, Tı	ansfer of Authority to
Inject, for the enhanced/secondary recovery unit/project for	r the water disposal well(s)	) listed on:	2/23/2005
			_
ATA ENTRY:			
Changes entered in the Oil and Gas Database on:	2/28/2005		
Changes have been entered on the Monthly Operator Cha	inge Spread Sheet on:	2/28/20	05
Bond information entered in RBDMS on:	2/28/2005		
Fee/State wells attached to bond in RBDMS on:	2/28/2005		
Injection Projects to new operator in RBDMS on:	2/28/2005		
Receipt of Acceptance of Drilling Procedures for APD/New	v on: wa	aived	
EDERAL WELL(S) BOND VERIFICATION:			
Federal well(s) covered by Bond Number:	UT_0056		
NDIAN WELL(S) BOND VERIFICATION:			
Indian well(s) covered by Bond Number:	61BSBDH2912		
EEE & STATE WELL(S) BOND VERIFICATIO	N:		
. (R649-3-1) The NEW operator of any fee well(s) listed cov		61BSBDH	<b>I</b> 2919
		( 4	
The FORMER operator has requested a release of liability to The Division sent response by letter on:	from their bond on: 1/a	<u>n/a*</u>	
The Division sent response by received.			
EASE INTEREST OWNER NOTIFICATION:			
. (R649-2-10) The <b>FORMER</b> operator of the fee wells has be of their responsibility to notify all interest owners of this cha		l by a letter fron n∕a	n the Division
of their responsionity to notify all interest owners of this circ		1D G	····
OMMENTS:			1 2/22/05
Bond rider changed operator name from Inland Production Co	mpany to Newfield Produc	ction Company	- received 2/23/05

#### STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5	LEASE DESIGNATION	AND	SERIAL	NUMBER:
ı	ITU44426			

	UTU44426					
SUNDRY	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:					
o not use this form for proposals to drill net to drill horizontal late	7. UNIT OF CA AGREEMENT NAME: JONAH UNIT					
1. TYPE OF WELL: OIL WELL						
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMP	ANY		9. API NUMBER: 4301331492			
3. ADDRESS OF OPERATOR:		PHONE NUMBER	10. FIELD AND POOL, OR WILDCAT:			
Route 3 Box 3630 CIT	y Myton STATE UT	ZIP 84052 435.646.3721	Monument Butte			
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 0681 FNL	0447 FWL		COUNTY: Duchesne			
OTR/OTR, SECTION, TOWNSHIP, RANGE,	MERIDIAN: NW/NW, 7, T9S, R17E		STATE: Utah			
II. CHECK APPROF		E NATURE OF NOTICE, REPO	RT, OR OTHER DATA			
	TYP	E OF ACTION <u>SubDate</u>				
TYPE OF SUBMISSION		TYPE OF ACTION				
	ACIDIZE	DEEPEN	REPERFORATE CURRENT FORMATION			
NOTICE OF INTENT (Submit in Duplicate)	ALTER CASING	FRACTURE TREAT	SIDETRACK TO REPAIR WELL			
(Subnut in Dupitcate)	I <b>≒</b>	NEW CONSTRUCTION	TEMPORARITLY ABANDON			
Approximate date work will	CASING REPAIR	=	=			
	CHANGE TO PREVIOUS PLANS	OPERATOR CHANGE	TUBING REPAIR			
	CHANGE TUBING	PLUG AND ABANDON	VENT OR FLAIR			
X SUBSEQUENT REPORT	CHANGE WELL NAME	PLUG BACK	WATER DISPOSAL			
(Submit Original Form Only)	CHANGE WELL STATUS	PRODUCTION (START/STOP)	WATER SHUT-OFF			
Date of Work Completion:	COMMINGLE PRODUCING FORMATIONS	RECLAMATION OF WELL SITE	X OTHER: - 5 Year MIT			
06/20/2006	l <u>=</u>	<b>=</b>	Z TIMES TOWNS			
	CONVERT WELL TYPE	RECOMPLETE - DIFFERENT FORMATION				
12. DESCRIBE PROPOSED OR CO	MPLETED OPERATIONS. Clearly show a	all pertinent details including dates, depths, ve	olumes, etc.			
that time to perform the test or loss. The well was injecting du	6/2/06. On 6/2/06 the csg was pre	the 5-year MIT on the above listed v ssured up to 1140 psig and charted s 2000 psig during the test. There was 31492.	for 30 minutes with no pressure			
		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONL				
NAME (PLEASE PRINT) Callie Duncan		TITLE_Production Clerk				
(MADOO. T.	uncan	DATE 06/21/2006				
SIGNATURE ( 1/3/2/ YYW / /	1	DATE				

(This space for State use only)

RECEIVED

JUN 2 3 2006

## Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test U.S. Environmental Protection Agency Underground Injection Control Program


999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness:			Date: _	6/20	12006	
EPA Witness: Test conducted by: Others present:	Horrock	3			<del></del>	
Others present:	<del></del>	•				
Well Name: Monument	Federal 1	1-71-9-17	Type: ER SW	D Statu	s: AC TA UC	
Field: Track worth						
Location: NW NW Sec	: <u>    7                                </u>	_N <i>I</i> SS R <u>_//</u> 2	<b> ∰</b> /W County	Duckesn	eState: <u>U.f.</u>	1
Operator: New Fold e	x plocation_			0.0	PSIG	1
Last MIT:/	_/Ma	ximum Allowa	able Pressure:	2025	1910	
Is this a regularly scheduled	d test?	Yes [	] No			
Initial test for permit?	[	] Yes [X	] No			
Test after well rework?		] Yes [X	] No		10 11	
Well injecting during test?	[X	Yes [	] No If Yes	s, rate:	bpd	
D	ic processo.	Ø	· 1	nsia		
Pre-test casing/tubing annulu	is pressure			P3-5		
MIT DATA TABLE	Test #1		Test #2		Test #3	
TUBING	PRESSURI	5				
Initial Pressure	2000	psig		psig		psig
End of test pressure	2000	psig		psig		psig
CASING / TUBING	ANNULUS		PRESSURE		and the second s	
0 minutes	1140	psig		psig		psig
5 minutes	1140	psig		psig		psig
10 minutes	1140	psig		psig		psig
15 minutes	1140	psig		psig		psig
20 minutes	1140	psig		psig		psig
25 minutes	1140	psig		psig		psig
30 minutes	1140	psig		psig		psig
minutes	1.75	psig		psig		psig
minutes		psig		psig		psig
RESULT	Pass	[ ]Fail	[ ] Pass	[ ]Fail	Pass [	]Fail

#### [X] No Does the annulus pressure build back up after the test? [ ] Yes MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness	



#### STATE OF UTAH

	5. LEASE DESIGNATION AND SERIAL NUMBER:				
SUNDRY	NOTICES AND REPO	RTS ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
	Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.				
1. TYPE OF WELL: OIL WELL	GAS WELL OTHER			8. WELL NAME and NUMBER:	
	GAS WELL GIHER			MON 11-7J-9-17	
2. NAME OF OPERATOR:	DANIV			4301331492	
NEWFIELD PRODUCTION COM  3. ADDRESS OF OPERATOR:	PANI	1-11-1	PHONE NUMBER	10. FIELD AND POOL, OR WILDCAT:	
Route 3 Box 3630 CIT	Y Myton STATE UT	ZIP 84052	435.646.3721	MONUMENT BUTTE	
4 LOCATION OF WELL:  FOOTAGES AT SURFACE: 681 FNL 447 FWL  COUNTY: DUCHESNE					
OTR/OTR. SECTION. TOWNSHIP, RANGE.	MERIDIAN: NWNW, 7, T9S, R17E			STATE: UT	
CHECK APPROP	PRIATE BOXES TO INDICATE			ORT, OR OTHER DATA	
TYPE OF SUBMISSION		TY	PE OF ACTION		
NOTIOE OF INTENT	ACIDIZE	DEEPEN		REPERFORATE CURRENT FORMATION	
NOTICE OF INTENT (Submit in Duplicate)	☐ ALTER CASING	FRACTURE 1	REAT	SIDETRACK TO REPAIR WELL	
Approximate date work will	CASING REPAIR	☐ NEW CONST	RUCTION	TEMPORARITLY ABANDON	
	CHANGE TO PREVIOUS PLANS	OPERATOR (	CHANGE	TUBING REPAIR	
	CHANGE TUBING	PLUG AND	ABANDON	■ VENT OR FLAIR	
X SUBSEQUENT REPORT	CHANGE WELL NAME	PLUGBACK		WATER DISPOSAL	
(Submit Original Form Only)	CHANGE WELL STATUS	PRODUCTIO	N (START/STOP)	WATER SHUT-OFF	
Date of Work Completion:	COMMINGLE PRODUCING FORMATIONS		ION OF WELL SITE	OTHER: -	
09/26/2006	CONVERT WELL TYPE	=	E - DIFFERENT FORMATION		
				violumes etc	
	MPLETED OPERATIONS. Clearly show a				
The subject well was recor	npleted in the Green River Formation	11 011 9/20/00.	The packer is now s	et at 4010.	
to perform the test on 10/1 loss. The well was not inje	with the EPA was contacted concern 0/06. On 10/10/06 the csg was prescring during the test. The tbg pressor witness the test. EPA# UT20642-04	ssured up to 1° ure was 1000	100 psig and charted psig during the test.	ell. Permission was given at that time I for 30 minutes with no pressure There was not an EPA	
		F	Accepted by Utah Division Oil, Gas and N	Mining	
NAME (PLEASE PRINT) Callie Duncan			TITLE_ Production Clerk		
SIGNATURE (Alla)	incon		DATE 10/24/2006		

(This space for State use only)

**RECEIVED** 

OCT 2 5 2006

# Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test U.S. Environmental Protection Agency


U.S. Environmental Protection Agency Underground Injection Control Program 999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness:  Test conducted by:	·fley J. k	Care	Date:/	0110	100	<u> </u>	
Well Name: MONUMED  Field: MONUMENT  Location: Null Sec  Operator: New Fice  Last MIT: /	<i>BUHE</i> :_7 T <u>9</u> N	N /&) R	7_(E)/ W County:_			TA UC State: <u>[/]</u> PSIG	
Is this a regularly scheduled test?  [ ] Yes [ ] No Initial test for permit?  [ ] Yes [ ] No Test after well rework?  [ ] Yes [ ] No Well injecting during test?  [ ] Yes [ ] No If Yes, rate:							
MIT DATA TABLE	Test #1	3.3.3	Test #2			Test #3	
TUBING	PRESSURE		i	•			nsia
Initial Pressure	1000	psig		psig			psig
End of test pressure	1000	psig		psig			psig
CASING / TUBING	ANNULUS		PRESSURE				
0 minutes	1100	psig		psig			psig
5 minutes	1100	psig		psig			psig
10 minutes	1100	psig		psig			psig
15 minutes	1100	psig		psig			psig
20 minutes	1100	psig		psig			psig
25 minutes	1100	psig		psig			psig
30 minutes	1100	psig		psig			psig
minutes		psig		psig			psig
minutes		psig		psig			psig
RESULT	[.] Pass	[ ]Fail	[ ] Pass	[ ]Fail		Pass	]Fail

Does the annulus pressure build back up after the test? [ ] Yes [ > No MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness:	



	5. LEASE DESIGNATION AND SERIAL NUMBER: USA UTU-44426 6. IF INDIAN, ALLOTTEE OR TRIBE NAME:						
SUNDR							
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.  1. TYPE OF WELL:  OIL WELL GAS WELL OTHER				7. UNIT of CA AGREEMENT NAME: GMBU 8. WELL NAME and NUMBER: MON FED 11-7J			
						2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	<ol> <li>API NUMBER:</li> <li>4301331492</li> </ol>
3. ADDRESS OF OPERATOR: PHONE NUMBER				10. FIELD AND POOL, OR WILDCAT:			
Route 3 Box 3630  LOCATION OF WELL:	CITY Myton STATE UT	ZIP 84052	435.646.3721	GREATER MB UNIT			
FOOTAGES AT SURFACE: 681 FNL	447 FWL			COUNTY: DUCHESNE			
OTR/OTR, SECTION, TOWNSHIP, RANG	E. MERIDIAN: NWNW, 7, T9S, R17E			STATE: UT			
11. CHECK APPRO	OPRIATE BOXES TO INDICATE	E NATURE (	OF NOTICE, REP	ORT, OR OTHER DATA			
TYPE OF SUBMISSION		TY	PE OF ACTION				
	ACIDIZE DEEPEN			REPERFORATE CURRENT FORMATION			
NOTICE OF INTENT (Submit in Duplicate)	ALTER CASING	FRACTURE	TRÉAT	SIDETRACK TO REPAIR WELL			
Approximate date work will	CASING REPAIR	NEW CONST	RUCTION	TEMPORARITLY ABANDON			
Approximate date work will	CHANGE TO PREVIOUS PLANS	OPERATOR		TUBING REPAIR			
	CHANGE TUBING	PLUG AND		VENT OR FLAIR			
·	<del> </del>	_		_			
SUBSEQUENT REPORT (Submit Original Form Only)	CHANGE WELL NAME	PLUG BACK		WATER DISPOSAL			
Date of Work Completion:	CHANGE WELL STATUS	PRODUCTION (START/STOP)		WATER SHUT-OFF			
-	COMMINGLE PRODUCING FORMATIONS	RECLAMATION OF WELL SITE		OTHER: - Five Year MIT			
05/16/2011	CONVERT WELL TYPE	RECOMPLE	i				
On 05/02/2011 Nathan V casing was pressured up	COMPLETED OPERATIONS. Clearly show a fiser with the EPA was contacted cond to 1270 psig and charted for 30 minuted 4 psig during the test. There was not a API# 43-013-31492	cerning the 5 y	rear MIT on the abovessure loss. The we	re listed well. On 05/16/2011 the ll was injecting during the test. The			
				ed by the			
	Utah Division of						
			Oil, Gas a	nd Mining			
			FOR RECO	ORD ONLY			
	·			·			
AME (PLEASE PRINT) Lucy Chavez	-Naupoto		TITLE Water Services T	echnician			

(This space for State use only)

**RECEIVED** 

MAY 2 5 2011

# Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test U.S. Environmental Protection Agency


U.S. Environmental Protection Agency Underground Injection Control Program 999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness:			Date: <u>5</u>	116	12011			
Test conducted by: Lade Pass								
Others present: James	Bird, A	IFrado Rio	6		<del>, , , , , , , , , , , , , , , , , , , </del>			
						<del></del>		
Well Name: Montount Federal Type: ER SWD Status: AC TA UC								
Field: Mennount Butte				<b>~</b> .	~ 111			
Location: 11-7-9-17 Sec: 7 T 9 N/S R E/W County: Duchasne State: Ut.								
Operator: Newtield								
Last MIT: / / Maximum Allowable Pressure: 2025 PSIG								
Is this a regularly schedule	d test?	➤ Yes [	l No					
Initial test for permit?		Yes	-					
Test after well rework?		Yes 🔀	—					
Well injecting during test?		>√ Yes [	No If Yes, ra	ite: <u>5</u>	bpdb			
		_						
Pre-test casing/tubing annulu	is pressure:	<u>O</u>	psig					
	[				- "	<del></del>		
MIT DATA TABLE	Test #1		Test #2		Test #3			
TUBING	PRESSUL	<u>RE</u>						
Initial Pressure	1804	psig		psig		psig		
End of test pressure	1864	psig		psig		psig		
CASING / TUBING	ANNULU	S	PRESSURE					
0 minutes	1270	psig		psig		psig		
5 minutes	1270	psig		psig		psig		
10 minutes	1270	psig		psig		psig		
15 minutes	1270	psig		psig		psig		
20 minutes	1270	psig		psig		psig		
25 minutes	1270	psig	·	psig		psig		
30 minutes	1270	psig	·	psig		psig		
minutes		psig		psig		psig		
minutes		psig		psig		psig		
RESULT	M Pass	[ ]Fail	Pass [	]Fail	Pass [	Fail		

### MECHANICAL INTEGRITY PRESSURE TEST


Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness:_	Wash	David	`	
•				 



#### Monument Federal 11-7J-9-17

INJECTION DIAGRAM Wellbore Diagram



Sundry Number: 71148 API Well Number: 43013314920000

	FORM 9				
1	5.LEASE DESIGNATION AND SERIAL NUMBER: UTU-44426				
SUNDF	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:				
Do not use this form for procurrent bottom-hole depth, FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)				
1. TYPE OF WELL Water Injection Well	8. WELL NAME and NUMBER: MON FED 11-7J				
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	<b>9. API NUMBER:</b> 43013314920000				
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT		HONE NUMBER: Ext	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE		
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0681 FNL 0447 FWL			COUNTY: DUCHESNE		
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NWNW Section:	an: S	STATE: UTAH			
11. CHEC	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	RT, OR OTHER DATA		
TYPE OF SUBMISSION		TYPE OF ACTION			
	ACIDIZE	ALTER CASING	CASING REPAIR		
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME		
Approximate date work will start.	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE		
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION		
4/13/2016	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK		
		1			
SPUD REPORT Date of Spud:	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION		
	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	LI TEMPORARY ABANDON		
DRILLING REPORT	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL		
Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION		
	☐ WILDCAT WELL DETERMINATION ✓	OTHER	OTHER: 5 YR MIT		
5 YR MIT perform casing was pressur no pressure loss. pressure was 1	COMPLETED OPERATIONS. Clearly show all med on the above listed well. ed up to 1163 psig and charted the well was not injecting dure 532 psig during the test. There wailable to witness the test. EF	On 04/13/2016 the ed for 30 minutes with ing the test. The tbg was not an EPA	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 18, 2016		
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician			
SIGNATURE N/A		<b>DATE</b> 4/18/2016			
		■ .,			

Sundry Number: 71148 API Well Number: 43013314920000

## Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test U.S. Environmental Protection Agency Underground Injection Control Program 999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: Date: 4 113 116  Test conducted by: PETE MONTAGUE  Others present:							
Well Name: BALCRON MONUMENT FEDERAL Type: ER SWD Status: AC TA UC Field GREATER MONUMENT BUTTE Location: // Sec: 7 J T 9 N (S) R / 7 (E) W County: DICHESNE State: 14 Operator: Newfield Exp Last MIT: / Maximum Allowable Pressure: / 759 PSIG							
Is this a regularly scheduled test?    Yes   No							
MIT DATA TABLE	Test #1		Test #2		Tes	st #3	
TUBING	PRESSURE	-					
Initial Pressure	1532	psig	#	psig		psig	
End of test pressure	1532	psig		psig	*	psig	
CASING / TUBING ANNULUS PRESSURE							
0 minutes	1163	psig		psig		psig	
5 minutes	1163	psig	10	psig		psig	
10 minutes	1163	psig		psig	,	psig	
15 minutes	1164	psig		psig		psig	
20 minutes	1143	psig		psig		psig	
25 minutes	1163	psig		psig		psig	
30 minutes	1163	psig		psig		psig	
minutes		psig		psig		psig	
minutes		psig		psig		psig	
RESULT	[ ] Pass	Fail	Pass	[ ]Fail	Pass	Fail	
Does the annulus pressure build back up after the test? [] Yes No MECHANICAL INTEGRITY PRESSURE TEST  Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:  Signature of Witness:							
Signature of witness:							

Sundry Number: 71148 API Well Number: 43013314920000

P23448 = 1800 1900 7000 9:5: P23448 Legend 9:45:00 AM 4/13/2016 -06:00 9:36:40 AM 4/13/2016 -06:00 4/13/2016 9:16:04 AM 9:28:20 AM 4/13/2016 -06:00 9:20:00 AM 4/13/2016 -06:00

Balcron Monument Federal 11-7J-9-17, 5-Year MIT, (4-13-16).